

*Changes to Specifications and Drawings*  
*NNJ07182243R*

## Request for Proposal (RFP) NNJ07182243R

*Task Order, "Building 265 Addition"  
Changes to Drawings and Specifications*

### Changes to Drawings (Write changes on all drawings):

1. **D-265-1** - Note at the South side of the building at scupper add to the note. "Add short downspout with 90 degree turn onto new roof".
2. **E-265-2** - Add the following to the end of key note 13: "Core drill through a 24" concrete block wall at 8 ft. North of the existing South wall of building and a CMU wall 40 ft North of the existing South wall also adding two 6 inch sleeves. Metal sleeves are not necessary in solid concrete walls, only CMU"
3. **E-265-5** - Add to key note 11: "...from panel PB overhead to disconnect at panel PA core drilling through concrete beams above ceiling in two locations in the existing building".
4. **E-265-5** - Detail 1 - Add to the end of the note called out at the junction gang box: "All gang boxes to have a blank brushed metal cover – security system not to be installed until later".
5. **E-265-5** - At the top center of the page change "EXISTING POWER POLE C7 & XFmR" to read "EXISTING POWER POLE C7 WITH NEW GOVERNMENT FURNISHED 100 KVA XFMR'S INSTALLED BY CONTRACTOR – REMOVED EXISTING TRANSFORMERS TO REMAIN GOVERNMENT PROPERTY".
6. **E-265-2** - At key note 2 symbol at top center of drawing, add a note that says: "New ground connection can tie in just west of drive way, rather than in driveway as shown".
7. **S-265-3** - Add the following to Note 30: This note applies to all elements of the facility exposed to wind loads.
8. **A-265-1** - Add note as follows and place arrow with note number encircled at the 5 locations indicated: "12. Install 5 recessed fire extinguisher cabinets with extinguishers at the following locations: 1 – inside the west door, on the west wall just south of the door frame; 2 – inside the east door at the same location; 3 & 4 – on the south wall of mechanical room; 5 – in the vestibule between door between door 111 and 113. Coordinate exact location with NASA project manager."
9. **A-265-7** - Above Detail 10 and above windows A & B add the following note: "All window Type A and Type B require louver blinds".
10. **S-265-3** (Sheet 21) - Delete the forth sentence in Note 13 that starts with "A unit price".
11. **A-265-8** - Detail 04 for CPT-1: Under FINISH/MANUFACTURER delete DESIGN WEAVE -TRAPANI II and replace with DESIGN WEAVE - PLUG IN Z6388; Under COLOR delete #00456 BLUE HORIZON and replace with CIRCUIT 00449. For clarification, the new finish/manufacturer and color relates to electrical components. These are not typical carpet descriptions, but are the correct product names chosen by the manufacturer for these respective products.

**Changes to Specifications** *(Write changes in all specifications documents):*

1. **01220** - In part 1.4 delete remainder of sentence beginning with “within 180 calendar days” and replace with “as stated in the contract”.
2. **13121** - In part 2.5 in the seventh paragraph in the first sentence that reads in part “...24-inch coverage; ...” change to read “...16 or 24 – inch coverage; ...”
3. **08710** - Delete pages 9, 10 and 11 – Hardware schedule. Use the hardware schedule on Drawing A-265-7.
4. **02825** – Delete this section, annotate index accordingly.
5. **02985** – Delete this section, annotate index accordingly.