

1  
2  
COMPOSITE DEMOLITION PLAN LEVEL 2  
1/16" = 1'-0"  
0 8 16 32 FT

**DEMOLITION LEGEND**

- EXISTING CONSTRUCTION PARTITION, DOOR, GLAZING AND FRAMES TO REMAIN
- REMOVE EXISTING PARTITION, DOOR, GLAZING AND FRAMES
- SAW-CUT SLAB FOR UNDER FLOOR PLUMBING WORK IN SCOPE


**GENERAL NOTES**

- A REMOVE ALL CEILING ELEMENTS, INCLUDING LAY IN ACOUSTICAL TILES, GRID, METAL PANELS AND ASSOCIATED SUPPORTS, LIGHT FIXTURES, AIR DEVICES, PA SPEAKERS, FIRE DEVICES AND ALL SUPPORT HANGERS. REFER TO MEP DEMOLITION SHEETS FOR MORE INFORMATION.
- B REMOVE ALL EXISTING EQUIPMENT, ELECTRICAL DEVICES, WIRING & CONDUITS, THERMOSTATS, PLUMBING FIXTURES, SIGNAGE AND CASEWORK, U.N.O.
- C REMOVE ALL EXISTING FLOORING (EXCEPT TERRAZZO) TO CONCRETE SLAB. PREP. SLAB TO RECEIVE NEW FLOORING.
- D ON EXISTING WALLS THAT ARE TO REMAIN, REMOVE ALL EXISTING WALL BASE, CORNER GUARDS & WALL COVERINGS. PREP WALLS TO RECEIVE NEW FINISHES.
- E REMOVE EXISTING DOORS, FRAMES AND HARDWARE AS INDICATED.
- F ON EXISTING DOORS TO REMAIN, REMOVE HARDWARE.
- G CONTRACTOR SHALL VISIT THE EXISTING FACILITY AND OBSERVE EXISTING CONDITIONS PRIOR TO BIDDING.
- H GC SHALL PATCH AND REPAIR ANY VOIDS LEFT BEHIND IN REMAINING CONSTRUCTION & FINISHES BY THE REMOVAL OF WALLS OR OTHER OBJECTS SCHEDULED FOR DEMOLITION. REFER TO SPECIFICATION 0154 FOR ALTERATION PROCEDURES AND 0132 FOR CUTTING AND PATCHING.
- I THE FOLLOWING INFORMATION IS PROVIDED BY THE OWNER AND IS FOR THE CONTRACTOR'S GENERAL INFORMATION ONLY. CONTRACTOR SHALL MAKE ADDITIONAL INVESTIGATIONS TO IDENTIFY THE QUANTITY AND LOCATIONS OF ASBESTOS-CONTAINING MATERIALS TO BE ABATED:
  - ASBESTOS-CONTAINING MATERIALS (ACM) ARE KNOWN OR PRESUMED TO BE IN THE FOLLOWING MATERIALS:
    - SPRAY APPLIED INSULATION (SAI) IN ROOM 1M1.
    - SAI INSIDE THE BUILDING SCOFFITS
    - SOME OF THE THERMAL SYSTEMS INSULATION (TSI)
    - GASKETS AND PACKING MATERIALS
    - TRANSITE PANELING
  - REMOVAL/ABATEMENT OF THE ACM MUST FOLLOW THE REQUIREMENTS OF THE JSC SAFETY AND HEALTH HANDBOOK, JPR 1700, T. PART 12, ASBESTOS CONTROL REQUIREMENTS, AND OSHA 29 CFR 1926.1101, ASBESTOS.
- J EXISTING STRUCTURAL STEEL MEMBERS, DOORS AND DOOR FRAMES, SOME WALLS, AND OTHER SURFACES ARE COATED WITH LEAD AND/OR CHROMIUM CONTAINING PAINTS. ANY DRILLING, GRINDING, SANDING, CUTTING, TORCHING OR OTHER ACTIVITY WHICH DISTURBS THIS PAINT WILL CAUSE EXPOSURES. BEFORE PERFORMING ANY OF THESE ACTIVITIES USE CHEMICAL STRIPPING METHODS TO REMOVE THE PAINT FOR AT LEAST SIX (6) INCHES BEYOND THE AFFECTED AREA OR OTHERWISE CONTROL EXPOSURES TO MEET THE REQUIREMENTS OF OSHA 29 CFR 1926.
- K REFER TO RCP FOR ADDITIONAL DEMOLITION SCOPE.

**KEYED NOTES**

- 1 EXISTING STAIRS TO REMAIN. RAILINGS AND STEEL SUPPORT STRUCTURE TO REMAIN U.O.N.
- 2 REMOVE EXISTING STAIR AND HANDRAILS. FILL OPENING WITH NEW SLAB. COORD. WITH S-29-3
- 3 BASE BID. REMOVE EXISTING ELEVATOR FLOORING AND CONTROLS. REQUALIFY RAILINGS. REMOVE EXISTING HYDRAULIC ELEVATOR AND ELEVATOR DOORS
- 4 REMOVE EXISTING GLASS AND STEEL WINDOW WALL SYSTEM. SAW CUT AND REMOVE EXISTING PLASTER SOFFIT IN ITS ENTIRETY.
- 5 EXIST. STAIRS TO REMAIN. REMOVE EXISTING HANDRAILS / GUARDRAILS
- 6 REMOVE EXISTING GUARD RAIL AT NORTH SIDE OF INTERMEDIATE LANDING @ 14'-8" AFF.
- 7 EXISTING DOWNSPOUT TO REMAIN.
- 8 REMOVE EXISTING MEZZANINE, INCLUDING STEEL STRUCTURE, CONCRETE SLABS, WALLS, PLUMBING AND ELECTRICAL FIXTURES. 1ST AND 2ND FLOOR.
- 9 REMOVE EXISTING JIB CRANE AND SUPPORT STRUCTURE
- 10 EXISTING PRE-CAST STAIR ENCLOSURE TO REMAIN.
- 11 REMOVE EXISTING OVERHEAD DOOR. PREP. AREA FOR CONCRETE BLOCK INFILL. RE. SHEET A-29-19 FOR ADDITIONAL INFORMATION.
- 12 REMOVE EXISTING STEEL BF/OLD DOORS AND ASSOCIATED HINGES. DOOR JAMB AND HEAD TO REMAIN.
- 13 REMOVE EXISTING CRANE MONORAIL, TRACK AND ASSOCIATED SUPPORT STRUCTURE.
- 14 REMOVE EXISTING METAL CEILING PANELING, HVAC DUCTWORK AND AIR GRILLES (NOT SHOWN). ABOVE CEILING PIPING AND HANGERS, AND ALL ASSOCIATED SUPPORTS AND HANGER MATERIALS. PIPING REFERS TO ALL BUILDING SYSTEMS - WATER, FIRE PROTECTION, HYDRAULIC, STORM, SANITARY, ETC.
- 15 PATCH EXISTING CONCRETE DAMAGE AND EXPOSED RE-BAR AT STAIR TREAD.
- 16 REMOVE EXISTING CONCRETE SLAB AND ASSOCIATED STEEL SUPPORT STRUCTURE. (CROSS-HATCHED AREA)
- 17 REMOVE EXISTING METAL SUN SCREEN AND ASSOCIATED SUPPORT STRUCTURE AND HARDWARE. RE: 11A-29-21.
- 18 REMOVE EXISTING OVERHEAD CRANE, LIGHTS, AND ASSOCIATED EQUIPMENT
- 19 REMOVE EXISTING DRYWALL FURR OUT.
- 20 REMOVE EXISTING FURRING, P.E.A.F. WALL TO REMAIN.
- 21 REMOVE EXISTING ALUM. MOVING WINDOWS. EXISTING STEEL CHANNEL FRAME TO REMAIN.
- 22 EXISTING CEILING SYSTEM PANEL SUPPORT AND ASSOCIATED STEEL ANGLE SUPPORTS TO BE REMOVED.
- 23 REMOVE EXISTING H.I.D. LIGHT FIXTURE
- 24 REMOVE EXISTING OVERHEAD DOOR
- 25 AT ROTUNDA, ONLY REMOVE EXISTING ROOFING & INSULATION, AND ALL ASSOCIATED FLASHINGS, CURBS, LIGHTING PROTECTION AND OTHER APPURTENANCES. EXISTING METAL ROOF DECK TO REMAIN. GC TO FIELD VERY EXISTING CONDITIONS PRIOR TO BIDDING.
- 26 EXISTING FURRING ON COLUMNS IN THE INDICATED AREA SHALL REMAIN
- 27 REMOVE EXISTING MONORAIL CRANE AND TRACK
- 28 REMOVE EXISTING FURDOWN FRAMING
- 29 REMOVE EXISTING FLUORESCENT LIGHT FIXTURE
- 30 PROVIDE STEEL STRUCTURAL FRAME AT NEW CASED OPENING. REFER TO A-29-7 FOR EXACT LOCATION
- 31 REMOVE EXISTING WALL ABOVE +/- 16'-10" FOR NEW CONC. SLAB & STRUCT. VERY EXACT HEIGHT.
- 32 REMOVE EXISTING WALL ABOVE +/- 11'-4" FOR NEW CONC. SLAB & STRUCT. VERY EXACT HEIGHT.
- 33 REMOVE EXISTING CHUTE FROM FINISH FLOOR ELEVATION TO STRUCTURE ABOVE. CUT & REMOVE EXISTING WIDE FLANGE LITTLE END AND IN-WALL WIDE FLANGE COLUMN. EXISTING IN-WALL COLUMN ON WEST JAMB OF OPENING SHALL REMAIN.

2  
2  
ROTUNDA DEMOLITION RCP  
1/16" = 1'-0"  
0 8 16 32 FT



**h+k**  
HELLMUTH, OBATA + KASSABAUM, L.P.  
ARCHITECTURE, ENGINEERING, PLANNING, INTERIORS, GRAPHICS, CONSULTING  
2800 Post Oak Blvd, Suite 3700 Houston, Texas, USA 77056  
V+713.4077700 F+713.4077809 http://www.hok.com  
All reproduction & distribution property rights reserved © 2009



REVISION	DATE	DESCRIPTION
Δ	5/23/08	AMENDMENT 3
	4/29/08	ISSUE FOR BID AND CONSTRUCTION

SIGNATURES	DATE
DR. ENG.	
CH. APPR.	

PROJECT NO.		SHEET NO.
PROJECT CD. NO.		AD-29-2
CODE IDENT. NO.	SIZE	DWG. NO.
	F	of