



NOTICE - WHEN GOVERNMENT DRAWINGS, SPECIFICATIONS, OR OTHER DATA ARE USED FOR ANY PURPOSE OTHER THAN IN CONNECTION WITH A DEFINITELY RELATED GOVERNMENT PROCUREMENT OPERATION, THE UNITED STATES GOVERNMENT THEREBY INCURS NO RESPONSIBILITY NOR OBLIGATION WHATSOEVER, AND THE FACT THAT THE GOVERNMENT MAY HAVE FORMULATED, FURNISHED, OR IN ANY WAY SUPPLIED THE SAID DRAWINGS, SPECIFICATIONS, OR OTHER DATA IS NOT TO BE REGARDED BY IMPLICATION OR OTHERWISE AS IN ANY MANNER LICENSING THE HOLDER OR ANY OTHER PERSON OR CORPORATION, OR CONVEYING ANY RIGHTS OR PERMISSION TO MANUFACTURE, USE, OR SELL ANY PATENTED INVENTION THAT MAY IN ANY WAY BE RELATED THERETO.

APPLICATION		PART NO.	MF	REVISIONS			
NEXT ASSY	USED ON			SYM	DESCRIPTION	DATE	APPROVAL

TECHNICAL SPECIFICATIONS FOR DRAWING 79K38701

TITLE OF DOCUMENT:			
SENSITIVE BUT UNCLASSIFIED (SBU) INSTRUCTIONS: This item must be reviewed under the requirements for "Sensitive But Unclassified Information" as described in NPR 1600.1, Chapter 5.24 http://nodis3.gsfc.nasa.gov/main_lib.html			
	Yes	No	SBU Reviewer's Signature
Document contains SBU?	<input type="checkbox"/>	<input checked="" type="checkbox"/>	
			Date
			9-10-10
EXPORT CONTROL (EC) INSTRUCTIONS: If the document includes export-controlled data, contact your directorate Export Control Representative or the KSC ECO Help Desk (867-9209) for a determination of the proper export category. http://exportcontrol.ksc.nasa.gov/index.cfm			
ECO Reviewer's Name and Organization		ECO Reviewer's Signature	
PING YU, NASA TA-B3A			
		Date	
		9-10-10	
EXPORT DETERMINATION (<input checked="" type="checkbox"/> one box only)			
EAR 99 NLR	<input checked="" type="checkbox"/>	The information contained in the document is technical in content, but is not technical data as defined by the ITAR or the EAR, and therefore is EAR 99 NLR (no export license required). [General Prohibition Six (Embargo) applies to all items subject to the EAR, i.e. items on the CCL and within EAR 99 NLR. You may not make an export or re-export contrary to the provisions of part 746 (Embargos and Other Special Controls) of the EAR and 22 CFR part 126.1 of the ITAR.]	
EAR Controlled	<input type="checkbox"/>	This document is within the purview of the Export Administration Regulations (EAR), 15 CFR 730-774, and is export controlled. It may not be transferred to foreign nationals in the U.S. or abroad without specific approval of a knowledgeable NASA export control official, and/or unless an export license or license exception is obtained/available from the Bureau of Industry and Security, United States Department of Commerce. <i>Violations of these regulations are punishable by fine, imprisonment, or both.</i>	
ITAR Controlled	<input type="checkbox"/>	This document contains information which falls under the purview of the U.S. Munitions List (USML), as defined in the International Traffic in Arms Regulations (ITAR), 22 CFR 120-130, and is export controlled. It shall not be transferred to foreign nationals, in the U.S. or abroad, without specific approval of a knowledgeable NASA export control official, and/or unless an export license or license exemption is obtained/available from the United States Department of State. <i>Violations of these regulations are punishable by fine, imprisonment, or both.</i>	

THIS DRAWING CREATED ON THE CAD/CAE INTERACTIVE GRAPHICS SYSTEM MUST BE REVISED ONLY ON THAT SYSTEM.
FILE:

UNLESS OTHERWISE SPECIFIED	ORIGINAL DATE OF DRAWING		REVITALIZE KSC WATER SYSTEMS, DESIGN PACKAGE 2	JOHN F. KENNEDY SPACE CENTER, NASA
DIMENSIONS ARE IN INCHES TOLERANCES ON FRACTIONS DECIMALS ANGLES	DRAFTSMAN	CHECKER		
MATERIAL	TRACER	CHECKER		
	ENGINEER	ENGINEER	TECHNICAL SPECIFICATIONS	KENNEDY SPACE CENTER, FLORIDA
HEAT TREATMENT	SUBMITTED	SCALE	DWG SIZE	79K38702
		9-10-10	A	
FINAL PROTECTIVE FINISH	APPROVED	PCN 98814		SHEET 1 OF 176

PCN 98814 and 98815	DOCUMENT RELEASE AUTHORIZATION KENNEDY SPACE CENTER, NASA	PAGE 1 OF 4
ESR N/A		REV/DATE
DIR N/A	DRA NO. E-WA000000-1046	SIGNATURE
EFF	TITLE: Revitalize KSC Water Systems & Revitalize KSC Waste Water Systems Fiscal Year (FY) 2011	VEN CODE
EQ. LOC. KSC, K6-0896, K6-0993, K6-0994, M6-0896A		CONTRACT NNK10CA40D / NNK09CB36D
SDL N/A		

DOCUMENTS

#	PREF	DOCUMENT NUMBER	ISSUE	SIZE	SHTS	B/L NO.	SS	MODEL NUMBER	WUC
1	DR	79K38699	NEW	F	129	353.00	ZO	K62-5235	ZOFACHV000
						353.40	ZO	K62-5230	ZOFACLV000
						100.00	ZO	K62-5236	ZOFAI00000
						355.00	ZO	K62-5224	ZOFFA10000
						360.10	ZO	K62-5231	ZOFFG00000
						492.00	ZO	K62-5233	ZOFHV10000
						360.11	ZO	K62-5232	ZOFLU00000
						497.01	ZO	K62-5234	ZOFSR00000
						495.50	ZO	K62-5225	ZOFSY00000
						505.10	ZO	K62-5237	ZOFTN20000
						360.05	ZO	K61-4414-3014	ZOFUCU0000
						353.40	ES	K62-5227	ESFACLV000
						360.10	ES	K62-5228	ESFFG10000
						360.11	ES	K62-5229	ESFLU10000
						497.01	ES	K62-5226	ESFSRTN000
						354.00	K-	K60-0434	K-FWA00000
2	SP	79K38700	NEW	A	788	**	**	**	**

TECHNICAL REMARKS

Prepared by Nicola Staton, Jones Edmunds, 269-2950

APPROVALS

TECHNICAL CONTACT	MAIL CODE	DATE	R&QA	MAIL CODE	DATE
 Kevin Miller, 867-1271	TA-B3A	9-20-10		SA-E3	9-20-10
TECHNICAL Ping Yu, 867-7681	TA-B3A	9/20/2010	OTHER		
SPACE AND WEIGHT			JOINT RELEASE		
PROCUREMENT PKG.			RELEASE 	TA-B3A	9-20-10

PCN: 98814 and 98815 EQ. LOC. KSC, K6-0896, K6-0993, K6-0994, M6-0896A	DOCUMENT RELEASE AUTHORIZATION KENNEDY SPACE CENTER, NASA	PAGE 2 OF 4
	DRA NO. E-WA000000- 1046	

DOCUMENTS

#	PREF	DOCUMENT NUMBER	ISSUE	SIZE	SHTS	B/L NO.	SS	MODEL NUMBER	WUC						
3	DR	79K38701	NEW	F	10	353.40	ES	K61-0409	ESFACVL000						
						360.03	ES	K61-5606	ESFCP00000						
						360.10	ES	K60-0632	ESFFG00000						
						497.01	ES	K61-0813	ESFSR60000						
						391.00	ES	K61-7739	ESFSS00000						
						500.40	ES	K61-0789	ESFWPV0000						
						353.05	ET	K61-0544	ETFAC6L000						
						360.03	ET	K61-5608	ETFCP00000						
						360.10	ET	K61-3982	ETFFG00000						
						505.11	ET	K61-1388	ETFSR90000						
						501.10	ET	K61-7810	ETFSS00000						
						495.10	ET	K61-1338	ETFWP60000						
						4	SP	79K38702	NEW	A	176	**	**	**	**
						5	DR	79K38703	NEW	F	79	501.10	K-	K61-6981	K-FSSS0000
6	SP	79K38704	NEW	A	423	**	**	**	**						
7	DM	KSC-TA-10941 Cover, 1-362, 367-420, 423-430, 435-600, 605-924, 929-946, 951-968, 973-990, 995-1012, 1017-1040, 1047-1066, 363-366, 421-422, 431-434, 601-604, 925-928, 947-950, 969-972, 991-994, 1013-1016, 1041-1046, 1067-1082	NEW	A	1027	**	**	**	**						
				B	56	**	**	**	**						
8	SW	79K38699	NEW	M	1	353.00	ZO	K62-5235	ZOFACHV000						
						353.40	ZO	K62-5230	ZOFACLV000						
						100.00	ZO	K62-5236	ZOFAI00000						
						355.00	ZO	K62-5224	ZOFFA10000						
						360.10	ZO	K62-5231	ZOFFG00000						
						492.00	ZO	K62-5233	ZOFHV10000						
						360.11	ZO	K62-5232	ZOFLU00000						
						497.01	ZO	K62-5234	ZOFSR00000						
						495.50	ZO	K62-5225	ZOFSY00000						
						505.10	ZO	K62-5237	ZOFTN20000						
						360.05	ZO	K61-4414-3014	ZOFUCU0000						
						353.40	ES	K62-5227	ESFACLV000						
						360.10	ES	K62-5228	ESFFG10000						
						360.11	ES	K62-5229	ESFLU10000						
						497.01	ES	K62-5226	ESFSRTN000						
						354.00	K-	K60-0434	K-FWA00000						
9	SW	79K38700	NEW	M	1	**	**	**	**						

PCN: 98814 and 98815 EQ. LOC. KSC, K6-0896, K6-0993, K6-0994, M6-0896A	DOCUMENT RELEASE AUTHORIZATION KENNEDY SPACE CENTER, NASA	PAGE 3 OF 4
	DRA NO. E-WA000000- 1046	

DOCUMENTS

I#	PREF	DOCUMENT NUMBER	ISSUE	SIZE	SHTS	B/L NO.	SS	MODEL NUMBER	WUC						
10	SW	79K38701	NEW	M	1	353.40	ES	K61-0409	ESFACVL000						
						360.03	ES	K61-5606	ESFCP00000						
						360.10	ES	K60-0632	ESFFG00000						
						497.01	ES	K61-0813	ESFSR60000						
						391.00	ES	K61-7739	ESFSS00000						
						500.40	ES	K61-0789	ESFWPV0000						
						353.05	ET	K61-0544	ETFAC6L000						
						360.03	ET	K61-5608	ETFCP00000						
						360.10	ET	K61-3982	ETFFG00000						
						505.11	ET	K61-1388	ETFSR90000						
						501.10	ET	K61-7810	ETFSS00000						
						495.10	ET	K61-1338	ETFWP60000						
						11	SW	79K38702	NEW	M	1	**	**	**	**
						12	SW	79K38703	NEW	M	1	501.10	K-	K61-6981	K-FSSS0000
13	SW	79K38704	NEW	M	1	**	**	**	**						
14	SW	KSC-TA-10941	NEW	M	1	**	**	**	**						

DISTRIBUTION NUMBER

**DOCUMENT RELEASE AUTHORIZATION DISTRIBUTION
KENNEDY SPACE CENTER, NASA**

DRA NO.

E-WA000000- 1046

QUANTITY	MAIL CODE	NAME	QUANTITY	MAIL CODE	NAME
DRA	TA-B3A	Ping Yu			
DRA	TA-B3A	F. Der			
1P	TA-B3A	K. Miller			
1P	TA-B3A	M. Oyola	1P	Jones Edmunds	Mike Clark
DRA	IHA-200	K. Herpich			Jones Edmunds
DRA	ISC-2200	R. Carson			730 NE Waldo Road
DRA	ISC-2200	T. King			Gainesville, FL 32641
DRA	MEI	J. Dillon			
DRA	ISC-8600	H. Truong			
DRA	USK-754	J. Smith			
DRA	TA-B1B	R. Kline			
DRA	ISC-8200	E. Hupfer			
DRA	SA-E3	P. Swihart			
DRA	ISC-8640	J. Johnson			
DRA	ISC-5000	D. Leinbach			
DRA	TA-B3B	D. Trang			
DRA	TA-B3B	L. Kiel	DRA	ISC-4210	R. Koralewicz
DRA	ISC-4013	D. Nero	DRA	ISC-4235	H. Hepp
DRA	ISC-4013	M. Skidmore	DRA	ISC-4126	S. Hopper
DRA	ISC-4013	T. Pobjecky	DRA	TA-B1B	D. Durham
DRA	ISC-4013	J. Ward	DRA	SGS-322	E. Levison
DRA	ISC-4300	E. Beyette	DRA	ISC-4011	E. Lyon
DRA	ISC-2100	S. Ho	DRA	SA-E3	C. Miller
DRA	ISC-2120	P. Smith	CD	ISC-4026	S. Hopper
DRA	ISC-4410	D. Carraway			
DRA	ISC-2120	A. Studt			
1P	ISC-4500	D. Smith			
1P	ISC-2200	E. Feeney			
DRA	ISC-2300	D. Czerwinski			
DRA	ISC-4410	T. Roosa			
DRA	ISC-4300	G. Hegde			
DRA	ISC-4500	R. Hatcher			
DRA	ISC-2200	B. Orrison			
DRA	ISC-4300	P. Kroning			
1P	ISC-4250	B. Buchawiecki			
DRA	ISC-8600	L. Sardella			
DRA	TA-B3E	G. Diaz			
DRA	TA-B3E	B. Glover			
DRA	TA-B3E	J. Green			

REPRODUCTION AND DISTRIBUTION INSTRUCTIONS

Reduce all drawings from "F" size to "B" size for distribution.

PROJECT TABLE OF CONTENTS

DIVISION 01 - GENERAL REQUIREMENTS

01 11 00	SUMMARY OF WORK
01 33 00	SUBMITTAL PROCEDURES
01 35 26	GOVERNMENTAL SAFETY REQUIREMENTS
01 42 00	SOURCES FOR REFERENCE PUBLICATIONS
01 57 20.00 10	ENVIRONMENTAL PROTECTION
01 57 23	TEMPORARY STORM WATER POLLUTION CONTROL
01 74 19	CONSTRUCTION AND DEMOLITION WASTE MANAGEMENT
01 78 00	CLOSEOUT SUBMITTALS

DIVISION 02 - EXISTING CONDITIONS

02 41 00	DEMOLITION AND DECONSTRUCTION
02 82 13.00 98	ASBESTOS ABATEMENT
02 82 33.13 20	REMOVAL/CONTROL AND DISPOSAL OF PAINT WITH LEAD
02 84 33	REMOVAL AND DISPOSAL OF POLYCHLORINATED BIPHENYLS (PCBs)

DIVISION 31 - EARTHWORK

31 00 00	EARTHWORK
----------	-----------

DIVISION 32 - EXTERIOR IMPROVEMENTS

32 92 23	SODDING
----------	---------

DIVISION 33 - UTILITIES

33 11 00	WATER DISTRIBUTION
----------	--------------------

-- End of Project Table of Contents --

SECTION TABLE OF CONTENTS

DIVISION 01 - GENERAL REQUIREMENTS

SECTION 01 11 00

SUMMARY OF WORK

PART 1 GENERAL

- 1.1 REFERENCES
- 1.2 DEFINITIONS
- 1.3 SUBMITTALS
- 1.4 WORK COVERED BY CONTRACT DOCUMENTS
 - 1.4.1 Project Description
 - 1.4.2 Location
- 1.5 CONTRACT DRAWINGS
- 1.6 EPA DESIGNATED ITEMS INCORPORATED IN THE WORK

PART 2 PRODUCTS

PART 3 EXECUTION

-- End of Section Table of Contents --

SECTION 01 11 00

SUMMARY OF WORK

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

ASTM INTERNATIONAL (ASTM)

ASTM E 2114 (2008) Standard Terminology for Sustainability Relative to the Performance of Buildings

1.2 DEFINITIONS

Definitions pertaining to sustainable development are as defined in ASTM E 2114, Section 01 57 20.00 10 ENVIRONMENTAL PROTECTION, and as specified.

a. "Environmentally preferable products" have a lesser or reduced effect on the environment in comparison to conventional products and services. This comparison may consider raw materials acquisition, production, manufacturing, packaging, distribution, reuse, operation, maintenance, or disposal of the product.

b. "Sustainability" is the balance of environmental, economic, and societal considerations.

1.3 SUBMITTALS

Not used.

1.4 WORK COVERED BY CONTRACT DOCUMENTS

1.4.1 Project Description

The work includes the demolition of the two elevated storage tanks and associated appurtenances in the Industrial Area (M6-896A) and the VAB Area (K6-994). The work includes demolishing the steel structures and removing all equipment associated with the elevated storage tanks, including but not limited to pumps, valves, water lines (to the point of source), and electrical system components (to the point of source).

1.4.2 Location

The work shall be located at the Industrial Area and VAB Area, approximately as indicated on the drawings. The exact locations will be shown by the Contracting Officer.

1.5 CONTRACT DRAWINGS

The following drawings accompany this specification and are a part thereof.

Drawing No. 79K38701
Sheets 1 through 10

The publications of the issues of referenced documents in effect on the date of issuance of invitation for bids form a part of this specification and, where referred to herein by basic designation only, are applicable to the extent indicated by the references thereto. In the event of difference between this specification or its accompanying drawings and the referenced document, this specification and its accompanying drawings must govern to the extent of such difference.

1.6 EPA DESIGNATED ITEMS INCORPORATED IN THE WORK

Various sections of the specifications contain requirements for materials that have been designated by EPA as being products which are or can be made with recovered recycled materials. These items, when incorporated into the work under this contract, must contain at least the specified percentage of recycled or recovered material.

PART 2 PRODUCTS

Not used.

PART 3 EXECUTION

Not used.

SPECIFICATION COVER SHEET

-- End of Section --

SECTION TABLE OF CONTENTS

DIVISION 01 - GENERAL REQUIREMENTS

SECTION 01 33 00

SUBMITTAL PROCEDURES

PART 1 GENERAL

- 1.1 DEFINITIONS
 - 1.1.1 Submittal Descriptions (SD)
 - 1.1.2 Approving Authority
 - 1.1.3 Work
- 1.2 SUBMITTALS
- 1.3 SUBMITTAL CLASSIFICATION
 - 1.3.1 Government Approved
 - 1.3.2 Information Only
- 1.4 FORWARDING SUBMITTALS REQUIRING GOVERNMENT APPROVAL
 - 1.4.1 Submittals Required from the Contractor
- 1.5 PREPARATION
 - 1.5.1 Transmittal Form
 - 1.5.2 Identifying Submittals
 - 1.5.3 Format for SD-02 Shop Drawings
 - 1.5.4 Format of SD-03 Product Data and SD-08 Manufacturer's Instructions
 - 1.5.5 Format of SD-04 Samples
 - 1.5.6 Format of SD-05 Design Data and SD-07 Certificates
 - 1.5.7 Format of SD-06 Test Reports and SD-09 Manufacturer's Field Reports
 - 1.5.8 Format of SD-01 Preconstruction Submittals and SD-11 Closeout Submittals
- 1.6 INFORMATION ONLY SUBMITTALS
- 1.7 VARIATIONS / SUBSTITUTION REQUESTS
 - 1.7.1 Considering Variations
 - 1.7.2 Proposing Variations
 - 1.7.3 Warranting That Variations Are Compatible
 - 1.7.4 Review Schedule Is Modified
- 1.8 SCHEDULING
 - 1.8.1 Reviewing, Certifying, Approving Authority
 - 1.8.2 Constraints
- 1.9 GOVERNMENT APPROVING AUTHORITY
 - 1.9.1 Review Notations
- 1.10 DISAPPROVED SUBMITTALS
- 1.11 APPROVED SUBMITTALS
- 1.12 APPROVED SAMPLES
- 1.13 STATUS REPORT ON MATERIALS ORDERS

PART 2 PRODUCTS

PART 3 EXECUTION

-- End of Section Table of Contents --

SECTION 01 33 00

SUBMITTAL PROCEDURES

PART 1 GENERAL

The Contracting Officer may request submittals in addition to those specified when deemed necessary to adequately describe the work covered in the respective sections.

Units of weights and measures used on all submittals are to be the same as those used in the contract drawings.

Each submittal is to be complete and in sufficient detail to allow ready determination of compliance with contract requirements.

Contractor's Quality Control (CQC) System Manager and the Designer of Record, if applicable, to check and approve all items prior to submittal and stamp, sign, and date indicating action taken. Proposed deviations from the contract requirements are to be clearly identified. Include within submittals items such as: Contractor's, manufacturer's, or fabricator's drawings; descriptive literature including (but not limited to) catalog cuts, diagrams, operating charts or curves; test reports; test cylinders; samples; O&M manuals (including parts list); certifications; warranties; and other such required submittals.

Submittals requiring Government approval are to be scheduled and made prior to the acquisition of the material or equipment covered thereby. Picked up and disposed of in accordance with manufacturer's Material Safety Data Sheets (MSDS) and in compliance with existing laws and regulations samples remaining upon completion of the work.

1.1 DEFINITIONS

1.1.1 Submittal Descriptions (SD)

Submittals requirements are specified in the technical sections. Submittals are identified by Submittal Description (SD) numbers and titles as follows:

SD-01 Preconstruction Submittals

Submittals which are required prior to a notice to proceed commencing work on site. Submittals required prior to the start of the next major phase of the construction on a multi-phase contract. Schedules or tabular list of data or tabular list including location, features, or other pertinent information regarding products, materials, equipment, or components to be used in the work, submitted prior to contract notice to proceed or next major phase of construction.

Certificates of insurance
Surety bonds
List of proposed subcontractors
List of proposed products
Construction Progress Schedule
Network Analysis Schedule (NAS)

Submittal register
Schedule of prices
Safety and health plan
Work plan
Quality control(QC) plan
Environmental protection plan

SD-02 Shop Drawings

Drawings, diagrams and schedules specifically prepared to illustrate some portion of the work.

Diagrams and instructions from a manufacturer or fabricator for use in producing the product and as aids to the Contractor for integrating the product or system into the project.

Drawings prepared by or for the Contractor to show how multiple systems and interdisciplinary work will be coordinated.

SD-03 Product Data

Catalog cuts, illustrations, schedules, diagrams, performance charts, instructions and brochures illustrating size, physical appearance and other characteristics of materials, systems or equipment for some portion of the work.

Samples of warranty language when the contract requires extended product warranties.

SD-06 Test Reports

Report signed by authorized official of testing laboratory that a material, product or system identical to the material, product or system to be provided has been tested in accord with specified requirements. (Testing must have been within three years of date of contract award for the project.)

Report which includes findings of a test required to be performed by the Contractor on an actual portion of the work or prototype prepared for the project before shipment to job site.

Report which includes finding of a test made at the job site or on sample taken from the job site, on portion of work during or after installation.

Investigation reports.

Daily logs and checklists.

Final acceptance test and operational test procedure.

SD-07 Certificates

Statements printed on the manufacturer's letterhead and signed by responsible officials of manufacturer of product, system or material attesting that product, system or material meets specification requirements. Must be dated after award of project contract and clearly name the project.

Document required of Contractor, or of a manufacturer, supplier, installer or subcontractor through Contractor, the purpose of which is to further quality of orderly progression of a portion of the work by documenting procedures, acceptability of methods or personnel qualifications.

Confined space entry permits.

Text of posted operating instructions.

SD-08 Manufacturer's Instructions

Preprinted material describing installation of a product, system or material, including special notices and Material Safety Data sheets concerning impedances, hazards and safety precautions.

SD-11 Closeout Submittals

Documentation to record compliance with technical or administrative requirements or to establish an administrative mechanism.

Special requirements necessary to properly close out a construction contract. For example, record drawings and as-built drawings. Also, submittal requirements necessary to properly close out a major phase of construction on a multi-phase contract.

1.1.2 Approving Authority

Office or designated person authorized to approve submittal.

1.1.3 Work

As used in this section, on- and off-site construction required by contract documents, including labor necessary to produce submittals, construction, materials, products, equipment, and systems incorporated or to be incorporated in such construction.

1.2 SUBMITTALS

Not used.

1.3 SUBMITTAL CLASSIFICATION

Submittals are classified as follows:

1.3.1 Government Approved

Government approval is required for extensions of design, critical materials, deviations, equipment whose compatibility with the entire system must be checked, and other items as designated by the Contracting Officer. Government approval is required for any deviations from the Solicitation or Accepted Proposal and other items as designated by the Contracting Officer. Within the terms of the Contract Clause entitled "Specifications and Drawings for Construction," they are considered to be "shop drawings."

1.3.2 Information Only

Submittals not requiring Government approval will be for information only. They are not considered to be "shop drawings" within the terms of the

Contract Clause referred to above.

1.4 FORWARDING SUBMITTALS REQUIRING GOVERNMENT APPROVAL

1.4.1 Submittals Required from the Contractor

As soon as practical after award of contract, and before procurement of fabrication, forward to the Contracting Officer, submittals required in the technical sections of this specification, including shop drawings, product data and samples.

The Government will review and approve for the Contracting Officer those submittals reserved for Contracting Officer approval to verify submittals comply with the contract requirements.

1.5 PREPARATION

1.5.1 Transmittal Form

Transmit each submittal, except sample installations and sample panels to office of approving authority. Transmit submittals with transmittal form prescribed by Contracting Officer and standard for project. On the transmittal form identify Contractor, indicate date of submittal, and include information prescribed by transmittal form and required in paragraph entitled "Identifying Submittals." Process transmittal forms to record actions regarding sample installations.

1.5.2 Identifying Submittals

When submittals are provided by a Subcontractor, the Prime Contractor is to prepare, review and stamp with Contractor's approval all specified submittals prior to submitting for Government approval.

Identify submittals, except sample installations and sample panels, with the following information permanently adhered to or noted on each separate component of each submittal and noted on transmittal form. Mark each copy of each submittal identically, with the following:

- a. Project title and location.
- b. Construction contract number.
- c. Date of the drawings and revisions.
- d. Name, address, and telephone number of subcontractor, supplier, manufacturer and any other subcontractor associated with the submittal.
- e. Section number of the specification section by which submittal is required.
- f. Submittal description (SD) number of each component of submittal.
- g. When a resubmission, add alphabetic suffix on submittal description, for example, submittal 18 would become 18A, to indicate resubmission.
- h. Product identification and location in project.

1.5.3 Format for SD-02 Shop Drawings

- a. Shop drawings are not to be less than 8 1/2 by 11 inches nor more than 30 by 42 inches, except for full size patterns or templates. Prepare drawings to accurate size, with scale indicated, unless other form is required. Drawings are to be suitable for reproduction and be of a quality to produce clear, distinct lines and letters with dark lines on a white background.
- b. Present A4 8 1/2 by 11 inches sized shop drawings as part of the bound volume for submittals required by section. Present larger drawings in sets.
- c. Include on each drawing the drawing title, number, date, and revision numbers and dates, in addition to information required in paragraph entitled "Identifying Submittals."
- d. Number drawings in a logical sequence. Contractors may use their own number system. Each drawing is to bear the number of the submittal in a uniform location adjacent to the title block. Place the Government contract number in the margin, immediately below the title block, for each drawing.
- e. Reserve a blank space, no smaller than 4 inches on the right hand side of each sheet for the Government disposition stamp.
- f. Dimension drawings, except diagrams and schematic drawings; prepare drawings demonstrating interface with other trades to scale. Use the same unit of measure for shop drawings as indicated on the contract drawings. Identify materials and products for work shown.
- g. Include the nameplate data, size and capacity on drawings. Also include applicable federal, military, industry and technical society publication references.

1.5.4 Format of SD-03 Product Data and SD-08 Manufacturer's Instructions

- a. Present product data submittals for each section as a complete, bound volume. Include table of contents, listing page and catalog item numbers for product data.
- b. Indicate, by prominent notation, each product which is being submitted; indicate specification section number and paragraph number to which it pertains.
- c. Supplement product data with material prepared for project to satisfy submittal requirements for which product data does not exist. Identify this material as developed specifically for project, with information and format as required for submission of SD-07 Certificates.
- d. Provide product data in metric dimensions. Where product data are included in preprinted catalogs with English units only, submit metric dimensions on separate sheet.
- e. Include the manufacturer's name, trade name, place of manufacture, and catalog model or number on product data. Also include applicable federal, military, industry and technical society

publication references. Should manufacturer's data require supplemental information for clarification, submit as specified for SD-07 Certificates.

- f. Where equipment or materials are specified to conform to industry and technical society reference standards of the organizations such as American National Standards Institute (ANSI), ASTM International (ASTM), National Electrical Manufacturer's Association (NEMA), Underwriters Laboratories (UL), and Association of Edison Illuminating Companies (AEIC), submit proof of such compliance. The label or listing by the specified organization will be acceptable evidence of compliance. In lieu of the label or listing, submit a certificate from an independent testing organization, competent to perform testing, and approved by the Contracting Officer. State on the certificate that the item has been tested in accordance with the specified organization's test methods and that the item complies with the specified organization's reference standard.
- g. Collect required data submittals for each specific material, product, unit of work, or system into a single submittal and marked for choices, options, and portions applicable to the submittal. Mark each copy of the product data identically. Partial submittals will not be accepted for expedition of construction effort.
- h. Submit manufacturer's instructions prior to installation.

1.5.5 Format of SD-04 Samples

- a. Furnish samples in sizes below, unless otherwise specified or unless the manufacturer has prepackaged samples of approximately same size as specified:
 - (1) Sample of Equipment or Device: Full size.
 - (2) Sample of Materials Less Than 2 by 3 inches: Built up to 8 1/2 by 11 inches.
 - (3) Sample of Materials Exceeding 8 1/2 by 11 inches: Cut down to 8 1/2 by 11 inches and adequate to indicate color, texture, and material variations.
 - (4) Sample of Linear Devices or Materials: 10 inch length or length to be supplied, if less than 10 inches. Examples of linear devices or materials are conduit and handrails.

1.5.6 Format of SD-05 Design Data and SD-07 Certificates

Provide design data and certificates on 8 1/2 by 11 inches paper. Provide a bound volume for submittals containing numerous pages.

1.5.7 Format of SD-06 Test Reports and SD-09 Manufacturer's Field Reports

- a. Provide reports on 8 1/2 by 11 inches paper in a complete bound volume.
- b. Indicate by prominent notation, each report in the submittal.

Indicate specification number and paragraph number to which it pertains.

1.5.8 Format of SD-01 Preconstruction Submittals and SD-11 Closeout Submittals

- a. When submittal includes a document which is to be used in project or become part of project record, other than as a submittal, do not apply Contractor's approval stamp to document, but to a separate sheet accompanying document.

1.6 INFORMATION ONLY SUBMITTALS

Normally submittals for information only will not be returned. Approval of the Contracting Officer is not required on information only submittals. The Government reserves the right to require the Contractor to resubmit any item found not to comply with the contract. This does not relieve the Contractor from the obligation to furnish material conforming to the plans and specifications; will not prevent the Contracting Officer from requiring removal and replacement of nonconforming material incorporated in the work; and does not relieve the Contractor of the requirement to furnish samples for testing by the Government laboratory or for check testing by the Government in those instances where the technical specifications so prescribe.

1.7 VARIATIONS / SUBSTITUTION REQUESTS

Variations from contract requirements require Government approval pursuant to contract Clause FAR 52.236-21 and will be considered where advantageous to Government.

1.7.1 Considering Variations

Discussion with Contracting Officer prior to submission, will help ensure functional and quality requirements are met and minimize rejections and re-submittals. When contemplating a variation which results in lower cost, consider submission of the variation as a Value Engineering Change Proposal (VECP).

Specifically point out variations from contract requirements in transmittal letters. Failure to point out deviations may result in the Government requiring rejection and removal of such work at no additional cost to the Government.

1.7.2 Proposing Variations

When proposing variation, deliver written request to the Contracting Officer, with documentation of the nature and features of the variation and why the variation is desirable and beneficial to Government. If lower cost is a benefit, also include an estimate of the cost savings. In addition to documentation required for variation, include the submittals required for the item. Clearly mark the proposed variation in all documentation.

1.7.3 Warranting That Variations Are Compatible

When delivering a variation for approval, Contractor warrants that this contract has been reviewed to establish that the variation, if incorporated, will be compatible with other elements of work.

1.7.4 Review Schedule Is Modified

In addition to normal submittal review period, a period of 10 working days will be allowed for consideration by the Government of submittals with variations.

1.8 SCHEDULING

Schedule and submit concurrently submittals covering component items forming a system or items that are interrelated. Include certifications to be submitted with the pertinent drawings at the same time. No delay damages or time extensions will be allowed for time lost in late submittals.

- a. Coordinate scheduling, sequencing, preparing and processing of submittals with performance of work so that work will not be delayed by submittal processing. Allow for potential resubmittal of requirements.
- b. For submittals requiring review by fire protection engineer, allow review period, beginning when Government receives submittal from the Contractor, of 21 working days for return of submittal to the Contractor.
- c. Period of review for each resubmittal is the same as for initial submittal.

At the Preconstruction conference, provide, for approval by the Contracting Officer, the following schedule of submittals:

- a. A schedule of shop drawings and technical submittals required by the specifications and drawings. Indicate the specification or drawing reference requiring the submittal; the material, item, or process for which the submittal is required; the "SD" number and identifying title of the submittal; the Contractor's anticipated submission date and the approval need date.
- b. A separate schedule of other submittals required under the contract but not listed in the specifications or drawings. Schedule will indicate the contract requirement reference; the type or title of the submittal; the Contractor's anticipated submission date and the approved need date (if approval is required).

1.8.1 Reviewing, Certifying, Approving Authority

The Contractor is responsible for reviewing and certifying that submittals are in compliance with contract requirements. At each "Submittal" paragraph in individual specification sections, a notation "G," following a submittal item, indicates Contracting Officer is approving authority for that submittal item.

1.8.2 Constraints

- a. Conform to provisions of this section, unless explicitly stated otherwise for submittals listed or specified in this contract.
- b. Submit complete submittals for each definable feature of work. Submit at the same time components of definable feature

interrelated as a system.

- c. When acceptability of a submittal is dependent on conditions, items, or materials included in separate subsequent submittals, submittal will be returned without review.
- d. Approval of a separate material, product, or component does not imply approval of assembly in which item functions.

1.9 GOVERNMENT APPROVING AUTHORITY

When approving authority is Contracting Officer, the Government will:

- a. Note date on which submittal was received from the Contractor.
- b. Review submittals for approval within scheduling period specified and only for conformance with project design concepts and compliance with contract documents.
- c. Identify returned submittals with one of the actions defined in paragraph entitled "Review Notations" and with markings appropriate for action indicated.

Upon completion of review of submittals requiring Government approval, stamp and date approved submittals.

1.9.1 Review Notations

Contracting Officer review will be completed within 14 calendar days after date of submission. Submittals will be returned to the Contractor with the following notations:

- a. Submittals marked "approved" or "accepted" authorize the Contractor to proceed with the work covered.
- b. Submittals marked "approved as noted" "or approved except as noted, resubmittal not required," authorize the Contractor to proceed with the work covered provided he takes no exception to the corrections.
- c. Submittals marked "not approved" or "disapproved," or "revise and resubmit," indicate noncompliance with the contract requirements or design concept, or that submittal is incomplete. Resubmit with appropriate changes. No work shall proceed for this item until resubmittal is approved.
- d. Submittals marked "not reviewed" will indicate submittal has been previously reviewed and approved, is not required, does not have evidence of being reviewed and approved by Contractor, or is not complete. A submittal marked "not reviewed" will be returned with an explanation of the reason it is not reviewed. Resubmit submittals returned for lack of review by Contractor or for being incomplete, with appropriate action, coordination, or change.

1.10 DISAPPROVED SUBMITTALS

If changes are necessary to submittals, the Contractor shall make such revisions and submission of the submittals in accordance with the procedures above. No item of work requiring a submittal change is to be

accomplished until the changed submittals are approved.

1.11 APPROVED SUBMITTALS

The Contracting Officer's approval or acceptance of submittals is not be construed as a complete check, and indicates only that the general method of construction, materials, detailing and other information are satisfactory design, general method of construction, materials, detailing and other information appear to meet the Solicitation and Accepted Proposal. Approval or acceptance will not relieve the Contractor of the responsibility for any error which may exist, as the Contractor is responsible for dimensions, the design of adequate connections and details, and the satisfactory construction of all work. After submittals have been approved or accepted by the Contracting Officer, no resubmittal for the purpose of substituting materials or equipment will be considered unless accompanied by an explanation of why a substitution is necessary.

1.12 APPROVED SAMPLES

Approval of a sample is only for the characteristics or use named in such approval and is not be construed to change or modify any contract requirements. Before submitting samples, the Contractor to assure that the materials or equipment will be available in quantities required in the project. No change or substitution will be permitted after a sample has been approved.

Match the approved samples for Materials and equipment incorporated in the work. If requested, approved samples, including those which may be damaged in testing, will be returned to the Contractor, at his expense, upon completion of the contract. Samples not approved will also be returned to the Contractor at its expense, if so requested.

Failure of any materials to pass the specified tests will be sufficient cause for refusal to consider, under this contract, any further samples of the same brand or make of that material. Government reserves the right to disapprove any material or equipment which previously has proved unsatisfactory in service.

Samples of various materials or equipment delivered on the site or in place may be taken by the Contracting Officer for testing. Samples failing to meet contract requirements will automatically void previous approvals. Contractor to replace such materials or equipment to meet contract requirements.

Approval of the Contractor's samples by the Contracting Officer does not relieve the Contractor of his responsibilities under the contract.

1.13 STATUS REPORT ON MATERIALS ORDERS

Within 30 calendar days after notice to proceed, submit, for approval by the Contracting Officer, an initial material status report on all materials orders. This report will be updated and re-submitted every 30 calendar days as the status on material orders changes.

Report to include list, in chronological order by need date, materials orders necessary for completion of the contract. The following information will be required for each material order listed:

- a. Material name, supplier, and invoice number.
- b. Bar chart line item or CPM activity number affected by the order.
- c. Delivery date needed to allow directly and indirectly related work to be completed within the contract performance period.
- d. Current delivery date agreed on by supplier.
- e. When item d exceeds item c, the effect that delayed delivery date will have on contract completion date.
- f. When item d exceeds item c, a summary of efforts made by the Contractor to expedite the delayed delivery date to bring it in line with the needed delivery date, including efforts made to place the order (or subcontract) with other suppliers.

PART 2 PRODUCTS

Not Used

PART 3 EXECUTION

Not Used

-- End of Section --

SECTION TABLE OF CONTENTS

DIVISION 01 - GENERAL REQUIREMENTS

SECTION 01 35 26

GOVERNMENTAL SAFETY REQUIREMENTS

PART 1 GENERAL

- 1.1 REFERENCES
- 1.2 SUBMITTALS
- 1.3 DEFINITIONS
- 1.4 REGULATORY REQUIREMENTS
- 1.5 SITE QUALIFICATIONS, DUTIES AND MEETINGS
 - 1.5.1 Personnel Qualifications
 - 1.5.1.1 Site Safety and Health Officer (SSHO)
 - 1.5.1.2 Construction Safety Hazard Awareness Training
 - 1.5.1.3 Competent Person for Confined Space Entry
 - 1.5.1.4 Crane Operators
 - 1.5.2 Personnel Duties
 - 1.5.2.1 Site Safety and Health Officer (SSHO)
 - 1.5.3 Meetings
 - 1.5.3.1 Preconstruction Conference
 - 1.5.3.2 Safety Meetings
- 1.6 DISPLAY OF SAFETY INFORMATION
- 1.7 SITE SAFETY REFERENCE MATERIALS
- 1.8 EMERGENCY MEDICAL TREATMENT
- 1.9 REPORTS
 - 1.9.1 Accident Reports
 - 1.9.2 Accident Notification
 - 1.9.3 Crane Reports
 - 1.9.4 Certificate of Compliance
- 1.10 HOT WORK
- 1.11 FACILITY OCCUPANCY CLOSURE
- 1.12 WELDING
- 1.13 HIGH NOISE LEVEL PROTECTION
- 1.14 SEVERE STORM PLAN
- 1.15 CONFINED SPACE ENTRY REQUIREMENTS

PART 2 PRODUCTS

- 2.1 CONFINED SPACE SIGNAGE
- 2.2 FALL PROTECTION ANCHORAGE

PART 3 EXECUTION

- 3.1 CONSTRUCTION AND/OR OTHER WORK
- 3.2 PRE-OUTAGE COORDINATION MEETING
- 3.3 CONTROL OF HAZARDOUS ENERGY (LOCKOUT/TAGOUT)
 - 3.3.1 Tag Placement
 - 3.3.2 Tag Removal
- 3.4 FALL HAZARD PROTECTION AND PREVENTION PROGRAM
 - 3.4.1 Training

- 3.4.2 Fall Protection Equipment and Systems
 - 3.4.2.1 Personal Fall Arrest Equipment
- 3.4.3 Fall Protection for Roofing Work
- 3.4.4 Existing Anchorage
- 3.4.5 Horizontal Lifelines
- 3.4.6 Guardrails and Safety Nets
- 3.4.7 Rescue and Evacuation Procedures
- 3.5 SCAFFOLDING
 - 3.5.1 Stilts
- 3.6 EQUIPMENT
 - 3.6.1 Material Handling Equipment
 - 3.6.2 Weight Handling Equipment
 - 3.6.3 Equipment and Mechanized Equipment
 - 3.6.4 USE OF EXPLOSIVES
- 3.7 EXCAVATIONS
 - 3.7.1 Utility Locations
 - 3.7.2 Utility Location Verification
 - 3.7.3 Shoring Systems
 - 3.7.4 Trenching Machinery
- 3.8 UTILITIES WITHIN CONCRETE SLABS
- 3.9 ELECTRICAL
 - 3.9.1 Conduct of Electrical Work
 - 3.9.2 Portable Extension Cords
- 3.10 WORK IN CONFINED SPACES

-- End of Section Table of Contents --

SECTION 01 35 26

GOVERNMENTAL SAFETY REQUIREMENTS

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

ASME INTERNATIONAL (ASME)

ASME B30.22	(2005) Articulating Boom Cranes
ASME B30.3	(2009) Construction Tower Cranes
ASME B30.5	(2007) Mobile and Locomotive Cranes

NATIONAL AERONAUTICS AND SPACE ADMINISTRATION (NASA)

NASA NPG 8621.1	(2004a) NASA Mishap Reporting, Investigating and Record Keeping Policy
NASA NSS 1740.12	(1993) NASA Safety Standard For Explosives, Propellants and Pyrotechnics

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 10	(2007; Errata 2007; AMD 1 2007) Standard for Portable Fire Extinguishers
NFPA 51B	(2009) Standard for Fire Prevention During Welding, Cutting, and Other Hot Work
NFPA 70	(2008; AMD 1 2008) National Electrical Code - 2008 Edition
NFPA 70E	(2009; Errata 2009) Standard for Electrical Safety in the Workplace

U.S. NATIONAL ARCHIVES AND RECORDS ADMINISTRATION (NARA)

29 CFR 1910.146	Permit-required Confined Spaces
29 CFR 1926	Safety and Health Regulations for Construction
29 CFR 1926.500	Fall Protection

1.2 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for Contractor Quality Control approval. Submit the following in accordance with Section 01 33 00

SUBMITTAL PROCEDURES:

Government acceptance is required for submittals with a "G" designation.

SD-01 Preconstruction Submittals

Safety and Health Plan; G

Proof of qualification for Crane Operators; G

SD-06 Test Reports

Reports

Submit reports as their incidence occurs, in accordance with the requirements of the paragraph entitled, "Reports."

Accident Reports

Crane Reports

SD-07 Certificates

Confined Space Entry Permit

Hot work permit

Certificate of Compliance (Crane)

1.3 DEFINITIONS

- a. Competent Person for Fall Protection. A person who is capable of identifying hazardous or dangerous conditions in the personal fall arrest system or any component thereof, as well as their application and use with related equipment, and has the authority to take prompt corrective measures to eliminate the hazards of falling.
- b. High Visibility Accident. Any mishap which may generate publicity and/or high visibility.
- c. Medical Treatment. Treatment administered by a physician or by registered professional personnel under the standing orders of a physician. Medical treatment does not include first aid treatment even through provided by a physician or registered personnel.
- d. Operating Envelope. The area surrounding any crane. Inside this "envelope" is the crane, the operator, riggers and crane walkers, rigging gear between the hook and the load, the load and the crane's supporting structure (ground, rail, etc.).
- e. Qualified Person for Fall Protection. A person with a recognized degree or professional certificate, and with extensive knowledge, training and experience in the field of fall protection; who is capable of performing design, analysis, and evaluation of fall protection systems and equipment.
- f. Recordable Injuries or Illnesses. Any work-related injury or illness that results in:

- (1) Death, regardless of the time between the injury and death, or the length of the illness;
 - (2) Days away from work (any time lost after day of injury/illness onset);
 - (3) Restricted work;
 - (4) Transfer to another job;
 - (5) Medical treatment beyond first aid;
 - (6) Loss of consciousness; or
 - (7) A significant injury or illness diagnosed by a physician or other licensed health care professional, even if it did not result in (1) through (6) above.
- h. Weight Handling Equipment (WHE) Accident. A WHE accident occurs when any one or more of the six elements in the operating envelope fails to perform correctly during operation, including operation during maintenance or testing resulting in personnel injury or death; material or equipment damage; dropped load; derailment; two-blocking; overload; and/or collision, including unplanned contact between the load, crane, and/or other objects. A dropped load, derailment, two-blocking, overload and collision are considered accidents even though no material damage or injury occurs. A component failure (e.g., motor burnout, gear tooth failure, bearing failure) is not considered an accident solely due to material or equipment damage unless the component failure results in damage to other components (e.g., dropped boom, dropped load, roll over, etc.)

1.4 REGULATORY REQUIREMENTS

In addition to the detailed requirements included in the provisions of this contract, comply with the most recent addition of federal, state, and local laws, ordinances, criteria, rules and regulations. Submit matters of interpretation of standards to the appropriate administrative agency for resolution before starting work. Where the requirements of this specification, applicable laws, criteria, ordinances, regulations, and referenced documents vary, the most stringent requirements govern.

1.5 SITE QUALIFICATIONS, DUTIES AND MEETINGS

1.5.1 Personnel Qualifications

1.5.1.1 Site Safety and Health Officer (SSHO)

The contractor shall provide a Safety oversight team that includes a minimum of one (1) Competent Person at each project site to function as the Site Safety and Health Officer (SSHO). The SSHO shall be at the work site at all times, unless specified differently in the contract, to perform safety and occupational health management, surveillance, inspections, and safety enforcement for the Contractor, and their training, experience, and qualifications. A Competent Personal shall be provided for all of the hazards identified in the Contractor's Safety and Health Program in accordance with the accepted Accident Prevention Plan, and shall be on-site at all times when the work that presents the hazards associated with their professional expertise is being performed. The credentials of the

Competent Persons(s) shall be approved by the Contracting Officer in consultation with the Safety Office.

1.5.1.2 Construction Safety Hazard Awareness Training

The training requirements for the Site Safety and Health Officer (SSHO) must include the successful completion of the course entitled "Construction Safety Hazard Awareness Training for Contractors". If the SSHO does not have a current certification, they must obtain the course certification within sixty (60) calendar days from award.

1.5.1.3 Competent Person for Confined Space Entry

Provide a competent person for confined space.

1.5.1.4 Crane Operators

For mobile cranes with Original Equipment Manufacturer (OEM) rated capacities of 50,000 pounds or greater, designate crane operators as qualified by a source that qualifies crane operators (i.e., union, a government agency, or an organization that tests and qualifies crane operators). Provide proof of current qualification.

1.5.2 Personnel Duties

1.5.2.1 Site Safety and Health Officer (SSHO)

- a. Conduct daily safety and health inspections and maintain a written log which includes area/operation inspected, date of inspection, identified hazards, recommended corrective actions, estimated and actual dates of corrections. Attach safety inspection logs to the Contractors' daily production report.
- b. Conduct mishap investigations and complete required reports. Maintain the OSHA Form 300 and Daily Production reports for prime and sub-contractors.
- c. Maintain applicable safety reference material on the job site.
- d. Attend the pre-construction conference, pre-work meetings including preparatory inspection meeting, and periodic in-progress meetings.
- e. Implement and enforce accepted APPS and AHAs.
- f. Maintain a safety and health deficiency tracking system that monitors outstanding deficiencies until resolution. Post a list of unresolved safety and health deficiencies on the safety bulletin board.
- g. Ensure sub-contractor compliance with safety and health requirements.

Failure to perform the above duties will result in dismissal of the superintendent, QC Manager, and/or SSHO, and a project work stoppage. The project work stoppage will remain in effect pending approval of a suitable replacement.

- h. Maintain a list of hazardous chemicals on site and their material safety data sheets.

1.5.3 Meetings

1.5.3.1 Preconstruction Conference

- a. Contractor representatives who have a responsibility or significant role in accident prevention on the project shall attend the preconstruction conference. This includes the project superintendent, site safety and health officer, or any other assigned safety and health professionals who participated in the development of the APP Safety and Health Plan.
- b. Discuss the details of the submitted Safety and Health Plan.
- c. Deficiencies in the submitted Safety and Health Plan will be brought to the attention of the Contractor at the preconstruction conference, and the Contractor shall revise the plan to correct deficiencies and re-submit it for acceptance. Do not begin work until there is an accepted Safety and Health Plan.

1.5.3.2 Safety Meetings

Conduct and document meetings daily as required. Attach minutes showing contract title, signatures of attendees and a list of topics discussed to the Contractors' daily production report.

1.6 DISPLAY OF SAFETY INFORMATION

Within 1 calendar days after commencement of work, erect a safety bulletin board at the job site. Where size, duration, or logistics of project do not facilitate a bulletin board, an alternative method, acceptable to the Contracting Officer, that is accessible and includes all mandatory information for employee and visitor review, shall be deemed as meeting the requirement for a bulletin board. Additional items required to be posted include:

- a. Confined space entry permit.
- b. Hot work permit.

1.7 SITE SAFETY REFERENCE MATERIALS

Maintain safety-related references applicable to the project, including those listed in the article "References." Maintain applicable equipment manufacturer's manuals.

1.8 EMERGENCY MEDICAL TREATMENT

Emergency medical treatment is available to the Contractor by calling 321-867-7911. Medical facilities are located in the VAB area and Industrial Area as shown below.

Medical	
Occupational Health Facility 2nd and C Avenue Hours: 7:00 a.m. to 5:00 p.m., Mon-Fri	321-867-3346

Medical	
LC 39 Area Clinic Utility Road and VAB Road Hours: 7:00 a.m. to 3:30 p.m., Mon-Fri	321-867-3360

1.9 REPORTS

1.9.1 Accident Reports

- a. Conduct an accident investigation for recordable injuries and illnesses, as defined in 1.3.h and property damage accidents resulting in at least \$2,000 in damages, to establish the root cause(s) of the accident and provide the report to the Contracting Officer within 5 calendar day(s) of the accident. The Contracting Officer will provide copies of any required or special forms.
- b. Conduct an accident investigation for any weight handling equipment accident (including rigging gear accidents) to establish the root cause(s) of the accident, complete the WHE Accident Report (Crane and Rigging Gear) form and provide the report to the Contracting Officer within 30 calendar days of the accident. Do not proceed with crane operations until cause is determined and corrective actions have been implemented to the satisfaction of the contracting officer. The Contracting Officer will provide a blank copy of the accident report form.

1.9.2 Accident Notification

Notify the Contracting Officer as soon as practical, but not later than four hours, after any accident meeting the definition of Recordable Injuries or Illnesses or High Visibility Accidents, property damage equal to or greater than \$2,000, or any weight handling equipment accident in accordance with NASA NPG 8621.1. Within notification include contractor name; contract title; type of contract; name of activity, installation or location where accident occurred; date and time of accident; names of personnel injured; extent of property damage, if any; extent of injury, if known, and brief description of accident (to include type of construction equipment used, PPE used, etc.). Preserve the conditions and evidence on the accident site until the Government investigation team arrives on-site and Government investigation is conducted.

1.9.3 Crane Reports

Submit crane inspection reports as specified herein with Daily Reports of Inspections.

1.9.4 Certificate of Compliance

Provide a Certificate of Compliance for each crane entering an activity under this contract. State within the certificate that the crane and rigging gear meet applicable OSHA regulations (with the Contractor citing which OSHA regulations are applicable, e.g., cranes used in construction, demolition, or maintenance comply with 29 CFR 1926. Certify on the Certificate of Compliance that the crane operator(s) is qualified and trained in the operation of the crane to be used.

1.10 HOT WORK

Submit and obtain a written permit prior to performing "Hot Work" (welding, cutting, etc.) or operating other flame-producing/spark producing devices, from the Fire Division. A permit is required from the Explosives Safety Office for work in and around where explosives are processed, stored, or handled. CONTRACTORS ARE REQUIRED TO MEET ALL CRITERIA BEFORE A PERMIT IS ISSUED. The Contractor will provide at least two (2) twenty (20) pound 4A:20 BC rated extinguishers for normal "Hot Work". All extinguishers shall be current inspection tagged, approved safety pin and tamper resistant seal. It is also mandatory to have a designated FIRE WATCH for any "Hot Work" done at this activity. The Fire Watch shall be trained in accordance with NFPA 51B and remain on-site for a minimum of 30 minutes after completion of the task or as specified on the hot work permit.

When starting work in the facility, require personnel to familiarize themselves with the location of the nearest fire alarm boxes and place in memory the emergency Fire Division phone number. ANY FIRE, NO MATTER HOW SMALL, SHALL BE REPORTED IMMEDIATELY.

1.11 FACILITY OCCUPANCY CLOSURE

Streets, walks, and other facilities occupied and used by the Government shall not be closed or obstructed without written permission from the Contracting Officer.

1.12 WELDING

Toxic paint may exist on metals. Contractor shall require their employees to wear the proper PPE during welding activities.

1.13 HIGH NOISE LEVEL PROTECTION

Operations performed by the Contractor that involve the use of equipment with output of high noise levels (jackhammers, air compressors, and explosive-actuated devices) shall be scheduled with the Facility Manager. Use of any such equipment shall be approved in writing by the Contracting Officer prior to commencement of work.

1.14 SEVERE STORM PLAN

In the event of a severe storm warning, the Contractor must:

- a. Secure outside equipment and materials and place materials that could be damaged in protected areas.
- b. Check surrounding area, including roof, for loose material, equipment, debris, and other objects that could be blown away or against existing facilities.
- c. Ensure that temporary erosion controls are adequate.

1.15 CONFINED SPACE ENTRY REQUIREMENTS

Contractors entering and working in confined spaces performing general industry work are required to follow the requirements of OSHA 29 CFR 1926.

PART 2 PRODUCTS

Not used.

2.1 CONFINED SPACE SIGNAGE

Provide permanent signs integral to or securely attached to access covers for new permit-required confined spaces. Signs wording: "DANGER--PERMIT-REQUIRED CONFINED SPACE - DO NOT ENTER -" in bold letters a minimum of one inch in height and constructed to be clearly legible with all paint removed. The signal word "DANGER" shall be red and readable from 5 feet.

2.2 FALL PROTECTION ANCHORAGE

Leave in place fall protection anchorage, conforming to 29 CFR 1926, installed under the supervision of a qualified person in fall protection, for continued customer use and so identified by signage stating the capacity of the anchorage (strength and number of persons who may be tied-off to it at any one time).

PART 3 EXECUTION

3.1 CONSTRUCTION AND/OR OTHER WORK

Comply with Federal and/or State OSHA regulations, and other related submittals and activity fire and safety regulations. The most stringent standard prevails.

3.2 PRE-OUTAGE COORDINATION MEETING

Contractors are required to apply for utility outages at least 14 days in advance. As a minimum, the request should include the location of the outage, utilities being affected, duration of outage and any necessary sketches. Special requirements for electrical outage requests are contained elsewhere in this specification section. Once approved, and prior to beginning work on the utility system requiring shut down, attend a pre-outage coordination meeting with the Contracting Officer to review the scope of work and the lock-out/tag-out procedures for worker protection. No work will be performed on energized electrical circuits unless proof is provided that no other means exist.

3.3 CONTROL OF HAZARDOUS ENERGY (LOCKOUT/TAGOUT)

Contractor shall ensure that each employee is familiar with and complies with these procedures.

Contracting Officer will, at the Contractor's request, apply lockout/tagout tags and take other actions that, because of experience and knowledge, are known to be necessary to make the particular equipment safe to work on for government owned and operated systems.

No person, regardless of position or authority, shall operate any switch, valve, or equipment that has an official lockout/tagout tag attached to it, nor shall such tag be removed except as provided in this section. No person shall work on any energized equipment including, but not limited to activities such as erecting, installing, constructing, repairing, adjusting, inspecting, un-jamming, setting up, trouble shooting, testing, cleaning, dismantling, servicing and maintaining machines equipment of

processes until an evaluation has been conducted identifying the energy source and the procedures which will be taken to ensure the safety of personnel.

When work is to be performed on electrical circuits, only qualified personnel shall perform work on electrical circuits.

A supervisor who is required to enter an area protected by a lockout/tagout tag will be considered a member of the protected group provided he notifies the holder of the tag stub each time he enters and departs from the protected area.

Identification markings on building light and power distribution circuits shall not be relied on for established safe work conditions.

Before clearance will be given on any equipment other than electrical (generally referred to as mechanical apparatus), the apparatus, valves, or systems shall be secured in a passive condition with the appropriate vents, pins, and locks.

Pressurized or vacuum systems shall be vented to relieve differential pressure completely.

Vent valves shall be tagged open during the course of the work.

Where dangerous gas or fluid systems are involved, or in areas where the environment may be oxygen deficient, system or areas shall be purged, ventilated, or otherwise made safe prior to entry.

3.3.1 Tag Placement

Lockout/tagout tags shall be completed in accordance with the regulations printed on the back thereof and attached to any device which, if operated, could cause an unsafe condition to exist.

If more than one group is to work on any circuit or equipment, the employee in charge of each group shall have a separate set of lockout/tagout tags completed and properly attached.

When it is required that certain equipment be tagged, the Government will review the characteristics of the various systems involved that affect the safety of the operations and the work to be done; take the necessary actions, including voltage and pressure checks, grounding, and venting, to make the system and equipment safe to work on; and apply such lockout/tagout tags to those switches, valves, vents, or other mechanical devices needed to preserve the safety provided. This operation is referred to as "Providing Safety Clearance."

3.3.2 Tag Removal

When any individual or group has completed its part of the work and is clear of the circuits or equipment, the supervisor, project leader, or individual for whom the equipment was tagged shall turn in his signed lockout/tagout tag stub to the Contracting Officer. That group's or individual's lockout/tagout tags on equipment may then be removed on authorization by the Contracting Officer.

3.4 FALL HAZARD PROTECTION AND PREVENTION PROGRAM

Establish a fall protection and prevention program, for the protection of all employees exposed to fall hazards. Within the program include company policy, identify responsibilities, education and training requirements, fall hazard identification, prevention and control measures, inspection, storage, care and maintenance of fall protection equipment and rescue and evacuation procedures.

3.4.1 Training

Institute a fall protection training program. As part of the Fall Hazard Protection and Prevention Program, provide training for each employee who might be exposed to fall hazards. Provide training by a competent person for fall protection in accordance with 29 CFR 1926.

3.4.2 Fall Protection Equipment and Systems

Enforce use of the fall protection equipment and systems designated for each specific work activity in the Fall Protection and Prevention Plan at all times when an employee is exposed to a fall hazard. Protect employees from fall hazards as specified in 29 CFR 1926. Personal fall arrest systems are required when working from an articulating or extendible boom, swing stages, or suspended platform. In addition, personal fall arrest systems are required when operating other equipment such as scissor lifts if the work platform is capable of being positioned outside the wheelbase. The need for tying-off in such equipment is to prevent ejection of the employee from the equipment during raising, lowering, or travel. Fall protection must comply with 29 CFR 1926.500, Subpart M.

3.4.2.1 Personal Fall Arrest Equipment

Personal fall arrest equipment, systems, subsystems, and components shall meet 29 CFR 1926. Only a full-body harness with a shock-absorbing lanyard or self-retracting lanyard is an acceptable personal fall arrest body support device. Body belts may only be used as a positioning device system (for uses such as steel reinforcing assembly and in addition to an approved fall arrest system). Harnesses shall have a fall arrest attachment affixed to the body support (usually a Dorsal D-ring) and specifically designated for attachment to the rest of the system. Only locking snap hooks and carabiners shall be used. Webbing, straps, and ropes shall be made of synthetic fiber. The maximum free fall distance when using fall arrest equipment shall not exceed 6 feet. The total fall distance and any swinging of the worker (pendulum-like motion) that can occur during a fall shall always be taken into consideration when attaching a person to a fall arrest system.

3.4.3 Fall Protection for Roofing Work

Implement fall protection controls based on the type of roof being constructed and work being performed. Evaluate the roof area to be accessed for its structural integrity including weight-bearing capabilities for the projected loading.

a. Low Sloped Roofs:

- (1) For work within 6 feet of an edge, on low-slope roofs, Protect personnel from falling by use of personal fall arrest systems, guardrails, or safety nets. A safety monitoring system is not

adequate fall protection and is not authorized.

- (2) For work greater than 6 feet from an edge, erect and install warning lines in accordance with 29 CFR 1926.500.

- b. Steep-Sloped Roofs: Work on steep-sloped roofs requires a personal fall arrest system, guardrails with toe-boards, or safety nets. This requirement also includes residential or housing type construction.

3.4.4 Existing Anchorage

Certified (or re-certified) by a qualified person for fall protection existing anchorages, to be used for attachment of personal fall arrest equipment in accordance with 29 CFR 1926. Existing horizontal lifeline anchorages must be certified (or re-certified) by a registered professional engineer with experience in designing horizontal lifeline systems.

3.4.5 Horizontal Lifelines

Design, install, certify and use under the supervision of a qualified person horizontal lifelines for fall protection as part of a complete fall arrest system which maintains a safety factor of 2 (29 CFR 1926.500).

3.4.6 Guardrails and Safety Nets

Design, install and use guardrails and safety nets in accordance with 29 CFR 1926 Subpart M.

3.4.7 Rescue and Evacuation Procedures

When personal fall arrest systems are used, the contractor must ensure that the mishap victim can self-rescue or can be rescued promptly should a fall occur. Prepare a Rescue and Evacuation Plan and include a detailed discussion of the following: methods of rescue; methods of self-rescue; equipment used; training requirement; specialized training for the rescuers; procedures for requesting rescue and medical assistance; and transportation routes to a medical facility. Include the Rescue and Evacuation Plan within the Fall Protection and Prevention (FP&P) Plan and the Safety and Health Plan.

3.5 SCAFFOLDING

Provide employees with a safe means of access to the work area on the scaffold. Climbing of any scaffold braces or supports not specifically designed for access is prohibited. Access scaffold platforms greater than 20 feet maximum in height by use of a scaffold stair system. Do not use vertical ladders commonly provided by scaffold system manufacturers for accessing scaffold platforms greater than 20 feet maximum in height. The use of an adequate gate is required. Ensure that employees are qualified to perform scaffold erection and dismantling. Do not use scaffold without the capability of supporting at least four times the maximum intended load or without appropriate fall protection as delineated in the accepted fall protection and prevention plan. Stationary scaffolds must be attached to structural building components to safeguard against tipping forward or backward. Give special care to ensure scaffold systems are not overloaded. Side brackets used to extend scaffold platforms on self-supported scaffold systems for the storage of material is prohibited. The first tie-in shall be at the height equal to 4 times the width of the smallest dimension of the scaffold base. Place work platforms on mud

sills. Scaffold or work platform erectors shall have fall protection during the erection and dismantling of scaffolding or work platforms that are more than six feet. Delineate fall protection requirements when working above six feet or above dangerous operations in the Fall Protection and Prevention (FP&P) Plan and the Safety and Health Plan for the phase of work.

3.5.1 Stilts

The use of stilts for gaining additional height in construction, renovation, repair or maintenance work is prohibited.

3.6 EQUIPMENT

3.6.1 Material Handling Equipment

- a. Material handling equipment such as forklifts shall not be modified with work platform attachments for supporting employees unless specifically delineated in the manufacturer's printed operating instructions.
- b. The use of hooks on equipment for lifting of material must be in accordance with manufacturer's printed instructions.
- c. Operators of forklifts or power industrial trucks shall be licensed in accordance with OSHA.

3.6.2 Weight Handling Equipment

- a. Notify the Contracting Officer 15 days in advance of any cranes entering the activity so that necessary quality assurance spot checks can be coordinated. Contractor's operator shall remain with the crane during the spot check.
- b. Comply with the crane manufacturer's specifications and limitations for erection and operation of cranes and hoists used in support of the work. Perform erection under the supervision of a designated person (as defined in ASME B30.5). Perform all testing in accordance with the manufacturer's recommended procedures.
- c. Comply with ASME B30.5 for mobile and locomotive cranes, ASME B30.22 for articulating boom cranes, and ASME B30.3 for construction tower cranes.
- d. Under no circumstance shall a Contractor make a lift at or above 90 percent of the cranes rated capacity in any configuration.
- e. When operating in the vicinity of overhead transmission lines, operators and riggers shall be alert to this special hazard and follow the requirements of OSHA and ASME B30.5 or ASME B30.22 as applicable.
- f. Do not crane suspended personnel work platforms (baskets) unless the Contractor proves that using any other access to the work location would provide a greater hazard to the workers or is impossible. Do not lift personnel with a line hoist or friction crane.
- g. Inspect, maintain, and recharge portable fire extinguishers as specified in NFPA 10, Standard for Portable Fire Extinguishers.

- h. All employees must keep clear of loads about to be lifted and of suspended loads.
 - i. Use cribbing when performing lifts on outriggers.
 - j. The crane hook/block must be positioned directly over the load. Side loading of the crane is prohibited.
 - k. A physical barricade must be positioned to prevent personnel from entering the counterweight swing (tail swing) area of the crane.
 - l. Certification records which include the date of inspection, signature of the person performing the inspection, and the serial number or other identifier of the crane that was inspected shall always be available for review by Contracting Officer personnel.
 - m. Written reports listing the load test procedures used along with any repairs or alterations performed on the crane shall be available for review by Contracting Officer personnel.
 - n. Certify that all crane operators have been trained in proper use of all safety devices (e.g. anti-two block devices).
 - o. Take steps to ensure that wind speed does not contribute to loss of control of the load during lifting operations. Prior to conducting lifting operations set a maximum wind speed at which a crane can be safely operated based on the equipment being used, the load being lifted, experience of operators and riggers, and hazards on the work site. This maximum wind speed determination shall be included as part of the activity hazard analysis plan for that operation.
- 3.6.3 Equipment and Mechanized Equipment
- a. Proof of qualifications for operator shall be kept on the project site for review.
 - b. Manufacture specifications or owner's manual for the equipment shall be on-site and reviewed for additional safety precautions or requirements that are sometimes not identified by OSHA.

3.6.4 USE OF EXPLOSIVES

Explosives shall not be used or brought to the project site without prior written approval from the Contracting Officer. Such approval shall not relieve the Contractor of responsibility for injury to persons or for damage to property due to blasting operations.

Storage of explosives, when permitted on Government property, shall be only where directed and in approved storage facilities. These facilities shall be kept locked at all times except for inspection, delivery, and withdrawal of explosives.

Explosive work shall be performed in accordance with NASA NSS 1740.12. This document is available at:

<http://www.hq.nasa.gov/office/codeq/doctree/871912.htm>

3.7 EXCAVATIONS

Perform soil classification by a competent person in accordance with 29 CFR 1926.

3.7.1 Utility Locations

Prior to digging, the appropriate digging permit must be obtained. All underground utilities in the work area must be positively identified by a private utility locating service in addition to any station locating service and coordinated with the station utility department. Any markings made during the utility investigation must be maintained throughout the contract.

3.7.2 Utility Location Verification

The Contractor must physically verify underground utility locations by hand digging using wood or fiberglass handled tools when any adjacent construction work is expected to come within three feet of the underground system. Digging within 2 feet of a known utility must not be performed by means of mechanical equipment; hand digging shall be used. If construction is parallel to an existing utility expose the utility by hand digging every 100 feet if parallel within 5 feet of the excavation.

3.7.3 Shoring Systems

Trench and shoring systems must be identified in the accepted safety plan. Manufacture tabulated data and specifications or registered engineer tabulated data for shoring or benching systems shall be readily available on-site for review. Job-made shoring or shielding must have the registered professional engineer stamp, specifications, and tabulated data. Extreme care must be used when excavating near direct burial electric underground cables.

3.7.4 Trenching Machinery

Operate trenching machines with digging chain drives only when the spotters/laborers are in plain view of the operator. Provide operator and spotters/laborers training on the hazards of the digging chain drives with emphasis on the distance that needs to be maintained when the digging chain is operating. Keep documentation of the training on file at the project site.

3.8 UTILITIES WITHIN CONCRETE SLABS

Utilities located within concrete slabs are extremely difficult to identify due to the reinforcing steel used in the construction of these structures. Whenever contract work involves concrete chipping, saw cutting, or core drilling, the existing utility location must be coordinated with utility departments. Outages to isolate utility systems must be used in circumstances where utilities are unable to be positively identified. The use of historical drawings does not alleviate the contractor from meeting this requirement.

3.9 ELECTRICAL

3.9.1 Conduct of Electrical Work

Underground electrical spaces must be certified safe for entry before

entering to conduct work. Cables that will be cut must be positively identified and de-energized prior to performing each cut. Positive cable identification must be made prior to submitting any outage request for electrical systems. Arrangements are to be coordinated with the Contracting Officer and Station Utilities for identification. The Contracting Officer will not accept an outage request until the Contractor satisfactorily documents that the circuits have been clearly identified. Perform all high voltage cable cutting remotely using hydraulic cutting tool. When racking in or live switching of circuit breakers, no additional person other than the switch operator will be allowed in the space during the actual operation. Plan so that work near energized parts is minimized to the fullest extent possible. Use of electrical outages clear of any energized electrical sources is the preferred method. When working in energized substations, only qualified electrical workers will be permitted to enter. When work requires the Contractor to work near energized circuits as defined by the NFPA 70, high voltage personnel must use personal protective equipment that includes, as a minimum, electrical hard hat, safety shoes, insulating gloves with leather protective sleeves, fire retarding shirts, coveralls, face shields, and safety glasses. In addition, provide electrical arc flash protection for personnel as required by NFPA 70E. Insulating blankets, hearing protection, and switching suits may also be required, depending on the specific job and as delineated in the Contractor's Safety and Health Plan.

3.9.2 Portable Extension Cords

Size portable extension cords in accordance with manufacturer ratings for the tool to be powered and protected from damage. Immediately removed from service all damaged extension cords. Portable extension cords shall meet the requirements of NFPA 70E and OSHA electrical standards.

3.10 WORK IN CONFINED SPACES

Comply with the requirements in OSHA 29 CFR 1910.146 and OSHA 29 CFR 1926.21(b)(6). Any potential for a hazard in the confined space requires a permit system to be used.

- a. Entry Procedures. Prohibit entry into a confined space by personnel for any purpose, including hot work, until the qualified person has conducted appropriate tests to ensure the confined or enclosed space is safe for the work intended and that all potential hazards are controlled or eliminated and documented. All hazards pertaining to the space shall be reviewed with each employee during review of the Safety and Health Plan.
- b. Forced air ventilation is required for all confined space entry operations and the minimum air exchange requirements must be maintained to ensure exposure to any hazardous atmosphere is kept below its' action level.
- c. All underground structures require continuous atmosphere monitoring with audible alarm for toxic gas detection.

-- End of Section --

SECTION TABLE OF CONTENTS

DIVISION 01 - GENERAL REQUIREMENTS

SECTION 01 42 00

SOURCES FOR REFERENCE PUBLICATIONS

PART 1 GENERAL

1.1 REFERENCES

1.2 ORDERING INFORMATION

-- End of Section Table of Contents --

SECTION 01 42 00

SOURCES FOR REFERENCE PUBLICATIONS

PART 1 GENERAL

1.1 REFERENCES

Various publications are referenced in other sections of the specifications to establish requirements for the work. These references are identified in each section by document number, date and title. The document number used in the citation is the number assigned by the standards producing organization, (e.g. ASTM B 564 Nickel Alloy Forgings). However, when the standards producing organization has not assigned a number to a document, an identifying number has been assigned for reference purposes.

1.2 ORDERING INFORMATION

The addresses of the standards publishing organizations whose documents are referenced in other sections of these specifications are listed below, and if the source of the publications is different from the address of the sponsoring organization, that information is also provided. Documents listed in the specifications with numbers which were not assigned by the standards producing organization should be ordered from the source by title rather than by number.

AIR-CONDITIONING AND REFRIGERATION INSTITUTE (ARI)
4301 North Fairfax Drive
Suite 425
Arlington, VA 22203
Ph: 703-524-8800
Fax: 703-523-3816
E-mail: hhwong@ari.org
Internet:

AMERICAN ASSOCIATION OF STATE HIGHWAY AND TRANSPORTATION OFFICIALS
(AASHTO)
444 North Capital Street, NW, Suite 249
Washington, DC 20001
Ph: 202-624-5800
Fax: 202-624-5806
E-Mail: info@aaashto.org
Internet: <http://www.aashto.org>

AMERICAN NATIONAL STANDARDS INSTITUTE (ANSI)
1819 L Street, NW, 6th Floor
Washington, DC 20036
Ph: 202-293-8020
Fax: 202-293-9287
E-mail: info@ansi.org
Internet: <http://www.ansi.org/>

AMERICAN SOCIETY OF SAFETY ENGINEERS (ASSE/SAFE)
1800 East Oakton Street
Des Plaines, IL 60018-2187

Ph: 847-699-2929
Fax: 847-768-3434
E-mail: customerservice@asse.org
Internet: <http://www.asse.org>

AMERICAN WATER WORKS ASSOCIATION (AWWA)
6666 West Quincy Avenue
Denver, CO 80235
Ph: 800-926-7337
Fax: 303-347-0804
Internet: <http://www.awwa.org>

ASME INTERNATIONAL (ASME)
Three Park Avenue, M/S 10E
New York, NY 10016
Ph: 212-591-7722 or 800-843-2763
Fax: 212-591-7674
E-mail: infocentral@asme.org
Internet: <http://www.asme.org>

ASTM INTERNATIONAL (ASTM)
100 Barr Harbor Drive, P.O. Box C700
West Conshohocken, PA 19428-2959
Ph: 610-832-9500
Fax: 610-832-9555
E-mail: service@astm.org
Internet: <http://www.astm.org>

COMPRESSED GAS ASSOCIATION (CGA)
4221 Walney Road, 5th Floor
Chantilly, VA 20151-2923
Ph: 703-788-2700
Fax: 703-961-1831
E-mail: cga@cganet.com
Internet: <http://www.cganet.com>

FLORIDA ADMINISTRATIVE CODE (FAC)
R.A. Gray Building, Room 101
500 South Bronough Street
Tallahassee, FL 32399-0250
Ph: 850-245-6270
Fax: 850-245-6282
Email: lcloud@dos.state.fl.us
Internet: <https://www.flrules.org/>

FLORIDA DEPARTMENT OF ENVIRONMENTAL PROTECTION (FDEP)
3900 Commonwealth Boulevard M.S. 49
Tallahassee, Florida 32399
Ph: 850-245-2118
Fax: 850-245-2128
Internet: <https://www.dep.state.fl.us/>

FLORIDA DEPARTMENT OF TRANSPORTATION (FDOT)
605 Suwannee Street
Tallahassee, Florida 32399-0450
Ph: 850-414-4100
Fax: 850-414-5201
E-mail: fdot@dot.state.fl.us
Internet: <https://www.dot.state.fl.us/>

FLORIDA STATUTES (FL-STAT)
Division of Legislative Information Services
Room 407 Claude Pepper Building
111 West Madison Street
Tallahassee, FL 32399-1400
Ph: 850-488-4371/800-342-1827
Email: leg.info@leg.state.fl.us
Internet: <http://www.leg.state.fl.us/statutes/>

JOHN F. KENNEDY SPACE CENTER (KSC)
Kennedy Space Center
Florida, 32899
Ph: 321-867-5000
Email: public-inquiries@ksc.nasa.gov
Internet: <http://www.nasa.gov/centers/kennedy/home/index.html>

NATIONAL AERONAUTICS AND SPACE ADMINISTRATION (NASA)
Publication(s) Available From
Superintendent of Documents
U.S. Government Printing Office
Washington, DC 20402
Ph: 202-783-3238

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)
1 Batterymarch Park
Quincy, MA 02169-7471
Ph: 617-770-3000
Fax: 617-770-0700
E-mail: webmaster@nfpa.org
Internet: <http://www.nfpa.org>

NATIONAL INSTITUTE FOR OCCUPATIONAL SAFETY AND HEALTH (NIOSH)
Mail Stop C-13
4676 Columbia Parkway
Cincinnati, OH 45226-1998
Ph: 800-356-4674
Fax: 513-533-8573
E-mail: pubstaff@cdc.gov
Internet: <http://www.cdc.gov/niosh/homepage.html>

NSF INTERNATIONAL (NSF)
789 North Dixboro Road
P.O. Box 130140
Ann Arbor, MI 48113-0140
Ph: 734-769-8010 or 800-NSF-MARK
Fax: 734-769-0109
E-mail: info@nsf.org
Internet: <http://www.nsf.org>

TURFGRASS PRODUCERS INTERNATIONAL (TPI)
2 East Main Street
East Dundee, IL 60118
Ph: 847-649-5555 or 800-405-8873
Fax: 847-649-5678
E-mail: info@turfgrasssod.org
Internet: <http://www.turfgrasssod.org>

UNDERWRITERS LABORATORIES (UL)
333 Pfingsten Road
Northbrook, IL 60062-2096
Ph: 847-272-8800
Fax: 847-272-8129
E-mail: customerexperiencecenter@us.ul.com
Internet: <http://www.ul.com/>

U.S. ARMY CORPS OF ENGINEERS (USACE)
Order CRD-C DOCUMENTS from:
U.S. Army Engineer Waterways Experiment Station
ATTN: Technical Report Distribution Section, Services
Branch, TIC
3909 Halls Ferry Road
Vicksburg, MS 39180-6199
Ph: 601-634-2664
Fax: 601-634-2388
E-mail: mtc-info@erdc.usace.army.mil
Internet: <http://www.wes.army.mil/SL/MTC/handbook.htm>

Order Other Documents from:
USACE Publications Depot
Attn: CEHEC-IM-PD
2803 52nd Avenue
Hyattsville, MD 20781-1102
Ph: 301-394-0081
Fax: 301-394-0084
E-mail: pubs-army@usace.army.mil
Internet: <http://www.usace.army.mil/publications>
or <http://www.hnd.usace.army.mil/techinfo/engpubs.htm>

U.S. DEPARTMENT OF HOUSING AND URBAN DEVELOPMENT (HUD)
Order from:
HUD User
P.O. Box 23268
Washington, DC 20026-3268
Ph: 800-245-2691 or 202-708-9981
Fax: 202-708-9981
E-mail: Huduser@aspensys.com
Internet: <http://www.huduser.org>

U.S. ENVIRONMENTAL PROTECTION AGENCY (EPA)
Ariel Rios Building
1200 Pennsylvania Avenue, N.W.
Washington, DC 20460
Ph: 202-272-0167
Internet: <http://www.epa.gov>

--- Some EPA documents are available only from:
National Technical Information Service (NTIS)
5285 Port Royal Road
Springfield, VA 22161
Ph: 703-605-6585
Fax: 703-605-6900
E-mail: info@ntis.gov
Internet: <http://www.ntis.gov>

U.S. FEDERAL AVIATION ADMINISTRATION (FAA)
Order for sale documents from:

Superintendent of Documents
U.S. Government Printing Office (GPO)
732 North Capitol Street, NW
Washington, DC 20401
Ph: 202-512-1800
Fax: 202-512-2104
E-mail: contactcenter@gpo.gov
Internet: <http://www.gpoaccess.gov>

Order free documents from:
Federal Aviation Administration
Department of Transportation
800 Independence Avenue, SW
Washington, DC 20591
Ph: 1-866-835-5322
Internet: <http://www.faa.gov>

U.S. NATIONAL ARCHIVES AND RECORDS ADMINISTRATION (NARA)
8601 Adelphi Road
College Park, MD 20740-6001
Ph: 866-272-6272
Fax: 301-837-0483
Internet: <http://www.archives.gov>

Order documents from:
Superintendent of Documents
U.S. Government Printing Office (GPO)
732 North Capitol Street, NW
Washington, DC 20401
Ph: 202-512-1800
Fax: 202-512-2104
E-mail: contactcenter@gpo.gov
Internet: <http://www.gpoaccess.gov>

-- End of Section --

SECTION TABLE OF CONTENTS

DIVISION 01 - GENERAL REQUIREMENTS

SECTION 01 57 20.00 10

ENVIRONMENTAL PROTECTION

PART 1 GENERAL

- 1.1 REFERENCES
- 1.2 DEFINITIONS
 - 1.2.1 Environmental Pollution and Damage
 - 1.2.2 Environmental Protection
 - 1.2.3 Contractor Generated Hazardous Waste
 - 1.2.4 Land Application for Discharge Water
 - 1.2.5 Surface Discharge
 - 1.2.6 Waters of the United States
 - 1.2.7 Wetlands
 - 1.2.8 Universal Waste
- 1.3 GENERAL REQUIREMENTS
- 1.4 SUBCONTRACTORS
- 1.5 SUBMITTALS
- 1.6 ENVIRONMENTAL PROTECTION PLAN
 - 1.6.1 Compliance
 - 1.6.2 Contents
 - 1.6.3 Appendix
- 1.7 PROTECTION FEATURES
- 1.8 ENVIRONMENTAL ASSESSMENT OF CONTRACT DEVIATIONS
- 1.9 NOTIFICATION

PART 2 PRODUCTS (NOT USED)

PART 3 EXECUTION

- 3.1 LAND RESOURCES
 - 3.1.1 Work Area Limits
 - 3.1.2 Landscape
 - 3.1.3 Erosion and Sediment Controls
 - 3.1.4 Contractor Facilities and Work Areas
- 3.2 WATER RESOURCES
 - 3.2.1 Cofferdams, Diversions, and Dewatering Operations
 - 3.2.2 Wetlands
- 3.3 AIR RESOURCES
 - 3.3.1 Particulates
 - 3.3.2 Odors
 - 3.3.3 Sound Intrusions
 - 3.3.4 Burning
- 3.4 MATERIALS MANAGEMENT AND WASTE DISPOSAL
 - 3.4.1 Solid Wastes
 - 3.4.2 Chemicals and Chemical Wastes
 - 3.4.3 Hazardous Materials and Universal Waste/Contractor General Hazardous Wastes

- 3.4.4 Fuel and Lubricants
- 3.4.5 Waste Water
- 3.4.6 PCB Management
- 3.5 RECYCLING AND WASTE MINIMIZATION
- 3.6 NON-HAZARDOUS SOLID WASTE DIVERSION REPORT
- 3.7 HISTORICAL, ARCHAEOLOGICAL, AND CULTURAL RESOURCES
- 3.8 BIOLOGICAL RESOURCES
- 3.9 SOLID WASTE MANAGEMENT UNIT (SWMU)
- 3.10 PREVIOUSLY USED EQUIPMENT
- 3.11 MAINTENANCE OF POLLUTION FACILITIES
- 3.12 TRAINING OF CONTRACTOR PERSONNEL
- 3.13 POST CONSTRUCTION CLEANUP

-- End of Section Table of Contents --

SECTION 01 57 20.00 10

ENVIRONMENTAL PROTECTION

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

U.S. ARMY CORPS OF ENGINEERS (USACE)

WETLAND MANUAL	Corps of Engineers Wetlands Delineation Manual Technical Report Y-87-1
----------------	---

U.S. NATIONAL ARCHIVES AND RECORDS ADMINISTRATION (NARA)

33 CFR 328	Definitions of Waters of the United States
40 CFR 261	Identification and Listing of Hazardous Waste
40 CFR 262	Standards Applicable to Generators of Hazardous Waste
40 CFR 273	Standards For Universal Waste Management
40 CFR 279	Standards for the Management of Used Oil
40 CFR 302	Designation, Reportable Quantities, and Notification
40 CFR 355	Emergency Planning and Notification
40 CFR 68	Chemical Accident Prevention Provisions
49 CFR 171 - 178	Hazardous Materials Regulations

1.2 DEFINITIONS

1.2.1 Environmental Pollution and Damage

Environmental pollution and damage is the presence of chemical, physical, or biological elements or agents which adversely affect human health or welfare; unfavorably alter ecological balances of importance to human life; affect other species of importance to humankind; or degrade the environment aesthetically, culturally and/or historically.

1.2.2 Environmental Protection

Environmental protection is the prevention/control of pollution and habitat disruption that may occur to the environment during construction. The control of environmental pollution and damage requires consideration of

land, water, and air; biological and cultural resources; and includes management of visual aesthetics; noise; solid, chemical, gaseous, and liquid waste; radiant energy and radioactive material as well as other pollutants.

1.2.3 Contractor Generated Hazardous Waste

Contractor generated hazardous waste means materials that, if abandoned or disposed of, may meet the definition of a hazardous waste. These waste streams would typically consist of material brought on site by the Contractor to execute work, but are not fully consumed during the course of construction. Examples include, but are not limited to, excess paint thinners (i.e. methyl ethyl ketone, toluene etc.), waste thinners, excess paints, excess solvents, waste solvents, and excess pesticides, and contaminated pesticide equipment rinse water.

1.2.4 Land Application for Discharge Water

The term "Land Application" for discharge water implies that the Contractor must discharge water at a rate which allows the water to percolate into the soil. No sheeting action, soil erosion, discharge into storm sewers, discharge into defined drainage areas, or discharge into the "waters of the United States" must occur. Land Application must be in compliance with all applicable Federal, State, and local laws and regulations.

1.2.5 Surface Discharge

The term "Surface Discharge" implies that the water is discharged with possible sheeting action and subsequent soil erosion may occur. Waters that are surface discharged may terminate in drainage ditches, storm sewers, creeks, and/or "waters of the United States" and would require a permit to discharge water from the governing agency.

1.2.6 Waters of the United States

All waters which are under the jurisdiction of the Clean Water Act, as defined in 33 CFR 328.

1.2.7 Wetlands

Those areas that are inundated or saturated by surface or ground water at a frequency and duration sufficient to support, and that under normal circumstances do support, a prevalence of vegetation typically adapted for life in saturated soil conditions. Wetlands generally include swamps, marshes, and bogs. Official determination of whether or not an area is classified as a wetland must be done in accordance with WETLAND MANUAL.

1.2.8 Universal Waste

Universal Waste means any of the following hazardous wastes that are managed under the universal waste requirements 40 CFR 273:

- (1) Batteries as described in Sec. 273.2 of this chapter;
- (2) Pesticides as described in Sec. 273.3 of this chapter;
- (3) Thermostats as described in Sec. 273.4 of this chapter; and
- (4) Lamps as described in Sec. 273.5 of this chapter.

1.3 GENERAL REQUIREMENTS

Minimize environmental pollution and damage that may occur as the result of

construction operations. The environmental resources within the project boundaries and those affected outside the limits of permanent work must be protected during the entire duration of this contract. Comply with all applicable environmental Federal, State, and local laws and regulations. Any delays resulting from failure to comply with environmental laws and regulations will be the Contractor's responsibility.

1.4 SUBCONTRACTORS

Ensure compliance with this section by subcontractors.

1.5 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for Contractor Quality Control approval. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-01 Preconstruction Submittals

Environmental Protection Plan; G

The environmental protection plan.

1.6 ENVIRONMENTAL PROTECTION PLAN

Prior to commencing construction activities or delivery of materials to the site, submit an Environmental Protection Plan for review and approval by the Contracting Officer. The purpose of the Environmental Protection Plan is to present a comprehensive overview of known or potential environmental issues which the Contractor must address during construction. Issues of concern must be defined within the Environmental Protection Plan as outlined in this section. Address each topic at a level of detail commensurate with the environmental issue and required construction task(s). Topics or issues which are not identified in this section, but are considered necessary, must be identified and discussed after those items formally identified in this section. Prior to submittal of the Environmental Protection Plan, meet with the Contracting Officer for the purpose of discussing the implementation of the initial Environmental Protection Plan; possible subsequent additions and revisions to the plan including any reporting requirements; and methods for administration of the Contractor's Environmental Plans. The Environmental Protection Plan must be current and maintained onsite by the Contractor.

1.6.1 Compliance

No requirement in this Section will relieve the Contractor of any applicable Federal, State, and local environmental protection laws and regulations. During Construction, the Contractor will be responsible for identifying, implementing, and submitting for approval any additional requirements to be included in the Environmental Protection Plan.

1.6.2 Contents

Include in the environmental protection plan, but not limit it to, the following:

- a. Name(s) of person(s) within the Contractor's organization who is(are) responsible for ensuring adherence to the Environmental

Protection Plan.

- b. Name(s) and qualifications of person(s) responsible for manifesting hazardous waste to be removed from the site, if applicable.
- c. Name(s) and qualifications of person(s) responsible for training the Contractor's environmental protection personnel.
- d. Description of the Contractor's environmental protection personnel training program.
- e. An erosion and sediment control plan which identifies the type and location of the erosion and sediment controls to be provided. The plan must include monitoring and reporting requirements to assure that the control measures are in compliance with the erosion and sediment control plan, Federal, State, and local laws and regulations. A Storm Water Pollution Prevention Plan (SWPPP) may be substituted for this plan.
- f. Drawings showing locations of proposed temporary excavations or embankments for haul roads, stream crossings, material storage areas, structures, sanitary facilities, and stockpiles of excess or spoil materials including methods to control runoff and to contain materials on the site.
- g. Traffic control plans including measures to reduce erosion of temporary roadbeds by construction traffic, especially during wet weather. Plan shall include measures to minimize the amount of mud transported onto paved public roads by vehicles or runoff.
- h. Work area plan showing the proposed activity in each portion of the area and identifying the areas of limited use or nonuse. Plan should include measures for marking the limits of use areas including methods for protection of features to be preserved within authorized work areas.
- i. Drawing showing the location of borrow areas.
- j. Include in the Spill Control plan the procedures, instructions, and reports to be used in the event of an unforeseen spill of a substance regulated by 40 CFR 68, 40 CFR 302, 40 CFR 355, and/or regulated under State or Local laws and regulations. The Spill Control Plan supplements the requirements the contract clause "Spills". Include in this plan, as a minimum:
 - 1). The name of the individual who will report any spills or hazardous substance releases and who will follow up with complete documentation. This individual will immediately notify the Contracting Officer and NASA Environmental. Include in the plan a list of the required reporting channels and telephone numbers.
 - 2). The name and qualifications of the individual who will be responsible for implementing and supervising the containment and cleanup.
 - 3). Training requirements for Contractor's personnel and methods of accomplishing the training.
 - 4). A list of materials and equipment to be immediately available at the job site, tailored to cleanup work of the potential

hazard(s) identified.

5). The names and locations of suppliers of containment materials and locations of additional fuel oil recovery, cleanup, restoration, and material-placement equipment available in case of an unforeseen spill emergency.

6). The methods and procedures to be used for expeditious contaminant cleanup.

k. A hazardous waste disposal plan identifying methods and locations for hazardous waste and universal waste collection and disposal.

l. A non-hazardous solid waste disposal plan identifying methods and locations for solid waste disposal including clearing debris and schedules for disposal.

1). Identify any subcontractors responsible for the transportation and disposal of solid waste. Submit licenses or permits for solid waste disposal sites that are not a commercial operating facility.

2). Evidence of the disposal facility's acceptance of the solid waste must be attached to this plan during the construction. Attach a copy of each of the Non-hazardous Solid Waste Diversion Reports to the disposal plan. Submit the report for the previous quarter on the first working day after the first quarter that non-hazardous solid waste has been disposed and/or diverted (e.g. the first working day of January, April, July, and October).

3). Indicate in the report the total amount of waste generated and total amount of waste diverted in cubic yards or tons along with the percent that was diverted.

m. A recycling and solid waste minimization plan with a list of measures to reduce consumption of energy and natural resources. Detail in the plan the Contractor's actions to comply with and to participate in Federal, State, Regional, and local government sponsored recycling programs to reduce the volume of solid waste at the source.

n. An air pollution control plan detailing provisions to assure that dust, debris, materials, trash, etc., do not become air borne and travel off the project site.

o. A contaminant prevention plan that: identifies potentially hazardous substances to be used on the job site; identifies the intended actions to prevent introduction of such materials into the air, water, or ground; and details provisions for compliance with Federal, State, and local laws and regulations for storage and handling of these materials. A copy of the Material Safety Data Sheets (MSDS) and the maximum quantity of each hazardous material to be onsite at any given time must be included in the contaminant prevention plan. Update the plan as new hazardous materials are brought onsite or removed from the site.

p. A waste water management plan that identifies the methods and procedures for management and/or discharge of waste waters which are directly derived from construction activities, such as concrete curing water, clean-up water, dewatering of ground water, disinfection water,

hydrostatic test water, and water used in flushing of lines. If a settling/retention pond is required, the plan must include the design of the pond including drawings, removal plan, and testing requirements for possible pollutants. If land application will be the method of disposal for the waste water, the plan must include a sketch showing the location for land application along with a description of the pretreatment methods to be implemented. If surface discharge will be the method of disposal, include a copy of the permit and associated documents as an attachment prior to discharging the waste water. If disposal is to a sanitary sewer, the plan must include documentation that the Waste Water Treatment Plant Operator has approved the flow rate, volume, and type of discharge.

q. A historical, archaeological, cultural resources biological resources and wetlands plan that defines procedures for identifying and protecting historical, archaeological, cultural resources, biological resources and wetlands known to be on the project site: and/or identifies procedures to be followed if historical archaeological, cultural resources, biological resources and wetlands not previously known to be onsite or in the area are discovered during construction. Include in the plan methods to assure the protection of known or discovered resources, identifying lines of communication between Contractor personnel and the Contracting Officer.

1.6.3 Appendix

Attach to the Environmental Protection Plan, as an appendix, copies of all environmental permits, permit application packages, approvals to construct, notifications, certifications, reports, and termination documents.

1.7 PROTECTION FEATURES

Prior to the start of any onsite construction activities, the Contractor and the Contracting Officer will make a joint condition survey. Immediately following the survey, the Contractor will prepare a brief report including a plan describing the features requiring protection under the provisions of the Contract Clauses, which are not specifically identified on the drawings as environmental features requiring protection along with the condition of trees, shrubs and grassed areas immediately adjacent to the site of work and adjacent to the Contractor's assigned storage area and access route(s), as applicable. This survey report will be signed by both the Contractor and the Contracting Officer upon mutual agreement as to its accuracy and completeness. The Contractor must protect those environmental features included in the survey report and any indicated on the drawings, regardless of interference which their preservation may cause to the work under the contract.

1.8 ENVIRONMENTAL ASSESSMENT OF CONTRACT DEVIATIONS

Any deviations from the drawings, plans and specifications, requested by the Contractor and which may have an environmental impact, will be subject to approval by the Contracting Officer and may require an extended review, processing, and approval time. The Contracting Officer reserves the right to disapprove alternate methods, even if they are more cost effective, if the Contracting Officer determines that the proposed alternate method will have an adverse environmental impact.

1.9 NOTIFICATION

The Contracting Officer will notify the Contractor in writing of any observed noncompliance with Federal, State or local environmental laws or regulations, permits, and other elements of the Contractor's Environmental Protection plan. After receipt of such notice, the Contractor will inform the Contracting Officer of the proposed corrective action and take such action when approved by the Contracting Officer. The Contracting Officer may issue an order stopping all or part of the work until satisfactory corrective action has been taken. No time extensions will be granted or equitable adjustments allowed for any such suspensions. This is in addition to any other actions the Contracting Officer may take under the contract, or in accordance with the Federal Acquisition Regulation or Federal Law.

PART 2 PRODUCTS (NOT USED)

PART 3 EXECUTION

3.1 LAND RESOURCES

Confine all activities to areas defined by the drawings and specifications. Identify any land resources to be preserved within the work area prior to the beginning of any construction. Do not remove, cut, deface, injure, or destroy land resources including trees, shrubs, vines, grasses, topsoil, and land forms without approval, except in areas indicated on the drawings or specified to be cleared. Ropes, cables, or guys will not be fastened to or attached to any trees for anchorage unless specifically authorized. Provide effective protection for land and vegetation resources at all times, as defined in the following subparagraphs. Remove stone, soil, or other materials displaced into uncleared areas.

3.1.1 Work Area Limits

Mark the areas that need not be disturbed under this contract prior to commencing construction activities. Mark or fence isolated areas within the general work area which are not to be disturbed. Protect monuments and markers before construction operations commence. Where construction operations are to be conducted during darkness, any markers must be visible in the dark. The Contractor's personnel must be knowledgeable of the purpose for marking and/or protecting particular objects.

3.1.2 Landscape

Trees, shrubs, vines, grasses, land forms and other landscape features indicated and defined on the drawings to be preserved must be clearly identified by marking, fencing, or wrapping with boards, or any other approved techniques. Restore landscape features damaged or destroyed during construction operations outside the limits of the approved work area.

3.1.3 Erosion and Sediment Controls

Providing erosion and sediment control measures in accordance with Federal, State, and local laws and regulations is the Contractor's responsibility. The erosion and sediment controls selected and maintained by the Contractor shall be such that water quality standards are not violated as a result of construction activities. The area of bare soil exposed at any one time by construction operations should be kept to a minimum. Construct or install

temporary and permanent erosion and sediment control best management practices (BMPs) as indicated on the drawings and as specified in Section 01 57 23 TEMPORARY STORM WATER POLLUTION CONTROL. BMPs may include, but not be limited to, vegetation cover, stream bank stabilization, slope stabilization, silt fences, construction of terraces, interceptor channels, sediment traps, inlet and outfall protection, diversion channels, and sedimentation basins. The Contractor's best management practices must also be in accordance with the National Pollutant Discharge Elimination System (NPDES) Storm Water Pollution Prevention Plan (SWPPP) which may be reviewed at NASA Environmental. Remove any temporary measures after the area has been stabilized.

3.1.4 Contractor Facilities and Work Areas

Place field offices, staging areas, stockpile storage, and temporary buildings in areas designated on the drawings or as directed by the Contracting Officer. Temporary movement or relocation of Contractor facilities will be made only when approved. Erosion and sediment controls must be provided for onsite borrow and spoil areas to prevent sediment from entering nearby waters. Temporary excavation and embankments for plant and/or work areas must be controlled to protect adjacent areas.

3.2 WATER RESOURCES

Monitor all water areas affected by construction activities to prevent pollution of surface and ground waters. Do not apply toxic or hazardous chemicals to soil or vegetation unless otherwise indicated. For construction activities immediately adjacent to impaired surface waters, the Contractor must be capable of quantifying sediment or pollutant loading to that surface water when required by State or Federally issued Clean Water Act permits.

3.2.1 Cofferdams, Diversions, and Dewatering Operations

Construction operations for dewatering shall be controlled at all times to maintain compliance with existing State water quality standards and designated uses of the surface water body. Comply with the contract clause "Dewatering/Consumptive Use Permit (CUP)".

3.2.2 Wetlands

Do not enter, disturb, destroy, or allow discharge of contaminants into any wetlands.

3.3 AIR RESOURCES

Equipment operation, activities, or processes will be in accordance with all Federal and State air emission and performance laws and standards.

3.3.1 Particulates

Dust particles; aerosols and gaseous by-products from construction activities; and processing and preparation of materials, such as from asphaltic batch plants; must be controlled at all times, including weekends, holidays and hours when work is not in progress. Maintain excavations, stockpiles, haul roads, permanent and temporary access roads, plant sites, spoil areas, borrow areas, and other work areas within or outside the project boundaries free from particulates which would cause the Federal, State, and local air pollution standards to be exceeded or which

would cause a hazard or a nuisance. Sprinkling, chemical treatment of an approved type, baghouse, scrubbers, electrostatic precipitators or other methods will be permitted to control particulates in the work area. Sprinkling, to be efficient, must be repeated to keep the disturbed area damp at all times. Provide sufficient, competent equipment available to accomplish these tasks. Perform particulate control as the work proceeds and whenever a particulate nuisance or hazard occurs. Comply with all State and local visibility regulations.

3.3.2 Odors

Odors from construction activities must be controlled at all times. The odors must be in compliance with State regulations and/or local ordinances and may not constitute a health hazard.

3.3.3 Sound Intrusions

Keep construction activities under surveillance and control to minimize environment damage by noise. Comply with State regulations and local ordinances.

3.3.4 Burning

Burning is prohibited on the Government premises.

3.4 MATERIALS MANAGEMENT AND WASTE DISPOSAL

Disposal of wastes will be as directed below, unless otherwise specified in other sections and/or shown on the drawings.

3.4.1 Solid Wastes

Solid wastes (excluding clearing debris) shall be handled in accordance with the contract clause "Landfill Operations/Solid Waste Removal".

3.4.2 Chemicals and Chemical Wastes

Dispense chemicals ensuring no spillage to the ground or water. Perform and document periodic inspections of dispensing areas to identify leakage and initiate corrective action. This documentation will be periodically reviewed by the Government. Collect chemical waste in corrosion resistant, compatible containers. Collection drums must be monitored and removed to a staging or storage area when contents are within 6 inches of the top. Wastes shall be classified, managed, stored, and disposed of in accordance with the contract clause "Hazardous Waste".

3.4.3 Hazardous Materials and Universal Waste/Contractor General Hazardous Wastes

Hazardous wastes are defined in 40 CFR 261, or are as defined by applicable State and local regulations. Hazardous materials are defined in 49 CFR 171 - 178. Manage and store hazardous waste and universal waste in compliance with 40 CFR 262 and the contract clause "Hazardous Waste". Take sufficient measures to prevent spillage of hazardous and toxic materials during dispensing.

3.4.4 Fuel and Lubricants

Storage, fueling and lubrication of equipment and motor vehicles must be

conducted in a manner that affords the maximum protection against spill and evaporation. Manage and store fuel, lubricants and oil in accordance with all Federal, State, Regional, and local laws and regulations. Used lubricants and used oil to be discarded must be stored in marked corrosion-resistant containers and recycled or disposed in accordance with 40 CFR 279, State, and local laws and regulations and the contract clause "Hazardous Waste".

3.4.5 Waste Water

Disposal of waste water will be as specified below.

- a. Waste water from construction activities, such as onsite material processing, concrete curing, foundation and concrete clean-up, water used in concrete trucks, forms, etc. shall be in accordance with the contract clause "Concrete Wastewater".
- b. For discharge of ground water, the Contractor shall land apply on the project site in accordance with all Federal, State, Regional, and/or Local laws and regulations for pumping and land applying ground water as well as the contract clause "Dewatering/Consumptive Use Permit (CUP)".
- c. Water generated from the flushing of lines after disinfection or disinfection in conjunction with hydrostatic testing will be land applied in accordance with all Federal, State, and local laws and regulations for land application.

3.4.6 PCB Management

Polychlorinated Biphenyl (PCB) wastes shall be managed in accordance with the contract clause "PCB Management".

3.5 RECYCLING AND WASTE MINIMIZATION

Participate in State and local government sponsored recycling programs. The Contractor is further encouraged to minimize solid waste generation throughout the duration of the project. Recycle material in accordance with the contract clause "Recycling and Salvaging Materials". For further information, please contact the NASA/KSC Recycling Manager.

3.6 NON-HAZARDOUS SOLID WASTE DIVERSION REPORT

Maintain an inventory of non-hazardous solid waste diversion and disposal of construction and demolition debris. Submit a report to the Environmental Program Branch through the Contracting Officer on the first working day after each fiscal year quarter, starting the first quarter that non-hazardous solid waste has been generated. Include the following in the report:

- a. Construction and Demolition (C&D) Debris Disposed = _____ in cubic yards or tons, as appropriate.
- b. Construction and Demolition (C&D) Debris Recycled = _____ in cubic yards or tons, as appropriate.
- c. Total C&D Debris Generated = _____ in cubic yards or tons, as appropriate.

d. Waste Sent to Waste-To-Energy Incineration Plant (This amount should not be included in the recycled amount) = _____ in cubic yards or tons, as appropriate.

e. Metal Recycled = _____ in tons, as appropriate.

3.7 HISTORICAL, ARCHAEOLOGICAL, AND CULTURAL RESOURCES

Refer to the contract clause "Historical, Architectural and Cultural Resources".

3.8 BIOLOGICAL RESOURCES

Minimize interference with, disturbance to, and damage to fish, wildlife, and plants including their habitat. The protection of threatened and endangered animal and plant species, including their habitat, is the Contractor's responsibility in accordance with Federal, State, Regional, and local laws and regulations. The Contractor shall comply with the contract clause "Biological Surveys".

3.9 SOLID WASTE MANAGEMENT UNIT (SWMU)

Portions of this project are located within the boundaries of various identified Solid Waste Management Unit (SWMU)/Potential Release Location (PRL) sites being managed by the Remediation Group of NASA Environmental. A SWMU/PRL designation means that the site has had historical operations which had the potential to impact the environment.

The systems being modified are located within various SWMU or PRL sites. These sites contain groundwater contamination, soil contamination, or both. Return soil excavated from the land surface to any depth to the area of excavation from which it was removed. Collect, containerize, sample, and dispose of excavated soil that cannot be returned to the area from which it was removed in accordance with the Process Waste Questionnaire (PWQ)/Technical Response Packet (TRP) process. Wear proper PPE when working in soil and groundwater. Use best management practices to prevent erosion and removal of soil from site.

Discharge dewatering effluent to grade upland of the excavated area and allow to percolate back into the pervious ground surface. Use best management practices to prevent dewatering effluent from entering surface waters. There is a potential that dewatering effluent from SWMU or PRL sites may not be discharged to grade. Coordinate with the Contracting Officer and NASA Environmental for approval of the Dewatering Plan within the boundary of a SWMU or PRL 12 days before the Notice to Proceed.

3.10 PREVIOUSLY USED EQUIPMENT

Clean all previously used construction equipment prior to bringing it onto the project site. Ensure that the equipment is free from soil residuals, egg deposits from plant pests, noxious weeds, and plant seeds. Consult with the USDA jurisdictional office for additional cleaning requirements.

3.11 MAINTENANCE OF POLLUTION FACILITIES

Maintain permanent and temporary pollution control facilities and devices for the duration of the contract or for that length of time construction activities create the particular pollutant.

3.12 TRAINING OF CONTRACTOR PERSONNEL

The Contractor's personnel must be trained in all phases of environmental protection and pollution control. Conduct environmental protection/pollution control meetings for all personnel prior to commencing construction activities. Additional meetings must be conducted for new personnel and when site conditions change. Include in the training and meeting agenda: methods of detecting and avoiding pollution; familiarization with statutory and contractual pollution standards; installation and care of devices, vegetative covers, and instruments required for monitoring purposes to ensure adequate and continuous environmental protection/pollution control; anticipated hazardous or toxic chemicals or wastes, and other regulated contaminants; recognition and protection of archaeological sites, artifacts, wetlands, and endangered species and their habitat that are known to be in the area.

3.13 POST CONSTRUCTION CLEANUP

The Contractor will clean up all areas used for construction. Unless otherwise instructed in writing by the Contracting Officer, obliterate all signs of temporary construction facilities such as haul roads, work area, structures, foundations of temporary structures, stockpiles of excess or waste materials, and other vestiges of construction prior to final acceptance of the work. The disturbed area must be graded, filled and the entire area seeded unless otherwise indicated.

-- End of Section --

SECTION TABLE OF CONTENTS

DIVISION 01 - GENERAL REQUIREMENTS

SECTION 01 57 23

TEMPORARY STORM WATER POLLUTION CONTROL

PART 1 GENERAL

- 1.1 REFERENCES
- 1.2 SYSTEM DESCRIPTION
- 1.3 EROSION AND SEDIMENT CONTROLS
 - 1.3.1 Stabilization Practices
 - 1.3.1.1 Unsuitable Conditions
 - 1.3.1.2 No Activity for Less Than 21 Days
 - 1.3.1.3 Burnoff
 - 1.3.1.4 Protection of Erodible Soils
 - 1.3.2 Erosion, Sediment and Stormwater Control
 - 1.3.3 Stormwater Drainage
 - 1.3.4 Structural Practices
 - 1.3.4.1 Silt Fences
 - 1.3.5 Vegetation and Mulch
- 1.4 SUBMITTALS
- 1.5 DELIVERY, STORAGE, AND HANDLING

PART 2 PRODUCTS

- 2.1 COMPONENTS FOR SILT FENCES
 - 2.1.1 Filter Fabric
 - 2.1.2 Silt Fence Stakes and Posts

PART 3 EXECUTION

- 3.1 INSTALLATION OF SILT FENCES
- 3.2 FIELD QUALITY CONTROL
 - 3.2.1 Silt Fence Maintenance
- 3.3 INSPECTIONS
 - 3.3.1 General
 - 3.3.2 Inspections Details
 - 3.3.3 Erosion and Sediment Control Inspection Reports

-- End of Section Table of Contents --

SECTION 01 57 23

TEMPORARY STORM WATER POLLUTION CONTROL

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

ASTM INTERNATIONAL (ASTM)

ASTM D 4439	(2004) Geosynthetics
ASTM D 4491	(1999a; R 2004e1) Water Permeability of Geotextiles by Permittivity
ASTM D 4533	(2004) Trapezoid Tearing Strength of Geotextiles
ASTM D 4632	(1991; R 2003) Grab Breaking Load and Elongation of Geotextiles
ASTM D 4751	(2004) Determining Apparent Opening Size of a Geotextile
ASTM D 4873	(2002) Identification, Storage, and Handling of Geosynthetic Rolls and Samples

U.S. ENVIRONMENTAL PROTECTION AGENCY (EPA)

EPA 832-R-92-005	(1992) Storm Water Management for Construction Activities Developing Pollution Preventions and Plans and Best Management Practices
------------------	--

U.S. NATIONAL ARCHIVES AND RECORDS ADMINISTRATION (NARA)

40 CFR 122.26	Storm Water Discharges (Applicable to State NPDES Programs, see section 123.25)
---------------	---

1.2 SYSTEM DESCRIPTION

The work consists of implementing the storm water pollution prevention measures to prevent sediment from entering streams or water bodies as specified in this Section in conformance with the requirements of Section 01 57 20.00 10 ENVIRONMENTAL PROTECTION, and the requirements of the National Pollution Discharge Elimination System (NPDES) permit.

1.3 EROSION AND SEDIMENT CONTROLS

The controls and measures required of the Contractor are described below.

1.3.1 Stabilization Practices

The stabilization practices to be implemented include temporary seeding, mulching, geotextiles, sod stabilization, vegetative buffer strips, erosion control mats, protection of trees, preservation of mature vegetation, etc. On the Daily Report, record the dates when the major grading activities occur, (e.g., clearing, excavation, and grading); when construction activities temporarily or permanently cease on a portion of the site; and when stabilization practices are initiated. Except as provided in paragraphs UNSUITABLE CONDITIONS and NO ACTIVITY FOR LESS THAN 21 DAYS, stabilization practices must be initiated as soon as practicable, but no more than 14 days, in any portion of the site where construction activities have temporarily or permanently ceased.

1.3.1.1 Unsuitable Conditions

Where the initiation of stabilization measures by the fourteenth day after construction activity temporarily or permanently ceases or is precluded by unsuitable conditions caused by the weather, stabilization practices shall be initiated as soon as practicable after conditions become suitable.

1.3.1.2 No Activity for Less Than 21 Days

When the total time period in which construction activity is temporarily ceased on a portion of the site is 14 days minimum, stabilization practices do not have to be initiated on that portion of the site until 14 days have elapsed after construction activity temporarily ceased.

1.3.1.3 Burnoff

Burnoff of the ground cover is not permitted.

1.3.1.4 Protection of Erodible Soils

Immediately finish the earthwork brought to a final grade, as indicated or specified, and protect the side slopes and back slopes upon completion of rough grading. Plan and conduct earthwork to minimize the duration of exposure of unprotected soils.

1.3.2 Erosion, Sediment and Stormwater Control

a. Storm Water Notice of Intent for Construction Activities

b. Submit a Storm Water Notice of Intent for NPDES coverage under the general permit for construction activities and a Storm Water Pollution Prevention Plan (SWPPP) for the project to the Contracting Officer prior to the commencement of work. The SWPPP shall meet the requirements of the State of Florida general permit for storm water discharges from construction sites. Submit the SWPPP along with any required Notice of Intent, Notice of Termination, and appropriate permit fees, via the Contracting Officer, to the appropriate State agency for approval, a minimum of 14 calendar days prior to the start of any land disturbing activities. Maintain an approved copy of the SWPPP at the construction on-site office, and continually update as regulations require, to reflect current site conditions. Include within the SWPPP:

- (1) Identify potential sources of pollution which may be reasonably expected to affect the quality of storm water discharge

from the site.

(2) Describe and ensure implementation of practices which will be used to reduce the pollutants in storm water discharge from the site.

(3) Ensure compliance with terms of the State of Florida general permit for storm water discharge.

(4) Select applicable best management practices from EPA 832-R-92-005.

(5) Include a completed copy of the Registration Statement, BMP Inspection Report Template and Notice of Termination except for the effective date.

(6) Storm Water Pollution Prevention Measures and Notice of Intent 40 CFR 122.26, EPA 832-R-92-005. Provide an SWPPP for the project.

(7) Install, inspect, and maintain best management practices (BMPs) as required by the general permit. Prepare and submit to the Contracting Officer, BMP Inspection Reports as required by the general permit.

(8) Once construction is complete and the site has been stabilized with a final, sustainable cover, submit the Notice of Termination to the Contracting Officer and NASA Environmental within 30 days after all land disturbing activities end.

(9) At the time of submittal to the Contracting Officer, concurrently forward copies of the SWPPP, Registration Statement, BMP Inspection Reports, and Notice of Termination to the Contracting Officer and to NASA Environmental.

1.3.3 Stormwater Drainage

There will be no discharge of excavation ground water to the sanitary sewer, storm drains, or to the river without prior specific authorization from the Contracting Officer and NASA Environmental. Discharge of hazardous substances will not be permitted under any circumstances. Construction site runoff will be prevented from entering any storm drain or the river directly by the use of silt fence or other method suitable to the Contracting Officer and NASA Environmental. Provide erosion protection of the surrounding soils.

1.3.4 Structural Practices

Implement structural practices to divert flows from exposed soils, temporarily store flows, or otherwise limit runoff and the discharge of pollutants from exposed areas of the site. Implement structural practices in a timely manner, during the construction process, to minimize erosion and sediment runoff. Include the following devices; Location and details of installation and construction are shown on the drawings.

1.3.4.1 Silt Fences

Provide silt fences as a temporary structural practice to minimize erosion and sediment runoff. Properly install silt fences to effectively retain

sediment immediately after completing each phase of work where erosion would occur in the form of sheet and rill erosion (e.g. clearing, excavation, and grading). Install silt fences in the locations indicated on the drawings. Obtain approval from the Contracting Officer prior to final removal of silt fence barriers.

1.3.5 Vegetation and Mulch

a. Provide temporary protection on sides and back slopes as soon as rough grading is completed or sufficient soil is exposed to require erosion protection. Protect slopes by accelerated growth of permanent vegetation, temporary vegetation, mulching, or netting. Stabilize slopes by hydroseeding, anchoring mulch in place, covering with anchored netting, sodding, or such combination of these and other methods necessary for effective erosion control.

b. Seeding: Provide new seeding where ground is disturbed. Include topsoil or nutriment during the seeding operation necessary to establish a suitable stand of grass.

1.4 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for Contractor Quality Control approval. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-01 Preconstruction Submittals

Storm Water Pollution Prevention Plan
Storm Water Notice of Intent

Pollution prevention plan and Notice of intent for NPDES coverage under the general permit for construction activities

1.5 DELIVERY, STORAGE, AND HANDLING

Identify, store and handle filter fabric in accordance with ASTM D 4873.

PART 2 PRODUCTS

2.1 COMPONENTS FOR SILT FENCES

2.1.1 Filter Fabric

Provide geotextile that complies with the requirements of ASTM D 4439, and consists of polymeric filaments which are formed into a stable network such that filaments retain their relative positions. The filament shall consist of a long-chain synthetic polymer composed of at least 85 percent by weight of ester, propylene, or amide, and contains stabilizers and/or inhibitors added to the base plastic to make the filaments resistant to deterioration due to ultraviolet and heat exposure. Provide synthetic filter fabric that contains ultraviolet ray inhibitors and stabilizers to assure a minimum of six months of expected usable construction life at a temperature range of 0 to 120 degrees F. The filter fabric shall meet the following requirements:

FILTER FABRIC FOR SILT SCREEN FENCE

PHYSICAL PROPERTY	TEST PROCEDURE	STRENGTH REQUIREMENT
-------------------	----------------	----------------------

Grab Tensile	ASTM D 4632	100 lbs. min.
Elongation (percent)		30 percent max.
Trapezoid Tear	ASTM D 4533	55 lbs. min.
Permittivity	ASTM D 4491	0.2 sec-1
AOS (U.S. Std Sieve)	ASTM D 4751	20-100

2.1.2 Silt Fence Stakes and Posts

Use either wooden stakes or steel posts for fence construction. Wooden stakes utilized for silt fence construction, shall have a minimum cross section of 2 by 2 inches when oak is used and 4 by 4 inches when pine is used, and have a minimum length of 5 feet. Steel posts (standard "U" or "T" section) utilized for silt fence construction, shall have a minimum weight of 1.33 pounds/linear foot and a minimum length of 5 feet.

PART 3 EXECUTION

3.1 INSTALLATION OF SILT FENCES

Extend silt fences a minimum of 16 inches above the ground surface without exceeding 34 inches above the ground surface. Provide filter fabric from a continuous roll cut to the length of the barrier to avoid the use of joints. When joints are unavoidable, splice together filter fabric at a support post, with a minimum 6 inch overlap, and securely sealed. Excavate trench approximately 4 inches wide and 4 inches deep on the upslope side of the location of the silt fence. The 4 by 4 inch trench shall be backfilled and the soil compacted over the filter fabric. Remove silt fences upon approval by the Contracting Officer.

3.2 FIELD QUALITY CONTROL

Maintain the temporary and permanent vegetation, erosion and sediment control measures, and other protective measures in good and effective operating condition by performing routine inspections to determine condition and effectiveness, by restoration of destroyed vegetative cover, and by repair of erosion and sediment control measures and other protective measures. Use the following procedures to maintain the protective measures.

3.2.1 Silt Fence Maintenance

Inspect the silt fences in accordance with paragraph, titled "Inspections," of this section. Any required repairs shall be made promptly. Pay close attention to the repair of damaged silt fence resulting from end runs and undercutting. Should the fabric on a silt fence decompose or become ineffective, and the barrier is still necessary, replace the fabric promptly. Remove sediment deposits when deposits reach one-third of the height of the barrier. Remove a silt fence when it is no longer required. The immediate area occupied by the fence and any sediment deposits shall be shaped to an acceptable grade. The areas disturbed by this shaping shall receive erosion control.

3.3 INSPECTIONS

3.3.1 General

Inspect disturbed areas of the construction site, areas that have not been finally stabilized used for storage of materials exposed to precipitation, stabilization practices, structural practices, other controls, and area where vehicles exit the site at least once every seven (7) calendar days and within 24 hours of the end of any storm that produces 0.5 inches or more rainfall at the site. Conduct inspections at least once every month where sites have been finally stabilized.

3.3.2 Inspections Details

Inspect disturbed areas and areas used for material storage that are exposed to precipitation for evidence of, or the potential for, pollutants entering the drainage system. Observe erosion and sediment control measures identified in the Storm Water Pollution Prevention Plan to ensure that they are operating correctly. Inspect discharge locations or points to ascertain whether erosion control measures are effective in preventing significant impacts to receiving waters. Inspect locations where vehicles exit the site for evidence of offsite sediment tracking.

3.3.3 Erosion and Sediment Control Inspection Reports

Prepare "Storm Water Pollution Prevention Plan (SWPPP) Inspection Reports" (form provided at the pre-construction conference) to the Contracting Officer once every 7 calendar days and within 24 hours of a storm event that produced 0.5 inch or more of rain, and submit reports monthly. A copy of the inspection report shall be maintained on the job site.

-- End of Section --

SECTION TABLE OF CONTENTS

DIVISION 01 - GENERAL REQUIREMENTS

SECTION 01 74 19

CONSTRUCTION AND DEMOLITION WASTE MANAGEMENT

PART 1 GENERAL

- 1.1 GOVERNMENT POLICY
- 1.2 MANAGEMENT
- 1.3 SUBMITTALS
- 1.4 MEETINGS
- 1.5 WASTE MANAGEMENT PLAN
- 1.6 RECORDS
- 1.7 COLLECTION
 - 1.7.1 Source Separated Method
 - 1.7.2 Co-Mingled Method
 - 1.7.3 Other Methods
- 1.8 DISPOSAL

PART 2 PRODUCTS

PART 3 EXECUTION

-- End of Section Table of Contents --

SECTION 01 74 19

CONSTRUCTION AND DEMOLITION WASTE MANAGEMENT

PART 1 GENERAL

1.1 GOVERNMENT POLICY

Government policy is to apply sound environmental principles in the design, construction and use of facilities. As part of the implementation of that policy the Contractor shall: (1) practice efficient waste management when sizing, cutting, and installing products and materials and (2) use all reasonable means to divert construction and demolition waste from landfills and incinerators and to facilitate their recycling or reuse.

1.2 MANAGEMENT

Take a pro-active, responsible role in the management of construction and demolition waste and require all subcontractors, vendors, and suppliers to participate in the effort. The Environmental Manager shall be responsible for instructing workers and overseeing and documenting results of the Waste Management Plan for the project. Construction and demolition waste includes products of demolition or removal, excess or unusable construction materials, packaging materials for construction products, and other materials generated during the construction process but not incorporated into the work. In the management of waste consideration shall be given to the availability of viable markets, the condition of the material, the ability to provide the material in suitable condition and in a quantity acceptable to available markets, and time constraints imposed by internal project completion mandates. The Contractor is responsible for implementation of any special programs involving rebates or similar incentives related to recycling of waste. Revenues or other savings obtained for salvage, or recycling accrue to the Contractor. Use appropriately permitted firms and facilities for recycling, reuse, and disposal to the extent required by federal, state, and local regulations. Also, provide on-site instruction of appropriate separation, handling, recycling, salvage, reuse, and return methods to be used by all parties at the appropriate stages of the project.

1.3 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for Contractor Quality Control approval. The following shall be submitted in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-01 Preconstruction Submittals

Waste Management Plan; G

SD-11 Closeout Submittals

Records

1.4 MEETINGS

Conduct Construction Waste Management meetings. After award of the Contract and prior to commencement of work, schedule and conduct a meeting with the Contracting Officer to discuss the proposed Waste Management Plan and to develop a mutual understanding relative to the details of waste management. At a minimum, environmental and waste management goals and issues shall be discussed at the following additional meetings:

- a. Pre-bid meeting.
- b. Pre-demolition meeting.
- c. Regular site meetings.
- d. Work safety meetings.

1.5 WASTE MANAGEMENT PLAN

A waste management plan shall be submitted within 15 days after notice to proceed and not less than 10 days before the pre-demolition meeting. The plan shall demonstrate how the project waste diversion goal shall be met and shall include the following:

- a. Name of individuals on the Contractor's staff responsible for waste prevention and management.
- b. Actions that will be taken to reduce solid waste generation, including coordination with subcontractors to ensure awareness and participation.
- c. Description of the regular meetings to be held to address waste management.
- d. Description of the specific approaches to be used in recycling/reuse of the various materials generated, including the areas on site and equipment to be used for processing, sorting, and temporary storage of wastes.
- e. Characterization, including estimated types and quantities, of the waste to be generated.
- f. Name of landfill and/or incinerator to be used and the estimated costs for use, assuming that there would be no salvage or recycling on the project.
- g. Identification of local and regional reuse programs, including non-profit organizations such as schools, local housing agencies, and organizations that accept used materials such as materials exchange networks and Habitat for Humanity. Include the name, location, and phone number for each reuse facility to be used, and provide a copy of the permit or license for each facility.
- h. List of specific waste materials that will be salvaged for resale or recycled. Refer to Section 01 57 20.00 10 ENVIRONMENTAL PROTECTION, paragraph entitled "Recycling and Waste Minimization" for more information. Recycling facilities that will be used shall be identified by name, location, and phone number, including a copy of the permit or license for each facility.

- i. Identification of materials that cannot be recycled/reused with an explanation or justification, to be approved by the Contracting Officer.
- j. Description of the means by which any waste materials identified in item (h) above will be protected from contamination.
- k. Description of the means of transportation of the recyclable materials (whether materials will be site-separated and self-hauled to designated centers, or whether mixed materials will be collected by a waste hauler and removed from the site).
- l. Anticipated net cost savings determined by subtracting Contractor program management costs and the cost of disposal from the revenue generated by sale of the materials and the incineration and/or landfill cost avoidance.

Revise and resubmit Plan as required by the Contracting Officer. Approval of Contractor's Plan will not relieve the Contractor of responsibility for compliance with applicable environmental regulations or meeting project cumulative waste diversion requirement. Distribute copies of the Waste Management Plan to each subcontractor and the Contracting Officer.

1.6 RECORDS

Records shall be maintained to document the quantity of waste generated; the quantity of waste diverted through sale, reuse, or recycling; and the quantity of waste disposed by landfill or incineration. Quantities may be measured by weight or by volume, but must be consistent throughout. List each type of waste separately noting the disposal or diversion date. Identify the landfill, recycling center, waste processor, or other organization used to process or receive the solid waste. Provide explanations for any waste not recycled or reused. With each application for payment, submit updated documentation for solid waste disposal and diversion, and submit manifests, weight tickets, receipts, and invoices specifically identifying the project and waste material. The records shall be made available to the Contracting Officer during construction, and a copy of the records shall be delivered to the Contracting Officer upon completion of the construction.

1.7 COLLECTION

Separate, store, protect, and handle at the site identified recyclable and salvageable waste products in a manner that maximizes recyclability and salvagability of identified materials. Provide the necessary containers, bins and storage areas to facilitate effective waste management and clearly and appropriately identify them. Provide materials for barriers and enclosures around recyclable material storage areas which are nonhazardous and recyclable or reusable. Locate out of the way of construction traffic. Provide adequate space for pick-up and delivery and convenience to subcontractors. Recycling and waste bin areas are to be kept neat and clean, and recyclable materials shall be handled to prevent contamination of materials from incompatible products and materials. Clean contaminated materials prior to placing in collection containers. Use cleaning materials that are nonhazardous and biodegradable. Handle hazardous waste and hazardous materials in accordance with applicable regulations and coordinate with Section 01 57 20.00 10 ENVIRONMENTAL PROTECTION. Separate materials by one of the following methods:

1.7.1 Source Separated Method

Waste products and materials that are recyclable shall be separated from trash and sorted as described below into appropriately marked separate containers and then transported to the respective recycling facility for further processing. Deliver materials in accordance with recycling or reuse facility requirements (e.g., free of dirt, adhesives, solvents, petroleum contamination, and other substances deleterious to the recycling process). Separate materials into the following category types as appropriate to the project waste and to the available recycling and reuse programs in the project area:

- a. Asphalt.
- b. Concrete and masonry.
- c. Metal (e.g. banding, stud trim, ductwork, piping, rebar, roofing, other trim, steel, iron, galvanized, stainless steel, aluminum, copper, zinc, lead brass, bronze).
 - (1) Ferrous.
 - (2) Non-ferrous.
- d. Wood (nails and staples allowed).
- e. Debris.
- f. Glass (colored glass allowed).
- g. Paper.
 - (1) Bond.
 - (2) Newsprint.
 - (3) Cardboard and paper packaging materials.
- h. Plastic.
 - (1) Type 1: Polyethylene Terephthalate (PET, PETE).
 - (2) Type 2: High Density Polyethylene (HDPE).
 - (3) Type 3: Vinyl (Polyvinyl Chloride or PVC).
 - (4) Type 4: Low Density Polyethylene (LDPE).
 - (5) Type 5: Polypropylene (PP).
 - (6) Type 6: Polystyrene (PS).
 - (7) Type 7: Other. Use of this code indicates that the package in question is made with a resin other than the six listed above, or is made of more than one resin listed above, and used in a multi-layer combination.
- i. Gypsum

- j. Non-hazardous paint and paint cans.
- k. Carpet.
- l. Ceiling tiles.
- m. Insulation.
- n. Beverage containers.

1.7.2 Co-Mingled Method

Waste products and recyclable materials shall be placed into a single container and then transported to a recycling facility where the recyclable materials are sorted and processed.

1.7.3 Other Methods

Other methods proposed by the Contractor may be used when approved by the Contracting Officer.

1.8 DISPOSAL

Disposal shall be in accordance with Section 01 57 20.00 10 ENVIRONMENTAL PROTECTION.

PART 2 PRODUCTS

Not used.

PART 3 EXECUTION

Not used.

-- End of Section --

SECTION TABLE OF CONTENTS

DIVISION 01 - GENERAL REQUIREMENTS

SECTION 01 78 00

CLOSEOUT SUBMITTALS

PART 1 GENERAL

- 1.1 REFERENCES
- 1.2 SUBMITTALS
- 1.3 PROJECT RECORD DOCUMENTS
 - 1.3.1 Record Drawings
 - 1.3.1.1 Working Record and Final Record Drawings
 - 1.3.1.2 Drawing Preparation
 - 1.3.2 As-Built Record of Equipment and Materials
 - 1.3.3 Final Approved Shop Drawings
 - 1.3.4 Construction Contract Specifications
 - 1.3.5 Real Property Equipment
- 1.4 SPARE PARTS DATA
- 1.5 PREVENTATIVE MAINTENANCE
- 1.6 WARRANTY MANAGEMENT
 - 1.6.1 Warranty Management Plan
 - 1.6.2 Performance Bond
 - 1.6.3 Pre-Warranty Conference
 - 1.6.4 Contractor's Response to Construction Warranty Service Requirements
 - 1.6.5 Warranty Tags
- 1.7 CLEANUP

PART 2 PRODUCTS (NOT USED)

PART 3 EXECUTION (NOT USED)

-- End of Section Table of Contents --

SECTION 01 78 00

CLOSEOUT SUBMITTALS

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

ASTM INTERNATIONAL (ASTM)

ASTM E 1971 (2005) Stewardship for the Cleaning of Commercial and Institutional Buildings

1.2 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for Contractor Quality Control approval. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-03 Product Data

As-Built Record of Equipment and Materials

Two copies of the record listing the as-built materials and equipment incorporated into the construction of the project.

Warranty Management Plan

One set of the warranty management plan containing information relevant to the warranty of materials and equipment incorporated into the construction project, including the starting date of warranty of construction. Furnish with each warranty the name, address, and telephone number of each of the guarantor's representatives nearest to the project location.

Final Cleaning

Two copies of the listing of completed final clean-up items.

Spare Parts Data

Two copies of list that indicates manufacturer's name, part number, nomenclature, and stock level recommended for maintenance and repair. List those items that may be standard to the normal maintenance of the system.

SD-08 Manufacturer's Instructions

Preventative Maintenance and Condition Monitoring (Predictive Testing) and Inspection schedules with instructions that state when systems should be retested.

Define within the schedule the anticipated length of each test, test apparatus, number of personnel identified by responsibility, and a testing validation procedure permitting the record operation capability requirements. On each test feature; e.g., gpm, rpm, psi, provide a signoff blank for the Contractor and Contracting Officer. Within a remarks column of the testing validation procedure include references to operating limits of time, pressure, temperature, volume, voltage, current, acceleration, velocity, alignment, calibration, adjustments, cleaning, or special system notes. Delineate procedures for preventative maintenance, condition monitoring (predictive testing) and inspection, adjustment, lubrication and cleaning necessary to prevent failure.

Posted Instructions

SD-11 Closeout Submittals

Record Drawings

Drawings showing final as-built conditions of the project. The final CADD record drawings must consist of one set of electronic CADD drawing files in the specified format, 2 sets of blue-line prints of the mylars, and one set of the approved working record drawings.

1.3 PROJECT RECORD DOCUMENTS

1.3.1 Record Drawings

This paragraph covers record drawings complete, as a requirement of the contract. The terms "drawings," "contract drawings," "drawing files," "working record drawings" and "final record drawings" refer to contract drawings which are revised to be used for final record drawings showing as-built conditions.

1.3.1.1 Working Record and Final Record Drawings

Revise 2 sets of paper drawings by red-line process to show the as-built conditions during the prosecution of the project. Keep these working as-built marked drawings current on a weekly basis and at least one set available on the jobsite at all times. Changes from the contract plans which are made in the work or additional information which might be uncovered in the course of construction must be accurately and neatly recorded as they occur by means of details and notes. Prepare final record (as-built) drawings after the completion of each definable feature of work as listed in the Contractor Quality Control Plan (Foundations, Utilities, Structural Steel, etc., as appropriate for the project). The working as-built marked prints and final record (as-built) drawings will be jointly reviewed for accuracy and completeness by the Contracting Officer and the Contractor prior to submission of each monthly pay estimate. If the Contractor fails to maintain the working and final record drawings as specified herein, the Contracting Officer will deduct from the monthly progress payment an amount representing the estimated cost of maintaining the record drawings. This monthly deduction will continue until an agreement can be reached between the Contracting Officer and the Contractor regarding the accuracy and completeness of updated drawings. Show on the working and final record drawings, but not limited to, the following

information:

a. The actual location, kinds and sizes of all sub-surface utility lines. In order that the location of these lines and appurtenances may be determined in the event the surface openings or indicators become covered over or obscured, show by offset dimensions to two permanently fixed surface features the end of each run including each change in direction on the record drawings. Locate valves, splice boxes and similar appurtenances by dimensioning along the utility run from a reference point. Also record the average depth below the surface of each run.

b. The location and dimensions of any changes within the building structure.

c. Correct grade, elevations, cross section, or alignment of roads, earthwork, structures or utilities if any changes were made from contract plans.

d. Changes in details of design or additional information obtained from working drawings specified to be prepared and/or furnished by the Contractor; including but not limited to fabrication, erection, installation plans and placing details, pipe sizes, insulation material, dimensions of equipment foundations, etc.

e. The topography, invert elevations and grades of drainage installed or affected as part of the project construction.

f. Changes or modifications which result from the final inspection.

g. Where contract drawings or specifications present options, show only the option selected for construction on the final as-built prints.

h. If borrow material for this project is from sources on Government property, or if Government property is used as a spoil area, furnish a contour map of the final borrow pit/spoil area elevations.

i. Systems designed or enhanced by the Contractor, such as HVAC controls, fire alarm, fire sprinkler, and irrigation systems.

j. Modifications (include within change order price the cost to change working and final record drawings to reflect modifications) and compliance with the following procedures.

(1) Follow directions in the modification for posting descriptive changes.

(2) Place a Modification Circle at the location of each deletion.

(3) For new details or sections which are added to a drawing, place a Modification Circle by the detail or section title.

(4) For minor changes, place a Modification Circle by the area changed on the drawing (each location).

(5) For major changes to a drawing, place a Modification Circle by the title of the affected plan, section, or detail at each location.

(6) For changes to schedules or drawings, place a Modification

Circle either by the schedule heading or by the change in the schedule.

(7) The Modification Circle size shall be 1/2 inch diameter unless the area where the circle is to be placed is crowded. Smaller size circle shall be used for crowded areas.

1.3.1.2 Drawing Preparation

Modify the record drawings as may be necessary to correctly show the features of the project as it has been constructed by bringing the contract set into agreement with approved working as-built prints, and adding such additional drawings as may be necessary. These working as-built marked prints must be neat, legible and accurate. These drawings are part of the permanent records of this project and must be returned to the Contracting Officer after approval by the Government. Any drawings damaged or lost by the Contractor must be satisfactorily replaced by the Contractor at no expense to the Government.

1.3.2 As-Built Record of Equipment and Materials

Furnish one copy of preliminary record of equipment and materials used on the project 15 days prior to final inspection. This preliminary submittal will be reviewed and returned 2 days after final inspection with Government comments. Submit two sets of final record of equipment and materials 10 days after final inspection. Key the designations to the related area depicted on the contract drawings. List the following data:

RECORD OF DESIGNATED EQUIPMENT AND MATERIALS DATA

Description	Specification Section	Manufacturer and Catalog, Model, and Serial Number	Composition and Size	Where Used
-------------	-----------------------	--	----------------------	------------

1.3.3 Final Approved Shop Drawings

Furnish final approved project shop drawings 30 days after transfer of the completed facility.

1.3.4 Construction Contract Specifications

Furnish final record (as-built) construction contract specifications, including modifications thereto, 30 days after transfer of the completed facility.

1.3.5 Real Property Equipment

Furnish a list of installed equipment furnished under this contract. Include all information usually listed on manufacturer's name plate. In the "EQUIPMENT-IN-PLACE LIST" include, as applicable, the following for each piece of equipment installed: description of item, location (by room number), model number, serial number, capacity, name and address of manufacturer, name and address of equipment supplier, condition, spare parts list, manufacturer's catalog, and warranty. Furnish a draft list at time of transfer. Furnish the final list 30 days after transfer of the completed facility.

1.4 SPARE PARTS DATA

Indicate manufacturer's name, part number, nomenclature, and stock level required for maintenance and repair. List those items that may be standard to the normal maintenance of the system.

Supply two items of each part for spare parts inventory. Provision of spare parts does not relieve the Contractor of responsibilities listed under the contract guarantee provisions.

1.5 PREVENTATIVE MAINTENANCE

Submit Preventative Maintenance and Condition Monitoring (Predictive Testing) and Inspection schedules with instructions that state when systems should be retested.

Define the anticipated length of each test, test apparatus, number of personnel identified by responsibility, and a testing validation procedure permitting the record operation capability requirements within the schedule. Provide a signoff blank for the Contractor and Contracting Officer for each test feature; e.g., gpm, rpm, psi. Include a remarks column for the testing validation procedure referencing operating limits of time, pressure, temperature, volume, voltage, current, acceleration, velocity, alignment, calibration, adjustments, cleaning, or special system notes. Delineate procedures for preventative maintenance, inspection, adjustment, lubrication and cleaning necessary to minimize corrective maintenance and repair.

Repair requirements must inform operators how to check out, troubleshoot, repair, and replace components of the system. Include electrical and mechanical schematics and diagrams and diagnostic techniques necessary to enable operation and troubleshooting of the system after acceptance.

1.6 WARRANTY MANAGEMENT

1.6.1 Warranty Management Plan

Develop a warranty management plan which contains information relevant to the clause Warranty of Construction. At least 30 days before the planned pre-warranty conference, submit the warranty management plan for Government approval. Include within the warranty management plan all required actions and documents to assure that the Government receives all warranties to which it is entitled. The plan must be in narrative form and contain sufficient detail to render it suitable for use by future maintenance and repair personnel, whether tradesmen, or of engineering background, not necessarily familiar with this contract. The term "status" as indicated below must include due date and whether item has been submitted or was accomplished. Warranty information made available during the construction phase must be submitted to the Contracting Officer for approval prior to each monthly pay estimate. Assemble approved information in a binder and turn over to the Government upon acceptance of the work. The construction warranty period will begin on the date of project acceptance and continue for the full product warranty period. A joint 4 month and 9 month warranty inspection will be conducted, measured from time of acceptance, by the Contractor, Contracting Officer and the Customer Representative. Include within the warranty management plan, but not limited to, the following:

a. Roles and responsibilities of all personnel associated with the warranty process, including points of contact and telephone numbers within

the organizations of the Contractors, subContractors, manufacturers or suppliers involved.

b. Listing and status of delivery of all Certificates of Warranty for extended warranty items, to include roofs, HVAC balancing, valves, meters, pumps, motors, transformers, and for all commissioned systems such as alarm systems, lightning protection systems, etc.

c. A list for each warranted equipment, item, feature of construction or system indicating:

1. Name of item.
2. Model and serial numbers.
3. Location where installed.
4. Name and phone numbers of manufacturers or suppliers.
5. Names, addresses and telephone numbers of sources of spare parts.
6. Warranties and terms of warranty. Include one-year overall warranty of construction. Items which have extended warranties must be indicated with separate warranty expiration dates.
7. Cross-reference to warranty certificates as applicable.
8. Starting point and duration of warranty period.
9. Summary of maintenance procedures required to continue the warranty in force.
10. Cross-reference to specific pertinent Operation and Maintenance manuals.
11. Organization, names and phone numbers of persons to call for warranty service.
12. Typical response time and repair time expected for various warranted equipment.

d. The Contractor's plans for attendance at the 4 and 9 month post-construction warranty inspections conducted by the Government.

e. Procedure and status of tagging of all equipment covered by extended warranties.

f. Copies of instructions to be posted near selected pieces of equipment where operation is critical for warranty and/or safety reasons.

1.6.2 Performance Bond

The Contractor's Performance Bond must remain effective throughout the construction period.

1.6.3 Pre-Warranty Conference

Prior to contract completion, and at a time designated by the Contracting Officer, meet with the Contracting Officer to develop a mutual understanding with respect to the requirements of this section. Communication procedures for Contractor notification of construction warranty defects, priorities with respect to the type of defect, reasonable time required for Contractor response, and other details deemed necessary by the Contracting Officer for the execution of the construction warranty will be established/reviewed at this meeting. In connection with these requirements and at the time of the Contractor's quality control completion inspection, furnish the name, telephone number and address of a licensed and bonded company which is authorized to initiate and pursue construction warranty work action on behalf of the Contractor. This point of contact

will be located within the local service area of the warranted construction, be continuously available, and be responsive to Government inquiry on warranty work action and status. This requirement does not relieve the Contractor of any of its responsibilities in connection with other portions of this provision.

1.6.4 Contractor's Response to Construction Warranty Service Requirements

Following oral or written notification by the Contracting Officer, respond to construction warranty service requirements in accordance with the "Construction Warranty Service Priority List" and the three categories of priorities listed below. Submit a report on any warranty item that has been repaired during the warranty period. Include within the report the cause of the problem, date reported, corrective action taken, and when the repair was completed. If the Contractor does not perform the construction warranty within the timeframes specified, the Government will perform the work and backcharge the construction warranty payment item established.

a. First Priority Code 1. Perform onsite inspection to evaluate situation, and determine course of action within 4 hours, initiate work within 6 hours and work continuously to completion or relief.

b. Second Priority Code 2. Perform onsite inspection to evaluate situation, and determine course of action within 8 hours, initiate work within 24 hours and work continuously to completion or relief.

c. Third Priority Code 3. All other work to be initiated within 3 work days and work continuously to completion or relief.

d. The "Construction Warranty Service Priority List" is as follows:

Code 1-Air Conditioning Systems

- (1) Recreational support.
- (2) Air conditioning leak in part of building, if causing damage.
- (3) Air conditioning system not cooling properly.

Code 1-Doors

- (1) Overhead doors not operational, causing a security, fire, or safety problem.
- (2) Interior, exterior personnel doors or hardware, not functioning properly, causing a security, fire, or safety problem.

Code 3-Doors

- (1) Overhead doors not operational.
- (2) Interior/exterior personnel doors or hardware not functioning properly.

Code 1-Electrical

- (1) Power failure (entire area or any building operational after 1600 hours).
- (2) Security lights
- (3) Smoke detectors

Code 2-Electrical

- (1) Power failure (no power to a room or part of building).
- (2) Receptacle and lights (in a room or part of building).

Code 3-Electrical

Street lights.

Code 1-Gas

- (1) Leaks and breaks.
- (2) No gas to family housing unit or cantonment area.

Code 1-Heat

- (1). Area power failure affecting heat.
- (2). Heater in unit not working.

Code 2-Kitchen Equipment

- (1) Dishwasher not operating properly.
- (2) All other equipment hampering preparation of a meal.

Code 1-Plumbing

- (1) Hot water heater failure.
- (2) Leaking water supply pipes.

Code 2-Plumbing

- (1) Flush valves not operating properly.
- (2) Fixture drain, supply line to commode, or any water pipe leaking.
- (3) Commode leaking at base.

Code 3 -Plumbing

Leaky faucets.

Code 3-Interior

- (1) Floors damaged.
- (2) Paint chipping or peeling.
- (3) Casework.

Code 1-Roof Leaks

Temporary repairs will be made where major damage to property is occurring.

Code 2-Roof Leaks

Where major damage to property is not occurring, check for location of leak during rain and complete repairs on a Code 2 basis.

Code 2-Water (Exterior)

No water to facility.

Code 2-Water (Hot)

No hot water in portion of building listed.

Code 3-All other work not listed above.

1.6.5 Warranty Tags

At the time of installation, tag each warranted item with a durable, oil and water resistant tag approved by the Contracting Officer. Attached each tag with a copper wire and spray with a silicone waterproof coating. The date of acceptance and the QC signature must remain blank until the project is accepted for beneficial occupancy. Show the following information on the tag.

a. Type of product/material_____.

b. Model number_____.

- c. Serial number_____.
- d. Contract number_____.
- e. Warranty period_____from_____to_____.
- f. Inspector's signature_____.
- g. Construction Contractor_____.
- Address_____.
- Telephone number_____.
- h. Warranty contact_____.
- Address_____.
- Telephone number_____.
- i. Warranty response time priority code_____.

j. WARNING - PROJECT PERSONNEL TO PERFORM ONLY OPERATIONAL MAINTENANCE DURING THE WARRANTY PERIOD.

1.7 CLEANUP

Provide final cleaning in accordance with ASTM E 1971. Leave premises "broom clean." Use only nonhazardous cleaning materials, including natural cleaning materials, in the final cleanup. Clean interior and exterior glass surfaces exposed to view; remove temporary labels, stains and foreign substances; polish transparent and glossy surfaces. Clean equipment and fixtures to a sanitary condition. Clean filters of operating equipment and comply with the Indoor Air Quality (IAQ) Management Plan. Clean debris from roofs, gutters, downspouts and drainage systems. Sweep paved areas and rake clean landscaped areas. Remove waste and surplus materials, rubbish and construction facilities from the site. Recycle, salvage, and return construction and demolition waste from project in accordance with the Waste Management Plan. Promptly and legally transport and dispose of any trash. Do not burn, bury, or otherwise dispose of trash on the project site.

PART 2 PRODUCTS (NOT USED)

PART 3 EXECUTION (NOT USED)

-- End of Section --

SECTION TABLE OF CONTENTS

DIVISION 02 - EXISTING CONDITIONS

SECTION 02 41 00

DEMOLITION AND DECONSTRUCTION

PART 1 GENERAL

- 1.1 REFERENCES
- 1.2 GENERAL REQUIREMENTS
- 1.3 SUBMITTALS
- 1.4 REGULATORY AND SAFETY REQUIREMENTS
 - 1.4.1 Notifications
 - 1.4.1.1 General Requirements
- 1.5 DUST AND DEBRIS CONTROL
- 1.6 PROTECTION
 - 1.6.1 Traffic Control Signs
 - 1.6.2 Existing Conditions Documentation
 - 1.6.3 Items to Remain in Place
 - 1.6.4 Existing Construction Limits and Protection
 - 1.6.5 Weather Protection
 - 1.6.6 Trees
 - 1.6.7 Utility Service
 - 1.6.8 Facilities
 - 1.6.9 Protection of Personnel
- 1.7 BURNING
- 1.8 RELOCATIONS
- 1.9 REQUIRED DATA
- 1.10 ENVIRONMENTAL PROTECTION
- 1.11 USE OF EXPLOSIVES

PART 2 PRODUCTS

- 2.1 FILL MATERIAL

PART 3 EXECUTION

- 3.1 EXISTING FACILITIES TO BE REMOVED
 - 3.1.1 Structures
 - 3.1.2 Utilities and Related Equipment
 - 3.1.2.1 General Requirements
 - 3.1.2.2 Disconnecting Existing Utilities
 - 3.1.3 Paving and Slabs
 - 3.1.4 Concrete
 - 3.1.5 Structural Steel
 - 3.1.6 Miscellaneous Metal
 - 3.1.7 Carpentry
 - 3.1.8 Cylinders and Canisters
 - 3.1.9 Mechanical Equipment and Fixtures
 - 3.1.9.1 Preparation for Storage
 - 3.1.9.2 Piping
 - 3.1.9.3 Fixtures, Motors and Machines

- 3.1.10 Electrical Equipment and Fixtures
 - 3.1.10.1 Fixtures
 - 3.1.10.2 Electrical Devices
 - 3.1.10.3 Wiring Ducts or Troughs
 - 3.1.10.4 Conduit and Miscellaneous Items
- 3.1.11 Items With Unique/Regulated Disposal Requirements
- 3.2 CONCURRENT EARTH-MOVING OPERATIONS
- 3.3 DISPOSITION OF MATERIAL
 - 3.3.1 Title to Materials
 - 3.3.2 Export Control
 - 3.3.3 Reuse of Materials and Equipment
 - 3.3.4 Salvaged Materials and Equipment
 - 3.3.5 Recycling
 - 3.3.6 Disposal of Ozone Depleting Substance (ODS)
 - 3.3.6.1 Special Instructions
 - 3.3.6.2 Fire Suppression Containers
 - 3.3.7 Unsalvageable and Non-Recyclable Material
- 3.4 CLEANUP
- 3.5 DISPOSAL OF REMOVED MATERIALS
 - 3.5.1 Regulation of Removed Materials
 - 3.5.2 Burning on Government Property
 - 3.5.3 Removal to Spoil Areas on Government Property
 - 3.5.4 Removal from Government Property
- 3.6 REUSE OF SALVAGED ITEMS

-- End of Section Table of Contents --

SECTION 02 41 00

DEMOLITION AND DECONSTRUCTION

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AIR-CONDITIONING AND REFRIGERATION INSTITUTE (ARI)

ARI Guideline K (2005) Guideline for Containers for Recovered Non-Flammable Fluorocarbon Refrigerants

AMERICAN SOCIETY OF SAFETY ENGINEERS (ASSE/SAFE)

ASSE/SAFE A10.6 (2006) Safety Requirements for Demolition Operations

U.S. FEDERAL AVIATION ADMINISTRATION (FAA)

FAA AC 70/7460-1 (Rev K; Change 1) Obstruction Marking and Lighting

U.S. NATIONAL ARCHIVES AND RECORDS ADMINISTRATION (NARA)

40 CFR 61 National Emission Standards for Hazardous Air Pollutants

40 CFR 82 Protection of Stratospheric Ozone

1.2 GENERAL REQUIREMENTS

Do not begin demolition or deconstruction until authorization is received from the Contracting Officer. The work of this section is to be performed in a manner that maximizes salvage and recycling of materials. Remove rubbish and debris from the project site; do not allow accumulations inside or outside the buildings. The work includes demolition, deconstruction, salvage of identified items and materials, and removal of resulting rubbish and debris. Remove rubbish and debris from Government property daily, unless otherwise directed. Store materials that cannot be removed daily in areas specified by the Contracting Officer. In the interest of occupational safety and health, perform the work in accordance with OSHA, NASA/KSC Health and Safety Policies, and other applicable Sections.

1.3 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for Contractor Quality Control approval. The following shall be submitted in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-01 Preconstruction Submittals

Existing Conditions; G
Demolition Plan; G
Notifications; G

Proposed salvage, demolition, deconstruction, and removal procedures for approval before work is started.

SD-07 Certificates

Certification of DBPR certified pollutant storage contractor; G

1.4 REGULATORY AND SAFETY REQUIREMENTS

Comply with federal, state, and local hauling and disposal regulations. In addition to the requirements of the "Contract Clauses," conform to the safety requirements contained in ASSE/SAFE A10.6.

1.4.1 Notifications

1.4.1.1 General Requirements

Furnish timely notification of demolition and deconstruction projects to Federal, State, regional, and local authorities in accordance with 40 CFR 61, Subpart M. Notify the State's environmental protection agency and the Contracting Officer in writing 10 working days prior to the commencement of work in accordance with 40 CFR 61, Subpart M.

1.5 DUST AND DEBRIS CONTROL

Prevent the spread of dust and debris and avoid the creation of a nuisance or hazard in the surrounding area. Do not use water if it results in hazardous or objectionable conditions such as, but not limited to, ice, flooding, or pollution.

Contractor shall use best management control measures to prevent the release of paint chips to the environment.

Best management practices include, but are not limited to, the following:

- a. Contractor shall contain demolition debris where possible to impermeable surfaces.
- b. Contractor shall control stormwater runoff from the site with silt fencing.
- c. Contractor shall conduct daily housekeeping to limit potential paint chip migration.
- d. Contractor shall collect and remove all demolition debris from the project area.
- e. Sediment collected adjacent to silt fence shall be containerized and disposed of appropriately.
- f. Upon completion of demolition, the first 6 inches of top soil shall be removed from within and 6 feet beyond the project area and disposed of

in the KSC landfill.

1.6 PROTECTION

1.6.1 Traffic Control Signs

Where pedestrian and driver safety is endangered in the area of removal work, use traffic barricades with flashing lights. Anchor barricades in a manner to prevent displacement by wind. Notify the Contracting Officer prior to beginning such work.

Contractor must provide a minimum of 2 aviation red or high intensity white obstruction lights on temporary structures (including cranes) over 100 feet above ground level. Light construction and installation must comply with FAA AC 70/7460-1. Lights must be operational during periods of reduced visibility, darkness, and as directed by the Contracting Officer. Maintain the temporary services during the period of construction and remove only after permanent services have been installed and tested and are in operation.

1.6.2 Existing Conditions Documentation

Before beginning any demolition or deconstruction work, survey the site and examine the drawings and specifications to determine the extent of the work. Record existing conditions in the presence of the Contracting Officer showing the condition of structures and other facilities adjacent to areas of alteration or removal. Digital photographs sized 4 inch will be acceptable as a record of existing conditions. Include in the record the elevation of the top of foundation walls, finish floor elevations, possible conflicting electrical conduits, plumbing lines, alarms systems, the location and extent of existing cracks and other damage and description of surface conditions that exist prior to before starting work. It is the Contractor's responsibility to verify and document all required outages which will be required during the course of work, and to note these outages on the record document.

1.6.3 Items to Remain in Place

Take necessary precautions to avoid damage to existing items to remain in place, to be reused, or to remain the property of the Government. Repair or replace damaged items as approved by the Contracting Officer. Coordinate the work of this section with all other work indicated. Construct and maintain shoring, bracing, and supports as required. Ensure that structural elements are not overloaded. Increase structural supports or add new supports as may be required as a result of any cutting, removal, deconstruction, or demolition work performed under this contract. Do not overload structural elements. Provide new supports and reinforcement for existing construction weakened by demolition, deconstruction, or removal work. Repairs, reinforcement, or structural replacement require approval by the Contracting Officer prior to performing such work.

1.6.4 Existing Construction Limits and Protection

Do not disturb existing construction beyond the extent indicated or necessary for installation of new construction. Provide temporary shoring and bracing for support of building components to prevent settlement or other movement. Provide protective measures to control accumulation and migration of dust and dirt in all work areas. Remove dust, dirt, and debris from work areas daily.

1.6.5 Weather Protection

For portions of the building to remain, protect building interior and materials and equipment from the weather at all times. Where removal of existing roofing is necessary to accomplish work, have materials and workmen ready to provide adequate and temporary covering of exposed areas.

1.6.6 Trees

Protect trees within the project site which might be damaged during demolition or deconstruction, and which are indicated to be left in place, by a 6 foot high fence. Erect and secure fence a minimum of 5 feet from the trunk of individual trees or follow the outer perimeter of branches or clumps of trees. Replace any tree designated to remain that is damaged during the work under this contract with like-kind or as approved by the Contracting Officer.

1.6.7 Utility Service

Maintain existing utilities indicated to stay in service and protect against damage during demolition and deconstruction operations. Prior to start of work, utilities serving each area of alteration or removal will be shut off by the Government and disconnected and sealed by the Contractor.

1.6.8 Facilities

Protect electrical and mechanical services and utilities. Where removal of existing utilities and pavement is specified or indicated, provide approved barricades, temporary covering of exposed areas, and temporary services or connections for electrical and mechanical utilities. Floors, roofs, walls, columns, pilasters, and other structural components that are designed and constructed to stand without lateral support or shoring, and are determined to be in stable condition, must remain standing without additional bracing, shoring, or lateral support until demolished or deconstructed, unless directed otherwise by the Contracting Officer. Ensure that no elements determined to be unstable are left unsupported and place and secure bracing, shoring, or lateral supports as may be required as a result of any cutting, removal, deconstruction, or demolition work performed under this contract.

1.6.9 Protection of Personnel

Before, during and after the demolition and deconstruction work the Contractor shall continuously evaluate the condition of the structure being demolished and deconstructed and take immediate action to protect all personnel working in and around the project site. No area, section, or component of floors, roofs, walls, columns, pilasters, or other structural element will be allowed to be left standing without sufficient bracing, shoring, or lateral support to prevent collapse or failure while workmen remove debris or perform other work in the immediate area.

1.7 BURNING

The use of burning at the project site for the disposal of refuse and debris will not be permitted.

1.8 RELOCATIONS

Perform the removal and reinstallation of relocated items as indicated with workmen skilled in the trades involved. Items to be relocated which are damaged by the Contractor shall be repaired or replaced with new undamaged items as approved by the Contracting Officer.

1.9 REQUIRED DATA

Prepare a Demolition Plan. Include in the plan procedures for careful removal and disposition of materials specified to be salvaged, coordination with other work in progress, and a disconnection schedule of utility services, a detailed description of methods and equipment to be used for each operation and of the sequence of operations. Identify components and materials to be salvaged for reuse or recycling with reference to paragraph Existing Facilities to be Removed. Append tracking forms for all removed materials indicating type, quantities, condition, destination, and end use. Coordinate with Waste Management Plan. Include statements affirming Contractor inspection of the existing roof deck and its suitability to perform as a safe working platform or if inspection reveals a safety hazard to workers, state provisions for securing the safety of the workers throughout the performance of the work. Submit certification of DBPR certified pollutant storage contractor for removal of underground storage tank. Provide procedures for safe conduct of the work in accordance with Section 01 35 26 GOVERNMENT SAFETY REQUIREMENTS. Plan shall be approved by Contracting Officer prior to work beginning.

1.10 ENVIRONMENTAL PROTECTION

Comply with the Environmental Protection Agency and NASA/KSC requirements specified.

Best Management Practices (BMPs) must be used to prevent releases of metal and/or PCB contaminated paint chips to the environment. The following are offered as suggested BMPs:

1. Where possible, demolish structures by collapsing walls inward onto facility foundation.
2. Where possible, limit heavy equipment use to paved surfaces.
3. Control stormwater runoff from paved areas by installing silt fencing and/or sediment barriers across stormwater flumes.
4. Drum or containerize, using appropriate PWQ/TRP listed containers, all paint chip contaminated sediments and submit debris for testing. Dispose of characterized sediment waste in accordance with KSC Waste Management Requirements following the PWQ/TRP process.
5. Maintain regular housekeeping on the construction site thus preventing significant stormwater runoff before it occurs.

1.11 USE OF EXPLOSIVES

Use of explosives will not be permitted.

PART 2 PRODUCTS

2.1 FILL MATERIAL

Comply with excavating, backfilling, and compacting procedures for soils used as backfill material to fill basements, voids, depressions or excavations resulting from demolition or deconstruction of structures above and below grade. Fill material shall be waste products from demolition or deconstruction until all waste appropriate for this purpose is consumed.

PART 3 EXECUTION

3.1 EXISTING FACILITIES TO BE REMOVED

Inspect and evaluate existing structures on site for reuse. Existing construction scheduled to be removed for reuse shall be disassembled. Dismantled and removed materials are to be separated, set aside, and prepared as specified, and stored or delivered to a collection point for reuse, remanufacture, recycling, or other disposal, as specified. Materials shall be designated for reuse on site whenever possible.

3.1.1 Structures

a. Remove existing structures indicated to bottom of foundation walls. Interior walls, other than retaining walls and partitions, shall be removed below grade or to top of concrete slab on ground as specified in the contract documents. Break up basement slabs to permit drainage. Remove sidewalks, curbs, gutters and street light bases as indicated.

b. Demolish structures in a systematic manner from the top of the structure to the ground. Complete demolition work above each tier or floor before the supporting members on the lower level are disturbed. Demolish concrete and masonry walls in small sections. Remove structural framing members and lower to ground by means of derricks, platforms hoists, or other suitable methods as approved by the Contracting Officer.

c. Locate demolition and deconstruction equipment throughout the structure and remove materials so as to not impose excessive loads to supporting walls, floors, or framing.

d. Building, or the remaining portions thereof, not exceeding 80 feet in height may be demolished by the mechanical method of demolition.

3.1.2 Utilities and Related Equipment

3.1.2.1 General Requirements

Do not interrupt existing utilities serving occupied or used facilities, except when authorized in writing by the Contracting Officer. Do not interrupt existing utilities serving facilities occupied and used by the Government except when approved in writing and then only after temporary utility services have been approved and provided. Do not begin demolition or deconstruction work until all utility disconnections have been made. Shut off and cap utilities for future use, as indicated.

3.1.2.2 Disconnecting Existing Utilities

Remove existing utilities, as indicated and uncovered by work and terminate in a manner conforming to the nationally recognized code covering the specific utility and approved by the Contracting Officer. When utility lines are encountered that are not indicated on the drawings, the Contracting Officer shall be notified prior to further work in that area. Remove meters and related equipment and deliver to a location in accordance with instructions of the Contracting Officer.

3.1.3 Paving and Slabs

Remove concrete and asphaltic concrete paving and slabs including aggregate base as indicated. Provide neat sawcuts at limits of pavement removal as indicated. Pavement and slabs designated to be recycled and utilized in this project shall be moved, ground and stored as directed by the Contracting Officer. Unpainted concrete shall be transported to DARC in accordance with the contract clause "Landfill Operations/Solid Waste Removal".

3.1.4 Concrete

Salvage removed concrete.

3.1.5 Structural Steel

Dismantle structural steel at field connections and in a manner that will prevent bending or damage. Salvage for reuse or recycle structural steel, steel joists, girders, angles, plates, columns and shapes. Flame-cutting torches are permitted when other methods of dismantling are not practical. Where possible, hot work on painted/coated metal structures should be avoided. If hot work is necessary, affected paint/coating must be sampled for PCBs to determine if additional respiratory protection is required. Degradation of PCBs occur under moderate/extreme thermal conditions (such as torch work) causing PCB materials to degrade into dioxins and other by-product chemicals. The Contractor shall consult with its Industrial Hygiene representative prior to conducting hot work on any painted/coated surfaces.

3.1.6 Miscellaneous Metal

Salvage shop-fabricated items such as access doors and frames, steel gratings, metal ladders, wire mesh partitions, metal railings, metal windows and similar items as whole units. Salvage light-gage and cold-formed metal framing, such as steel studs, steel trusses, metal gutters, roofing and siding, metal toilet partitions, toilet accessories and similar items. Scrap metal shall become the Contractor's property. Recycle scrap metal as part of demolition and deconstruction operations. Provide separate containers to collect scrap metal and transport to a scrap metal collection or recycling facility, in accordance with the Waste Management Plan.

3.1.7 Carpentry

Salvage for reuse or recycle lumber, millwork items, and finished boards, and sort by type and size. Chip or shred and recycle salvaged wood unfit for reuse, except stained, painted, or treated wood.

3.1.8 Cylinders and Canisters

Remove all fire suppression system cylinders and canisters and dispose of in accordance with the paragraph entitled "Disposal of Ozone Depleting Substance (ODS)."

3.1.9 Mechanical Equipment and Fixtures

Disconnect mechanical hardware at the nearest connection to existing services to remain, unless otherwise noted. Mechanical equipment and fixtures must be disconnected at fittings. Remove service valves attached to the unit. Where indicated, salvage each item of equipment and fixtures as a whole unit; listed, indexed, tagged, and stored. Salvage each unit with its normal operating auxiliary equipment. Transport salvaged equipment and fixtures, including motors and machines, to a designated storage area as directed by the Contracting Officer. Do not remove equipment until approved. Do not offer low-efficiency equipment for reuse; provide to recycling service for disassembly and recycling of parts.

3.1.9.1 Preparation for Storage

Remove water, dirt, dust, and foreign matter from units; tanks, piping and fixtures shall be drained; interiors, if previously used to store flammable, explosive, or other dangerous liquids, must be steam cleaned. Seal openings with caps, plates, or plugs. Secure motors attached by flexible connections to the unit.

3.1.9.2 Piping

Disconnect piping at unions, flanges and valves, and fittings as required to reduce the pipe into straight lengths for practical storage. Store salvaged piping according to size and type. If the piping that remains can become pressurized due to upstream valve failure, end caps, blind flanges, or other types of plugs or fittings with a pressure gage and bleed valve shall be attached to the open end of the pipe to ensure positive leak control. Carefully dismantle piping that previously contained gas, gasoline, oil, or other dangerous fluids, with precautions taken to prevent injury to persons and property. Store piping outdoors until all fumes and residues are removed. Box prefabricated supports, hangers, plates, valves, and specialty items according to size and type. Wrap sprinkler heads individually in plastic bags before boxing. Classify piping not designated for salvage, or not reusable, as scrap metal.

3.1.9.3 Fixtures, Motors and Machines

Drain oil and grease on motors and machines in accordance with Section 02 84 33 REMOVAL AND DISPOSAL OF POLYCHLORINATED BIPHENYLS (PCBs). Where indicated, remove and salvage fixtures, motors and machines associated with plumbing, heating, air conditioning, refrigeration, and other mechanical system installations. Salvage, box and store auxiliary units and accessories with the main motor and machines. Tag salvaged items for identification, storage, and protection from damage. Classify broken, damaged, or otherwise unserviceable units and not caused to be broken, damaged, or otherwise unserviceable as debris and disposed of by the Contractor.

3.1.10 Electrical Equipment and Fixtures

Where indicated, salvage motors, motor controllers, and operating and

control equipment that are attached to the driven equipment. Salvage wiring systems and components. Box loose items and tag for identification. Disconnect primary, secondary, control, communication, and signal circuits at the point of attachment to their distribution system.

3.1.10.1 Fixtures

Remove and salvage electrical fixtures. Salvage unprotected glassware from the fixture and salvage separately. Salvage incandescent, mercury-vapor, and fluorescent lamps and fluorescent ballasts manufactured prior to 1978, boxed and tagged for identification, and protected from breakage. Note: Ballasts that cannot be identified as being PCB-free shall be managed as if they are PCB-contaminated.

3.1.10.2 Electrical Devices

Remove and salvage switches, switchgear, transformers, conductors including wire and nonmetallic sheathed and flexible armored cable, regulators, meters, instruments, plates, circuit breakers, panelboards, outlet boxes, and similar items. Box and tag these items for identification according to type and size.

3.1.10.3 Wiring Ducts or Troughs

Remove and salvage wiring ducts or troughs. Dismantle plug-in ducts and wiring troughs into unit lengths. Remove plug-in or disconnecting devices from the busway and store separately.

3.1.10.4 Conduit and Miscellaneous Items

Salvage conduit except where embedded in concrete or masonry. Consider corroded, bent, or damaged conduit as scrap metal. Sort straight and undamaged lengths of conduit according to size and type. Classify supports, knobs, tubes, cleats, and straps as debris to be removed and disposed.

3.1.11 Items With Unique/Regulated Disposal Requirements

Remove and dispose of items with unique or regulated disposal requirements in the manner dictated by law or in the most environmentally responsible manner.

3.2 CONCURRENT EARTH-MOVING OPERATIONS

Do not begin excavation, filling, and other earth-moving operations that are sequential to demolition or deconstruction work in areas occupied by structures to be demolished or deconstructed until all demolition and deconstruction in the area has been completed and debris removed. Fill holes, open basements and other hazardous openings.

3.3 DISPOSITION OF MATERIAL

3.3.1 Title to Materials

Except for salvaged items specified in related Sections, and for materials or equipment scheduled for salvage, all materials and equipment removed and not reused or salvaged, shall become the property of the Contractor and shall be removed from Government property. Title to materials resulting from demolition and deconstruction, and materials and equipment to be

removed, is vested in the Contractor upon approval by the Contracting Officer of the Contractor's demolition, deconstruction, and removal procedures, and authorization by the Contracting Officer to begin demolition and deconstruction. The Government will not be responsible for the condition or loss of, or damage to, such property after contract award. Showing for sale or selling materials and equipment on site is prohibited.

3.3.2 Export Control

The Contractor shall comply with U.S. Export Control Laws. All facilities and associated equipment shall be deconstructed so that they can neither be reassembled nor recognized. The Contractor shall render unrecognizable all NASA and Contractor tags.

3.3.3 Reuse of Materials and Equipment

Remove and store materials and equipment listed in the Demolition Plan or as indicated by the Contracting Officer to be reused or relocated to prevent damage, and reinstall as the work progresses.

3.3.4 Salvaged Materials and Equipment

Remove materials and equipment that are listed in the Demolition Plan and specified to be removed by the Contractor and that are to remain the property of the Government, and deliver to the Reutilization, Recycling and Marketing Facility (RRMF).

- a. Salvage items and material to the maximum extent possible.
- b. Store all materials salvaged for the Contractor as approved by the Contracting Officer and remove from Government property before completion of the contract. Material salvaged for the Contractor shall not be sold on the site.
- c. Remove salvaged items to remain the property of the Government in a manner to prevent damage, and packed or crated to protect the items from damage while in storage or during shipment. Items damaged during removal or storage must be repaired or replaced to match existing items. Properly identify the contents of containers.
- d. Remove historical items in a manner to prevent damage.
- e. Remove and capture all Class I ODS refrigerants in accordance with the Clean Air Act Amendment of 1990.

3.3.5 Recycling

The Contractor must make every practical effort to reclaim and segregate materials that have the ability to be recycled. All reclaimed concrete must be segregated from other wastes and transported to the KSC Landfill (L7-0071) on Schwartz Road. All unpainted concrete must be transported to the Diverted Aggregate Reclamation and Collection Yard (DARCY). All reclaimed scrap metal, not being recycled by Contractor outside KSC, must be transported to the Reutilization, Recycling and Marketing Facility (RRMF) with a KSC Form 7-49. Please turn these items and the KSC Form 7-49 into RRMF personnel to ensure the proper disposition of the materials prior to leaving the recycling area. For any other information regarding what materials can be recycled or other general information regarding recycling

policies at KSC, please contact NASA Environmental.

3.3.6 Disposal of Ozone Depleting Substance (ODS)

Class I and Class II ODS are defined in Section, 602(a) and (b), of The Clean Air Act. Prevent discharge of Class I and Class II ODS to the atmosphere. Place recovered ODS in cylinders meeting ARI Guideline K suitable for the type ODS (filled to no more than 80 percent capacity) and provide appropriate labeling. Recovered ODS shall be turned over to the Contracting Officer. Products, equipment and appliances containing ODS in a sealed, self-contained system (e.g. residential refrigerators and window air conditioners) shall be disposed of in accordance with 40 CFR 82.

3.3.6.1 Special Instructions

No more than one type of ODS is permitted in each container. A warning/hazardous label shall be applied to the containers in accordance with the contract clause "Hazardous Waste". All cylinders including but not limited to fire extinguishers, spheres, or canisters containing an ODS shall have a tag with the following information:

- a. Activity name and unit identification code
- b. Activity point of contact and phone number
- c. Type of ODS and pounds of ODS contained
- d. Date of shipment

3.3.6.2 Fire Suppression Containers

Deactivate fire suppression system cylinders and canisters with electrical charges or initiators prior to shipment. Also, safety caps must be used to cover exposed actuation mechanisms and discharge ports on these special cylinders.

3.3.7 Unsalvageable and Non-Recyclable Material

Dispose of unsalvageable and non-recyclable noncombustible material in the KSC Class III landfill located on Schwartz Road in accordance with Section 01 57 20.00 10 ENVIRONMENTAL PROTECTION.

3.4 CLEANUP

Remove debris and rubbish from excavations. Remove and transport them in a manner that prevents spillage on streets or adjacent areas. Apply local regulations regarding hauling and disposal.

3.5 DISPOSAL OF REMOVED MATERIALS

3.5.1 Regulation of Removed Materials

Dispose of debris, rubbish, scrap, and other nonsalvageable materials resulting from removal operations with all applicable federal, state and local regulations as contractually specified in the Waste Management Plan and Section 01 57 20.00 10 ENVIRONMENTAL PROTECTION. Storage of removed materials on the project site is prohibited, unless otherwise specified on the drawings.

3.5.2 Burning on Government Property

Burning of materials removed from demolished and deconstructed structures will not be permitted on Government property.

3.5.3 Removal to Spoil Areas on Government Property

Transport noncombustible materials removed from demolition and deconstruction structures to designated spoil areas on Government property.

3.5.4 Removal from Government Property

Transport waste materials removed from demolished and deconstructed structures, except waste soil, from Government property for legal disposal. Dispose of waste soil as directed.

3.6 REUSE OF SALVAGED ITEMS

Recondition salvaged materials and equipment designated for reuse before installation. Replace items damaged during removal and salvage operations or restore them as necessary to usable condition.

-- End of Section --

SECTION TABLE OF CONTENTS

DIVISION 02 - EXISTING CONDITIONS

SECTION 02 82 13.00 98

ASBESTOS ABATEMENT

PART 1 GENERAL

- 1.1 SUMMARY
- 1.2 DEFINITIONS
- 1.3 REFERENCES
- 1.4 DESCRIPTION OF WORK
- 1.5 SUBMITTALS
- 1.6 LICENSES PERMITS, AND NOTICES
 - 1.6.1 Notification
- 1.7 IMPLEMENTATION PLAN
- 1.8 AIR MONITORING REPORTS
 - 1.8.1 Air Sample Analytical Method
 - 1.8.2 Air Sampling Rate, Volumes and Frequency
- 1.9 WORKER PROTECTION

PART 2 PRODUCTS

PART 3 EXECUTION

- 3.1 TEMPORARY UTILITIES AND SERVICES
- 3.2 WORK AREA PREPARATION
 - 3.2.1 Pre-Cleaning
 - 3.2.2 Work Area(s)
- 3.3 WASTE LOAD-OUT UNIT
- 3.4 SIGNS AND MARKINGS
- 3.5 NEGATIVE AIR SYSTEM
 - 3.5.1 Testing
- 3.6 RESPIRATORY PROTECTION
 - 3.6.1 Air Quality for Supplied Air Respiratory Systems
- 3.7 REMOVAL OF ASBESTOS
- 3.8 DAILY HOUSEKEEPING
- 3.9 CLEANING PROCEDURES
- 3.10 INSPECTION
 - 3.10.1 Initial Inspection
 - 3.10.2 Daily Inspection
 - 3.10.3 Final Inspection
- 3.11 ASBESTOS WASTE AND CONTAMINATED MATERIALS
 - 3.11.1 Removal of Asbestos Waste Materials
 - 3.11.1.1 Waste Inventory
 - 3.11.2 Work Area Disposal
 - 3.11.3 Decontamination Area And Support Area Disposal
- 3.12 WASTE TRANSPORTATION AND DISPOSAL
- 3.13 ASBESTOS ABATEMENT NOTICE AND CHECKLIST
- 3.14 FINAL ACCEPTANCE

-- End of Section Table of Contents --

SECTION 02 82 13.00 98

ASBESTOS ABATEMENT

PART 1 GENERAL

1.1 SUMMARY

This section specifies the asbestos abatement requirements and the Contractor's applicable asbestos procedures, which include demolition or salvage of structures where asbestos is present, removal or encapsulation of materials containing asbestos, construction, alteration, repair, maintenance, or renovation of structures, substrates, or portions thereof, that contain asbestos, installation of products containing asbestos, asbestos spill/emergency cleanup, transportation, disposal, storage, containment of and housekeeping activities involving asbestos or products containing asbestos, on the site or location at which construction activities are performed.

Under OSHA, Asbestos Abatement work is categorized into four classes:

Class I Work: Activities involving the removal of Thermal System Insulation (TSI) and surfacing Asbestos Containing Materials (ACM) and Presumed Asbestos Containing Material (PACM).

Class II Work: Activities involving the removal of ACM that is not TSI or surfacing material. This includes wallboard, floor tile and sheeting, roofing, siding, shingles, and construction mastics.

Class III Work: Repair and Maintenance operations, where ACM, including TSI and surfacing ACM and PACM, is likely to be disturbed.

Class IV Work: Maintenance and custodial activities during which employees contact but do not disturb ACM or PACM and activities to clean up dust, waste, and debris from Class I,II, and III activities.

Conduct abatement work in accordance with the Class I, II, III, or IV Methods of Compliance as required by 29 CFR 1910,29 CFR 1926, 40 CFR 61-SUBPART M, 49 CFR 171, 49 CFR 172, FAC CHAPTER 62-257, and FL-STAT 469. Submit all required training certifications prior to commencement of work.

1.2 DEFINITIONS

FLAC - Florida Licensed Asbestos Consultant as defined within the FL-STAT 469 ASBESTOS ABATEMENT.

IH - Kennedy Space Center Industrial Hygienist. This person can be either a Government Civil Servant or an authorized Government Contractor. This person is responsible for the oversight, approval of the abatement procedures and the health, safety, and welfare of those who it effects.

1.3 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

COMPRESSED GAS ASSOCIATION (CGA)

CGA G-7.1 (2004) Commodity Specification for Air

FLORIDA ADMINISTRATIVE CODE (FAC)

FAC CHAPTER 62-257 Florida Administrative Code, Asbestos Program

FLORIDA STATUTES (FL-STAT)

FL-STAT 469 Asbestos Abatement

JOHN F. KENNEDY SPACE CENTER (KSC)

KNPR 8500.1 (2007) KSC Environmental Requirements

KNPR 1840.19 KSC Industrial Hygiene Programs

KNPR 8715.3 KSC Safety Practices Procedural Requirements

NATIONAL INSTITUTE FOR OCCUPATIONAL SAFETY AND HEALTH (NIOSH)

NIOSH 7400 (1994) Standard Test Method for Asbestos and Other Fibers by PCM

NIOSH 94-113 (1994; 4th Ed) NIOSH Manual of Analytical Methods

U.S. NATIONAL ARCHIVES AND RECORDS ADMINISTRATION (NARA)

29 CFR 1910 Occupational Safety and Health Standards

29 CFR 1926 Safety and Health Regulations for Construction

40 CFR 61-SUBPART M National Emission Standard for Asbestos

40 CFR 763 Asbestos

49 CFR 171 General Information, Regulations, and Definitions

49 CFR 172 Hazardous Materials Table, Special Provisions, Hazardous Materials Communications, Emergency Response Information, and Training Requirements

1.4 DESCRIPTION OF WORK

Abate materials containing asbestos as indicated on the drawings in accordance with the contract clause "Asbestos Abatement."

1.5 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for Contractor Quality Control approval. Submit the following in accordance with Section 01 33 00

SUBMITTAL PROCEDURES:

SD-01 Preconstruction Submittals

Submit Work Schedule; G in accordance with the paragraph entitled, "Worker Protection," of this section.

Notification of Demolition/Renovation; G

SD-02 Shop Drawings

Submit items in accordance with the paragraph entitled, "Implementation Plan," of this section.

Coordination Drawings; G

Detailed Drawings

SD-06 Test Reports

Submit the following:

Initial Exposure Assessments in accordance with 29 CFR 1926

Submit Air Monitoring Reports in accordance with paragraph entitled, "Air Monitoring Report," of this section.

Maintain Work Site entry logs of all personnel entering and leaving the regulated work area by the on-site competent person indicating the date and time of entry and egress.

Maintain Daily Site Inspection Logs by the on-site competent person indicating the date, time and results of the work area daily site inspections.

Maintain Waste Inventory of all generated waste drums or containers indicating the location and approximate quantity of material in each container.

SD-07 Certificates

Submit the following certificates:

Asbestos Consultant's License from the State of Florida, Department of Business and Professional Regulation (DBPR)

Asbestos Contractor's License; G or other Contractor license approval from the State of Florida, Department of Business and Professional Regulation (DBPR).

Training Certifications; G, and experience of Contractor's "Competent Person", Supervisor, and workers.

Proficiency Analytical Test Certification

SD-08 Manufacturer's Instructions

Submit Material Safety Data Sheets in accordance with the paragraph entitled, "Licenses Permits, and Notices," of this section.

Submit Implementation Plan; G as identified in paragraph entitled, "Implementation Plan," prior to initial site set-ups or start of work.

SD-11 Closeout Submittals

Within 10 days after the completion of work, submit to the Contracts Administrator a written summary and copies of the following items:

Notification of Demolition/Renovation.

Waste Disposal Permit and all Disposal Shipping Manifests and Tickets.

Daily site inspection logs, negative pressure logs and other OSHA compliance inspection records.

Air Monitoring Reports conducted during the abatement.

Calibration Records; G for sampling equipment taken before and after each air sample.

Entry logs and Waste Stream Inventory maintained during the abatement task.

1.6 LICENSES PERMITS, AND NOTICES

Ensure that the FLAC possesses a current license and comply with all Federal, State and Local Regulations. Only those consultants who are certified and licensed by DBPR are permitted to perform Asbestos Surveys or abatement specifications and plans as per Florida Statute 469.

Contractor's possession of a current Asbestos Contractor's License is mandatory, as well as securing all necessary licenses and permits associated with asbestos removal, transportation, and disposal as may be required by Federal, State, and local regulations. Only those Contractors who are certified and licensed by the State of Florida will be permitted to perform asbestos abatement activities at Kennedy Space Center.

A Waste Disposal Permit and all Disposal Shipping Manifests and Tickets are to be obtained.

Submit the following certificates:

Certification of participation in a Proficiency Analytical Test (PAT) program such as or equivalent to the American Industrial Hygiene Association PAT or Asbestos Analytical Registry (AAR) accreditation certificate and Interlab QA/QC Program participation for the independent air monitoring agency selected by the Contractor before starting work.

Training Certifications and accreditation certificates for the independent air monitoring agency's on-site personnel and a copy of independent air monitoring agency's Quality Control Program.

Certification documents by the Contractor verifying that employees have been provided current respirator fit test, training, and medical examinations in compliance with 29 CFR 1926.

Material safety data sheets as required for materials to be used on the specified project.

1.6.1 Notification

When applicable, submit Florida Department of Environmental Protection (DEP) "Notice of Demolition or Asbestos Renovation" (DEP Form 62-257.900(1)) to DEP District Office. A copy of the notification is to be provided to the Government as part of the Implementation Plan.

1.7 IMPLEMENTATION PLAN

Prepare and submit a detailed, written Implementation Plan created, signed and sealed by a FLAC to the Government for approval, prior to the start of work, that includes the following:

Coordination drawings including site specific drawings of proposed work areas, clean room/change areas, mini-enclosures, shower, equipment room, waste loading/staging areas, locations of High Efficiency Particulate Air (HEPA) filtered negative pressure devices and exhaust points, work areas, emergency egress, and areas to be modified.

Detailed drawings for asbestos abatement systems consisting of fabrication and assembly drawings for all parts of the work in sufficient detail to enable the Government to check conformity with the requirements of the contract documents.

A copy of the applicable DEP Notification of Demolition/Renovation (DEP Form 62-257.900(1)).

Plan of Action, including proposed procedures to be used in complying with the requirements of this specification, 29 CFR 1926, and other applicable regulatory requirements, sequence of asbestos abatement work, the interfaces of trades involved in the performance of work, posting of licenses, permits, etc., methods to be used to assure the safety of building occupants and visitors to the site, disposal plan including location of approved disposal site, a detailed description of the methods employed to control pollution, and a detailed work schedule. Expand upon the method for removal of ACM, the use of portable HEPA ventilation systems, closing out of the buildings HVAC system, method of removal to prohibit visible emissions in the work area, and packaging of removed debris.

Details of the decontamination areas and procedures, locations of staging areas, posting of warning signs, and details of negative air system to be used in the work area.

Sketch(s) or drawing(s) of complete contract area(s) showing the shower room, clean room, drum staging area, decontamination and containment areas, the negative air system, and exits. Indicate designation of the "Competent

Person" (CP), and Site Supervisor.

Provide a written Air Monitoring Plan to be prepared under the direction of and signed/stamped by a Certified Industrial Hygienist (C.I.H.) or FLAC specifying the air monitoring criteria and an action plan for implementation by the Competent Person. Identify in the plan the Competent Person to be on site at all times (unless otherwise authorized by the Contracts Administrator) during asbestos abatement operations. The FLAC or his/her representative/competent person is responsible for ensuring applicable regulatory compliance during all phases of the asbestos abatement activities. The competent person has the authority to stop work for unsafe conditions and for not adhering to applicable regulations. Provide a qualified back-up person in the event that the Competent Person is absent from job site.

Provide certification that the Contractor, his staff, and abatement workers (including Supervisors) have attended and successfully completed (an) asbestos abatement course(s) including refresher courses as set forth in FL-STAT 469 and in accordance with 29 CFR 1926 and 40 CFR 763.

Provide a Respiratory Protection Program in accordance with 29 CFR 1910 including training in the care, use, and maintenance of respirators and fit test certification.

Provide a written description of respiratory equipment (name, type, model number) and protective clothing provided to the abatement workers.

Provide documentation that all personnel assigned to the abatement project have been examined annually by a physician. Submit the physician's written opinion containing the results of the employee's medical examination in compliance with 29 CFR 1926. Establish, maintain, and make readily available for review all Work site entry logs.

Provide Procedures for enforcement of Personal Hygiene Practices.

Prepare and submit a Contingency Plan for emergencies including fire, accident, power failure, heating or cooling, negative air system failure, respirator supplied air system failure, or any other event that may require modification of the work area isolation procedures. Include in the plan specific procedures for decontamination or work area isolation, safe exiting, and the need for medical attention in the event of an emergency.

Submit any additional procedures (fall protection, confined space, etc.) and policies that are in effect to ensure worker safety and environmental, KNPR 8500.1 and KNPR 8715.3) requirements are met.

Submit the Implementation Plan to the Government for review and approval. Commencement of work will not be permitted until the Implementation Plan is given final approval.

1.8 AIR MONITORING REPORTS

Obtain the services of an independent Air Monitoring Agency accredited by the American Industrial Hygiene Association (AIHA), for analysis of airborne asbestos concentration levels. Provide a copy of the monitoring agency's Quality Control Program to Contracts Administrator prior to commencement of the abatement activities. Ensure the individual performing the on-site air monitoring meets the requirements as set forth in FL-STAT 469 and 40 CFR 763, and performs sample collections in accordance

with the approved Air Monitoring Plan.

Perform all Air Monitoring under the direction of the FLAC using an independent Air Monitoring Contractor, in compliance with Florida Statute 469 requirements.

Calibrate pumps before and after each air sample and submit calibration records to the Government.

Submit daily Air Monitoring Reports. Include in the Air Monitoring Report the following information for each sample:

Sample identification, Sample location,
 Employee Name, Social Security Number,
 Description of task being monitored,
 Exposure level results in (f/cc),
 Monitoring instrument identification number,
 Pre-calibration, post calibration, and average flow rate of each sample,
 Sample date, start and stop times,
 Type of protective devices worn (if any),
 Project identification number, Facility number and name,
 Sampling and Analytical Methods used,
 Contact name and company, and name of individual performing the sampling.

1.8.1 Air Sample Analytical Method

Airborne fiber sampling and analytical procedures are to be analyzed by Phase Contrast Microscopy (PCM) in accordance with 29 CFR 1926 and NIOSH 94-113 7400 method.

1.8.2 Air Sampling Rate, Volumes and Frequency

Conduct daily monitoring utilizing sample rates, volumes and frequency in accordance with 29 CFR 1926 and retain for final submittal at closeout. The minimum number of samples or sample volumes may not be less than those specified below:

<u>Type of Sample</u>	<u>Volume</u>	<u>Minimum No. Samples</u>	<u>Location</u>
Prior to set-up (within 24 hrs)	1200L	2	Regulated Area
Personal, During work	400L	2	Personal B.Z.
Area samples, Adjacent to work area.	1200L	2	Regulated Area
Area samples at Negative	1200L	1	In area of outlets

<u>Type of Sample</u>	<u>Volume</u>	<u>Minimum No. Samples</u>	<u>Location</u>
Air Unit Exhaust.			

NOTE: The KSC IH will perform air sampling outside the regulated work area.

1.9 WORKER PROTECTION

Perform Initial Exposure Assessments and Employee Exposure Monitoring in accordance with 29 CFR 1926, part 1926.1101, with input and approval of the FLAC.

Select and provide respiratory protection to employees and ensure they are utilized in accordance with 29 CFR 1926.

Submit the Work schedule indicating the work days, hours, and the number of workers per shift. Include a bar chart to identify the individual milestones through to the completion of the project (i.e., number of days to complete work site preparation, number of days to complete ACM removal, number of days to complete final cleaning and lockdown, etc.).

Submit the OSHA compliance inspection records as part of the closeout documents.

PART 2 PRODUCTS

Not Used

PART 3 EXECUTION

3.1 TEMPORARY UTILITIES AND SERVICES

The Government will make available at the work site, water at hose bibs and 120 Volt AC at receptacles for the Contractor's use. Provide water proof safety lighting where necessary for safe, adequate illumination.

Ensure all electrical equipment to be used inside the work areas is powered from an Underwriters Laboratory (UL) approved Ground Fault Circuit Interrupter (GFCI). Do not exceed the manufacturers limits per GFCI. Make all necessary connections and restore the site connections to their original condition or better, prior to project completion.

Ensure all energized or pressurized systems inside the work area have been locked out, tagged out or otherwise rendered safe.

Provide temporary water from the existing building water source to control the generation of airborne dust, to allow for area, personnel, and equipment decontamination, and to supply decontamination unit needs. Also provide a backflow preventer at the source.

Provide temporary sanitary drainage piping to the decontamination unit sump and to the shower unit at a minimum slope of 2.0 percent, and temporary drainage piping to waste water pump and existing drain in accordance with local standards and as approved by the Contracts Administrator. Collect used shower water and filter with approved water filtration equipment to remove asbestos contamination. Discharge only clean water to the sanitary system.

3.2 WORK AREA PREPARATION

The Government will re-arrange equipment and storage areas to the extent of providing a direct and unobstructed path to the work area(s). During ACM removal, confine equipment and employees to the designated work area(s).

Unless otherwise directed by the Contracts Administrator, the Contractor is to establish and maintain a 25-foot access control barrier zone(s) around the designated work area(s). Interference with the functional operation of the building occupants outside these areas is not permitted.

Ensure all building supply and return air ducts from the mechanical system are isolated to eliminate air flow into or out of containment area(s).

3.2.1 Pre-Cleaning

Shut down HVAC systems and seal all critical barriers prior to initiating pre-cleaning actions. Seal, with 6 mil minimum thickness plastic sheeting, all openings, including but not limited to, windows, corridors, doorways, elevator openings, skylights, ducts, grilles, diffusers, and any other penetrations between the contaminated work areas and uncontaminated areas.

Pre-clean all movable objects identified as contaminated by the Contracts Administrator or his/her representative within the work area using a HEPA filtered vacuum and wet cleaning methods as appropriate. Remove these objects after cleaning and store in a protected area.

Pre-clean all surfaces in the work area using HEPA filtered vacuums and/or wet cleaning methods as appropriate. Methods that would raise dust, such as dry sweeping or vacuuming with equipment not equipped with HEPA filters, are PROHIBITED. Pay detailed attention to machinery or areas behind grilles and gratings.

Do not remove or otherwise disturb asbestos containing building materials during the pre-cleaning phase.

3.2.2 Work Area(s)

Inform all other Contractors and personnel on the site of the abatement work of the nature of the Contractor's work with ACM and/or PACM, of the existence of and requirements pertaining to regulated areas, and the measures taken to ensure that employees of such other Contractor employers are not exposed to asbestos in accordance with 29 CFR 1926.

Use industry controls and work practice methods in accordance with 29 CFR 1926. Ensure daily site inspection logs are posted at the jobsite by the on-site competent person.

Use flame resistant, 6 mil polyethylene sheeting when constructing Negative Pressure Enclosures (NPE) or decontamination areas.

3.3 WASTE LOAD-OUT UNIT

Establish a waste load-out unit to provide for interim secure storage. Include an equipment room for storage of asbestos-contaminated items (drums, tools, equipment). Decontaminate all equipment and waste containers prior to being taken out of the work area(s).

All asbestos-containing waste material is to be sealed in leak-tight

disposal containers or bags. Thoroughly wet all waste within the disposal containers. Maintain proper labeling protocols for all running and final inventory of filled disposable containers.

3.4 SIGNS AND MARKINGS

Post signs prior to commencing asbestos work as required in 29 CFR 1926. Post signs at the perimeter of the asbestos work areas, along the route of the temporary waste material holding (Drum Staging) area, and at all entrances to asbestos work areas. Ensure signs are conspicuous and legible.

Post telephone numbers and locations of emergency services including, but not limited to, fire, ambulance, doctor, and hospital, at the regulated area.

Post one copy of all permits at the work site perimeter in a accessible location outside the regulated area.

Post one copy of the Abatement Contractors current license at the work site perimeter in a accessible location outside the regulated area.

Post hazard communication notification signs in accordance with KNPR 1840.19 requirements.

3.5 NEGATIVE AIR SYSTEM

Construct Negative Pressure Enclosures (NPE's) as required by 29 CFR 1926.

Duct each of the negative air units through the containment barrier walls to the outside of the work area(s). When the building is occupied, ensure that the ducts exhaust into the outside air; otherwise, they may exhaust into an area of the building beyond the critical barriers. Never exhaust the units into the work area(s).

Provide each unit with temporary back-up electrical power (120 Volt AC) in the event of power failures or outages.

3.5.1 Testing

Design the negative air system to provide a minimum of four (4) air changes per hour and test before any work is begun. After the work area has been prepared, the decontamination unit set up, and the negative air units(s) installed, test the system. Prior to beginning abatement activities, an Asbestos Abatement Pre-Work Inspection checklist (KSC Form 28-1230NS) will be completed by the KSC IH to verify the adequacy of the containment system and work area. Once activated, ensure the negative air exhaust unit(s) remain in operation until final clearance air monitoring has been performed and the KSC IH has approved their shutdown/removal. Maintain daily negative pressure logs for review by the FLAC.

Install a differential pressure meter or manometer to continuously measure pressure differential between inside and outside the work area for all Class I activities which utilize a NPE. Maintain a minimum pressure differential of 0.02 inch of water column.

3.6 RESPIRATORY PROTECTION

Instruct and train each worker involved in asbestos abatement in proper respirator use and care. Fit all respirators by approved qualitative or

quantitative test. Use respiratory protection appropriate for the fiber level encountered in the Work Area and as specified herein, or as required for other situations encountered.

3.6.1 Air Quality for Supplied Air Respiratory Systems

The Contractor is to provide air used for breathing in Type "C" supplied air respiratory systems that meets or exceeds CGA G-7.1, standards for Grade D air.

3.7 REMOVAL OF ASBESTOS

Use industry controls and work practices for all operations in accordance with 29 CFR 1926 Methods of Compliance for Class I, II, III, or IV asbestos work. The FLAC or his/her representative are responsible for these practices.

Ensure all Class I, II, III and IV work is supervised by an on site Competent Person at all times that work is in progress.

Following removal of contaminated items and asbestos material, seal the edges of adjacent surfaces, which were exposed when asbestos was removed, with an asbestos bridging sealant/encapsulant.

3.8 DAILY HOUSEKEEPING

Maintain a clean work area in accordance with 29 CFR 1926. Perform the following housekeeping functions at the end of each shift or prior to leaving the work site unattended:

- a. Prepare contaminated waste for disposal by packaging the waste and removing it from the work area.
- b. HEPA vacuum the work area.
- c. Visually inspect polyethylene in the work area and other high traffic areas.

3.9 CLEANING PROCEDURES

Clean the work area at the end of each day's abatement activities. Designate a separate, secured area within the work area for storage of debris until it can be properly disposed. Secure the work area after termination of the work day to prevent entry. Regularly dispose and replace disposable supplies, such as mop heads, sponges, and rags. Clean all equipment by HEPA vacuuming and wet wiping.

Clean all work areas in which abatement operations have been completed, starting at the ceiling and working down to the floors, by HEPA vacuuming and wet wiping. Prior to removal of worksite access controls and re-occupancy inspection by the Government, and upon satisfactory final clearance air sampling, and removal of polyethylene sheeting, perform a final cleaning (wet wipe) of all surfaces within the work area.

3.10 INSPECTION

Do not commence removal of asbestos materials prior to satisfactory KSC IH, concurrence to proceed on the Asbestos Abatement Pre-Work Inspection (checklist KSC Form 28-1230NS).

3.10.1 Initial Inspection

The Contractor and the KSC IH will conduct a walk-through of the work area prior to beginning the abatement work to review existing conditions and ensure safe and practical conditions for the work to be implemented. Any damage to structures, surfaces, and equipment, which could be misconstrued as damage resulting from work, is to be documented by the Contractor and immediately submitted to the Contracts Administrator.

Perform background sampling for work areas in accordance with 29 CFR 1926 prior to beginning the abatement work.

3.10.2 Daily Inspection

Maintain a work site entry log of all personnel who enter the regulated work area. Through continuous surveillance and inspections of the worksite, ensure the integrity of containment, proper function of the negative pressure system, and posting of signs and labels. Also ensure, through frequent inspections during each work shift, that negative pressure is maintained, appropriate work practices are followed, appropriate protective clothing and equipment are used, and worker decontamination procedures are being followed.

Ensure that critical barriers and negative pressure enclosures remain effectively sealed and taped. Take immediate action to remedy defects immediately upon discovery. Details of the inspections are to be included in the Contractor's daily inspection log and posted in an accessible location outside the regulated area.

Provide updated copies of the Air Monitoring Reports, Daily Site Inspection Logs and Waste Stream Inventory to the Contracts Administrator at the end of each week of the abatement work.

NASA/Kennedy Space Center reserves the right to conduct periodic inspections and air monitoring in the work area(s). If the work area is unsafe as determined by the Contracts Administrator for KSC IH, the Contracts Administrator, will require the Contractor to stop work until the unsafe conditions are corrected.

3.10.3 Final Inspection

The thoroughness of asbestos removal is to be evaluated by visually inspecting the affected surfaces for residual asbestos material and accumulated dust followed by air sampling. Evidence of residual asbestos or asbestos debris on any adjacent surfaces upon completion of the work is not acceptable.

Upon completion of the work, conduct a thorough visual inspection of the work area by the Abatement Contractor and by the KSC IH to ensure no residual asbestos material, dust or debris remains. Document final inspections on the Asbestos Abatement Clearance Inspection Checklist (KSC Form 28-1231NS), which will be completed by KSC IH.

If applicable, final aggressive air sampling is to be performed by the KSC IH for each NPE work area after completion of a satisfactory visual inspection. The clearance criteria is 0.01 fibers per cubic centimeter (f/cc) of air as determined by phase contrast microscopy (PCM). Satisfactory fiber counts from all final samples are to be less than 0.01

f/cc. If any of the final air samples contain greater than 0.01 f/cc, repeat the final cleaning operation and re-test the area until satisfactory clearance levels are obtained.

Collect five (5) PCM final air samples for the first 5,000 square feet of containment plus one (1) additional PCM final air sample for each additional 5,000 square feet or one (1) air sample per room, whichever is greater. The number of final air samples may be reduced for small enclosures of less than approximately 2500 square feet. In no case may fewer than two (2) final samples be collected for any enclosure.

Ensure clearance air sample volumes meet the minimum volumes as indicated for analysis by NIOSH 7400 method.

3.11 ASBESTOS WASTE AND CONTAMINATED MATERIALS

3.11.1 Removal of Asbestos Waste Materials

For purposes of this paragraph, asbestos waste materials are defined as those materials which contain or have been contaminated by asbestos and are not planned to be encapsulated and remain at the job site. They are primarily removed asbestos, disposable clothing and safety equipment, polyethylene sheeting, contaminated amended water, vacuum cleaner contents, and filtration media.

Contain all asbestos waste material in two (2) 6 mil polyethylene disposal bags, or two (2) 6 mil disposal bags and a sealed leak-tight container such as, but not limited to, a steel or fiberboard drum. Pack the asbestos waste material while still wet. Clean the external surface of the waste containers by HEPA vacuuming and wet wiping before moving from the work area. Protect the interior of truck or dumpster with two layers of polyethylene sheeting.

3.11.1.1 Waste Inventory

Label and clearly mark all disposal containers, dumpsters, and trucks, in accordance with 40 CFR 61-SUBPART M, 29 CFR 1910 of OSHA's Hazard Communications Standard, and 49 CFR 171 and 49 CFR 172, Hazardous Substances.

Provide conspicuous, legible labels, affixed to plastic bags and drums indicating the name of the waste generator and the location (facility name and number) where the waste was generated.

For non-friable asbestos that will be disposed at the KSC/Schwartz Road Landfill, provide a completed landfill disposal verification form (KSC Form 28-1064NS) send to Contracts Administration. NOTE: Regulated ACM is not permitted for disposal at KSC/Schwartz Road Landfill.

Provide a Waste Shipment Record (WSR) to the Contracting Officer in accordance with the instructions in 40 CFR 61-SUBPART M.

3.11.2 Work Area Disposal

After final inspection has been completed and the work area is released for occupancy, shut off and remove the Negative Air System units. Unseal all entrances and exits. Dispose of all plastic sheeting, tape, and any other trash and debris, except for critical barriers, in sealable plastic bags, or in drums and moved to the staging area. After final wet wipe of the

work area and satisfactory clearance air sampling, dismantle critical barriers and the decontamination unit.

3.11.3 Decontamination Area And Support Area Disposal

Dismantle the decontamination area after the work area is released by the KSC IH for re-occupancy. Vacuum all surfaces of the decontamination unit before it is disassembled.

3.12 WASTE TRANSPORTATION AND DISPOSAL

Transport and dispose of asbestos waste in full compliance with 40 CFR 61-SUBPART M, SUBPART A, 49 CFR 171 and 49 CFR 172.

3.13 ASBESTOS ABATEMENT NOTICE AND CHECKLIST

An Asbestos Abatement Pre-Work Inspection form (KSC Form 28-1230NS) and an Asbestos Abatement Clearance Checklist (KSC Form 28-1231NS) will be provided by the KSC IH. Send copies to the Contracting Officer upon satisfactory completion of the work. Notify KSC IH and the Contracting Officer at least three days prior to the planned commencement of work. Coordinate and schedule all Pre-Work and Clearance Site inspections with KSC IH. The completed forms are to be used to establish approval of the containment, work practices and final acceptance/re-occupancy of the work area(s).

3.14 FINAL ACCEPTANCE

The work will not be considered complete until the asbestos materials identified herein have been abated, the areas cleaned, satisfactory clearance air monitoring completed, all asbestos contaminated waste has been properly disposed of, and all project close out documents have been received and approved by the Contracting Officer.

-- End of Section --

SECTION TABLE OF CONTENTS

DIVISION 02 - EXISTING CONDITIONS

SECTION 02 82 33.13 20

REMOVAL/CONTROL AND DISPOSAL OF PAINT WITH LEAD

PART 1 GENERAL

1.1 REFERENCES

1.2 DEFINITIONS

- 1.2.1 Abatement
- 1.2.2 Action Level
- 1.2.3 Area Sampling
- 1.2.4 Child Occupied Facility
- 1.2.5 Competent Person (CP)
- 1.2.6 Contaminated Room
- 1.2.7 Decontamination Shower Facility
- 1.2.8 Deleading
- 1.2.9 Eight-Hour Time Weighted Average (TWA)
- 1.2.10 High Efficiency Particulate Air (HEPA) Filter Equipment
- 1.2.11 Lead
- 1.2.12 Lead-Based Paint (LBP)
- 1.2.13 Lead-Based Paint Activities
- 1.2.14 Lead-Based Paint Hazard (LBP Hazard)
- 1.2.15 Paint with Lead (PWL)
- 1.2.16 Lead Control Area
- 1.2.17 Lead Permissible Exposure Limit (PEL)
- 1.2.18 Personal Sampling
- 1.2.19 Physical Boundary
- 1.2.20 Target Housing

1.3 DESCRIPTION

- 1.3.1 Description of Work
- 1.3.2 Coordination with Other Work

1.4 SUBMITTALS

1.5 QUALITY ASSURANCE

1.5.1 Qualifications

- 1.5.1.1 Qualifications of CP
- 1.5.1.2 Training Certification
- 1.5.1.3 Testing Laboratory
- 1.5.1.4 Third Party Consultant Qualifications

1.5.2 Requirements

- 1.5.2.1 Competent Person (CP) Responsibilities
- 1.5.2.2 Lead-Based Paint/Paint with Lead Removal/Control Plan (LBP/PWL R/CP)
- 1.5.2.3 Occupational and Environmental Assessment Data Report
- 1.5.2.4 Medical Examinations
- 1.5.2.5 Training
- 1.5.2.6 Respiratory Protection Program
- 1.5.2.7 Hazard Communication Program
- 1.5.2.8 Waste Management
- 1.5.2.9 Environmental, Safety and Health Compliance

1.5.3 Pre-Construction Conference

- 1.6 EQUIPMENT
 - 1.6.1 Respirators
 - 1.6.2 Special Protective Clothing
 - 1.6.3 Rental Equipment Notification
 - 1.6.4 Vacuum Filters
 - 1.6.5 Equipment for Government Personnel
- 1.7 PROJECT/SITE CONDITIONS
 - 1.7.1 Protection of Existing Work to Remain

PART 2 PRODUCTS

PART 3 EXECUTION

- 3.1 PREPARATION
 - 3.1.1 Protection
 - 3.1.1.1 Notification
 - 3.1.1.2 Boundary Requirements
 - 3.1.1.3 Heating, Ventilating and Air Conditioning (HVAC) Systems
 - 3.1.1.4 Decontamination Facility
 - 3.1.1.5 Eye Wash Station
 - 3.1.1.6 Mechanical Ventilation System
 - 3.1.1.7 Personnel Protection
- 3.2 ERECTION
 - 3.2.1 Lead Control Area Requirements
- 3.3 APPLICATION
 - 3.3.1 Work Procedures
 - 3.3.2 Lead-Based Paint Removal/Control/Deleading
 - 3.3.2.1 Outdoor Paint Removal
 - 3.3.3 Personnel Exiting Procedures
- 3.4 FIELD QUALITY CONTROL
 - 3.4.1 Tests
 - 3.4.1.1 Air and Wipe Sampling
 - 3.4.1.2 Air Sampling During Paint Removal Work
 - 3.4.1.3 Sampling After Paint Removal/Control
 - 3.4.1.4 Testing of Removed Paint and Used Abrasive
- 3.5 CLEANING AND DISPOSAL
 - 3.5.1 Cleanup
 - 3.5.1.1 Clearance Certification
 - 3.5.2 Disposal
 - 3.5.2.1 Disposal Documentation

-- End of Section Table of Contents --

SECTION 02 82 33.13 20

REMOVAL/CONTROL AND DISPOSAL OF PAINT WITH LEAD

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN NATIONAL STANDARDS INSTITUTE (ANSI)

ANSI Z88.2 (1992) Respiratory Protection

U.S. DEPARTMENT OF HOUSING AND URBAN DEVELOPMENT (HUD)

HUD 6780 (1995; Errata Aug 1996; Rev Ch. 7 - 1997)
Guidelines for the Evaluation and Control
of Lead-Based Paint Hazards in Housing

JOHN F. KENNEDY SPACE CENTER (KSC)

KNPR 8500.1 (2007) KSC Environmental Requirements

U.S. NATIONAL ARCHIVES AND RECORDS ADMINISTRATION (NARA)

29 CFR 1926.103 Respiratory Protection

29 CFR 1926.21 Safety Training and Education

29 CFR 1926.33 Access to Employee Exposure and Medical
Records

29 CFR 1926.55 Gases, Vapors, Fumes, Dusts, and Mists

29 CFR 1926.59 Hazard Communication

29 CFR 1926.62 Lead

40 CFR 261 Identification and Listing of Hazardous
Waste

40 CFR 262 Standards Applicable to Generators of
Hazardous Waste

40 CFR 745 Lead-Based Paint Poisoning Prevention in
Certain Residential Structures

UNDERWRITERS LABORATORIES (UL)

UL 586 (2004) Standard for High-Efficiency
Particulate, Air Filter Units

1.2 DEFINITIONS

1.2.1 Abatement

As applied to target housing and child occupied facilities, "abatement" means any set of measures designed to permanently eliminate lead-based paint hazards in accordance with standards established by appropriate Federal agencies. Such term includes:

a. The removal of lead-based paint and lead-contaminated dust, the permanent containment or encapsulation of lead-based paint, the replacement of lead-painted surfaces or fixtures, and the removal or covering of lead contaminated soil; and

b. All preparation, cleanup, disposal, and post-abatement clearance testing activities associated with such measures.

1.2.2 Action Level

Employee exposure, without regard to use of respirators, to an airborne concentration of lead of 30 micrograms per cubic meter of air averaged over an 8 hour period in a work environment.

1.2.3 Area Sampling

Sampling of lead concentrations within the lead control area and inside the physical boundaries, which is representative of the airborne lead concentrations but is not collected in the breathing zone of personnel.

1.2.4 Child Occupied Facility

A building or portion of a building constructed prior to 1978 visited regularly by the same child, 6 years of age or under, on a least two different days within any week, provided each days visit last at least 3 hours and the combined weekly visit last at least 6 hours and the combined annual visit last at least 60 hours. Child occupied facilities may include, but are not limited to day-care centers, preschools and kindergarten classrooms.

1.2.5 Competent Person (CP)

As used in this section, refers to a person employed by the Contractor who is trained in the recognition and control of lead hazards in accordance with current federal, State, and local regulations. A Certified Industrial Hygienist (CIH) certified for comprehensive practice by the American Board of Industrial Hygiene or a Certified Safety Professional (CSP) certified by the Board of Certified Safety Professionals is the best choice.

1.2.6 Contaminated Room

Refers to a room for removal of contaminated personal protective equipment (PPE).

1.2.7 Decontamination Shower Facility

That facility that encompasses a clean clothing storage room, and a contaminated clothing storage and disposal rooms, with a shower facility in between.

1.2.8 Deleading

Activities conducted by a person who offers to eliminate lead-based paint or lead-based paint hazards or to plan such activities in commercial buildings, bridges or other structures.

1.2.9 Eight-Hour Time Weighted Average (TWA)

Airborne concentration of lead to which an employee is exposed, averaged over an 8 hour workday as indicated in 29 CFR 1926.62.

1.2.10 High Efficiency Particulate Air (HEPA) Filter Equipment

HEPA filtered vacuuming equipment with a UL 586 filter system capable of collecting and retaining lead-contaminated paint dust. A high efficiency particulate filter means 99.97 percent efficient against 0.3 micron or larger size particles.

1.2.11 Lead

Metallic lead, inorganic lead compounds, and organic lead soaps.

1.2.12 Lead-Based Paint (LBP)

Paint or other surface coating that contains lead in excess of 1.0 milligrams per centimeter squared or 0.5 percent by weight.

1.2.13 Lead-Based Paint Activities

In the case of target housing or child occupied facilities, lead-based paint activities include; a lead-based paint inspection, a risk assessment, or abatement of lead-based paint hazards.

1.2.14 Lead-Based Paint Hazard (LBP Hazard)

Any condition that causes exposure to lead from lead-contaminated dust, lead-contaminated soil, lead-based paint that is deteriorated or present in accessible surfaces, friction surfaces, or impact surfaces that would result in adverse human health effects.

1.2.15 Paint with Lead (PWL)

Any paint that contains lead as determined by the testing laboratory using a valid test method. The requirements of this section does not apply if no detectable levels of lead are found using a quantitative method for analyzing paint using laboratory instruments with specified limits of detection (usually 0.01%). An X-Ray Fluorescence (XRF) instrument is not considered a valid test method.

1.2.16 Lead Control Area

A system of control methods to prevent the spread of lead dust, paint chips or debris to adjacent areas that may include temporary containment, floor or ground cover protection, physical boundaries, and warning signs to prevent unauthorized entry of personnel. HEPA filtered local exhaust equipment may be used as engineering controls to further reduce personnel exposures or building/outdoor environmental contamination.

1.2.17 Lead Permissible Exposure Limit (PEL)

Fifty micrograms per cubic meter of air as an 8 hour time weighted average as determined by 29 CFR 1926.62. If an employee is exposed for more than eight hours in a workday, the PEL shall be determined by the following formula:

$$\text{PEL (micrograms/cubic meter of air)} = 400/\text{No. hrs worked per day}$$

1.2.18 Personal Sampling

Sampling of airborne lead concentrations within the breathing zone of an employee to determine the 8 hour time weighted average concentration in accordance with 29 CFR 1926.62. Samples shall be representative of the employees' work tasks. Breathing zone shall be considered an area within a hemisphere, forward of the shoulders, with a radius of 6 to 9 inches and centered at the nose or mouth of an employee.

1.2.19 Physical Boundary

Area physically roped or partitioned off around an enclosed lead control area to limit unauthorized entry of personnel. As used in this section, "inside boundary" shall mean the same as "outside lead control area but inside the physical boundary."

1.2.20 Target Housing

Housing constructed prior to 1978. It does not include housing for the elderly, or persons with disabilities unless any one or more children age 6 years and younger resides or is expected to reside in such housing.

1.3 DESCRIPTION

1.3.1 Description of Work

Remove/control lead-based/paint with lead as indicated on the drawings. Contractor shall remove paint in accordance with this Section and shall recycle, handle and/or dispose of materials with lead paint in accordance with Federal and State regulations, this Section, and Section 01 57 20.00 10 ENVIRONMENTAL PROTECTION. If a painted surface has not been tested for lead paint, the Contractor shall assume lead is present. Sample and analyze the paint to determine if lead is present.

1.3.2 Coordination with Other Work

The contractor shall coordinate with work being performed in adjacent areas. Coordination procedures shall be explained in the Removal/Control Plan and shall describe how the Contractor will prevent lead exposure to other contractors and/or Government personnel performing work unrelated to lead activities.

1.4 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for Contractor Quality Control approval. The following shall be submitted in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-03 Product Data

Vacuum Filters; G

Respirators; G

SD-06 Test Reports

sampling results; G

Occupational and Environmental Assessment Data Report; G

SD-07 Certificates

Qualifications of CP; G

Testing Laboratory qualifications; G

Occupant Notification; G

Training Certification of workers and supervisors; G

Third Party Consultant Qualifications; G

Lead-based paint/paint with lead removal/control plan including CP approval (signature, date, and certification number); G

Respiratory Protection Program; G

Hazard Communication Program; G

Clearance Certification; G

SD-11 Closeout Submittals

KSC Waste Management Contractor is responsible for disposal of all Hazardous, Controlled, and Universal wastes.

KSC Waste Management Internal Manifest; G

Certification of Medical Examinations; G

1.5 QUALITY ASSURANCE

1.5.1 Qualifications

1.5.1.1 Qualifications of CP

Submit name, address, and telephone number of the CP selected to perform responsibilities specified in paragraph entitled "Competent Person (CP) Responsibilities." Provide previous experience of the CP. Submit proper documentation that the CP is trained, licensed, and certified in accordance with Federal, State, and local laws.

1.5.1.2 Training Certification

Submit a certificate for each employee and supervisor, signed and dated by the training provider meeting 40 CFR 745 (Subpart L) requirements, stating that the employee or supervisor has received the required lead training and

is certified to perform or supervise deleading or lead removal. Submit proof the work will be performed by a certified firm.

1.5.1.3 Testing Laboratory

Submit the name, address, and telephone number of the testing laboratory selected to perform the air and wipe sampling, testing, and reporting of airborne concentrations of lead. Use a laboratory accredited under the EPA National Lead Laboratory Accreditation Program (NLLAP) by either the American Association for Laboratory Accreditation (A2LA) or the American Industrial Hygiene Association (AIHA) and that is successfully participating in the Environmental Lead Proficiency Analytical Testing (ELPAT) program to perform sample analysis. Laboratories selected to perform blood lead analysis shall be OSHA approved.

1.5.1.4 Third Party Consultant Qualifications

Submit the name, address, and telephone number of the third party consultant selected to perform the wipe sampling for determining concentrations of lead in dust or soil sampling. Submit proper documentation that the consultant is trained and certified as an inspector technician or inspector/risk assessor by the USEPA authorized State (or local) certification and accreditation program.

1.5.2 Requirements

1.5.2.1 Competent Person (CP) Responsibilities

- a. Verify training meets all federal, State, and local requirements.
- b. Review and approve lead-based paint/paint with lead removal/control plan for conformance to the applicable standards. Ensure work is performed in strict accordance with specifications at all times.
- c. Continuously inspect lead-based paint removal/control work for conformance with the approved plan.
- d. Perform air and wipe sampling.
- e. Control work to prevent hazardous exposure to human beings and to the environment at all times.
- f. Certify the conditions of the work as called for elsewhere in this specification.

1.5.2.2 Lead-Based Paint/Paint with Lead Removal/Control Plan (LBP/PWL R/CP)

Submit a detailed job-specific plan of the work procedures to be used in the removal/control of LBP/PWL. The plan shall include a sketch showing the location, size, and details of lead control areas, location and details of decontamination facilities, viewing ports, and mechanical ventilation system. Include a description of equipment and materials, controls and job responsibilities for each activity from which lead is emitted. Include in the plan, eating, drinking, smoking and sanitary procedures, interface of trades, sequencing of lead related work, collected waste water and paint debris disposal plan, air sampling plan, respirators, personal protective equipment, and a detailed description of the method of containment of the operation to ensure that lead is not released outside the lead control area. Include site preparation, cleanup and clearance procedures. Include

occupational and environmental sampling, training, sampling methodology, frequency, duration of sampling, and qualifications of sampling personnel in the air sampling portion of the plan. Include a description of arrangements made among contractors on multi-contractor worksites to inform affected employees and to clarify responsibilities to control exposures.

The Removal/Control Plan shall be developed by a certified planner/project designer.

In occupied buildings, the Removal/Control Plan shall also include an occupant protection program that describes the measures that will be taken during the work to protect the building occupants.

1.5.2.3 Occupational and Environmental Assessment Data Report

If initial monitoring is necessary, submit occupational and environmental sampling results to the Contracting Officer within three working days of collection, signed by the testing laboratory employee performing the analysis, the employee that performed the sampling, and the CP.

In order to reduce the full implementation of 29 CFR 1926.62, the Contractor shall provide documentation. Submit a report that supports the determination to reduce full implementation of the requirements of 29 CFR 1926.62 and supporting the Lead Removal/Control Plan.

- a. The initial monitoring shall represent each job classification, or if working conditions are similar to previous jobs by the same employer, provide previously collected exposure data that can be used to estimate worker exposures per 29 CFR 1926.62. The data shall represent the worker's regular daily exposure to lead for stated work.
- b. Submit worker exposure data gathered during the task based trigger operations of 29 CFR 1926.62 with a complete process description. This includes manual demolition, manual scraping, manual sanding, heat gun, power tool cleaning, rivet busting, cleanup of dry expendable abrasives, abrasive blast enclosure removal, abrasive blasting, welding, cutting and torch burning where lead containing coatings are present.
- c. The initial assessment shall determine the requirement for further monitoring and the need to fully implement the control and protective requirements including the lead compliance plan per 29 CFR 1926.62.

1.5.2.4 Medical Examinations

Initial medical surveillance as required by 29 CFR 1926.62 shall be made available to all employees exposed to lead at any time (1 day) above the action level. Full medical surveillance shall be made available to all employees on an annual basis who are or may be exposed to lead in excess of the action level for more than 30 days a year or as required by 29 CFR 1926.62. Adequate records shall show that employees meet the medical surveillance requirements of 29 CFR 1926.33, 29 CFR 1926.62, and 29 CFR 1926.103. Maintain complete and accurate medical records of employees for a period of at least 30 years or for the duration of employment plus 30 years, whichever is longer.

1.5.2.5 Training

Train each employee performing paint removal, disposal, and air sampling

operations prior to the time of initial job assignment and annually thereafter, in accordance with 29 CFR 1926.21, 29 CFR 1926.62, and State and local regulations where appropriate.

1.5.2.6 Respiratory Protection Program

a. Provide each employee required to wear a respirator a respirator fit test at the time of initial fitting and at least annually thereafter as required by 29 CFR 1926.62.

b. Establish and implement a respiratory protection program as required by ANSI Z88.2, 29 CFR 1926.103, 29 CFR 1926.62, and 29 CFR 1926.55.

1.5.2.7 Hazard Communication Program

Establish and implement a Hazard Communication Program as required by 29 CFR 1926.59.

1.5.2.8 Waste Management

The Waste Management Plan shall be in accordance with Section 01 57 20.00 10 ENVIRONMENTAL PROTECTION.

1.5.2.9 Environmental, Safety and Health Compliance

In addition to the detailed requirements of this specification, comply with laws, ordinances, rules, and regulations of Federal, State, local authorities, and KNPR 8500.1 regarding removing, handling, storing, transporting, and disposing of lead waste materials. Comply with the applicable requirements of the current issue of 29 CFR 1926.62. Submit matters regarding interpretation of standards to the Contracting Officer for resolution before starting work. Where specification requirements and the referenced documents vary, the most stringent requirement shall apply. The following Federal and State laws, ordinances, criteria, rules and regulations regarding removing, handling, storing, transporting, and disposing of lead-contaminated materials apply:

a. 40 CFR 745 (Subpart L)

b. 29 CFR 1926.62

Licensing and certification in the State of Florida is required.

1.5.3 Pre-Construction Conference

Along with the CP, meet with the Contracting Officer to discuss in detail the waste management plan and the lead-based paint/paint with lead removal/control plan, including work procedures and precautions for the removal plan.

1.6 EQUIPMENT

1.6.1 Respirators

Furnish appropriate respirators approved by the National Institute for Occupational Safety and Health (NIOSH), Department of Health and Human Services, for use in atmospheres containing lead dust. Respirators shall comply with the requirements of 29 CFR 1926.62.

1.6.2 Special Protective Clothing

Furnish personnel who will be exposed to lead-contaminated dust with proper disposable protective whole body clothing, head covering, gloves, and foot coverings as required by 29 CFR 1926.62. Furnish proper disposable plastic or rubber gloves to protect hands. Reduce the level of protection only after obtaining approval from the CP.

1.6.3 Rental Equipment Notification

If rental equipment is to be used during lead-based paint handling and disposal, notify the rental agency in writing concerning the intended use of the equipment. Furnish a copy of the written notification to the Contracting Officer.

1.6.4 Vacuum Filters

UL 586 labeled HEPA filters.

1.6.5 Equipment for Government Personnel

Furnish the Contracting Officer with two complete sets of personal protective equipment (PPE) daily, as required herein, for entry into and inspection of the paint removal work within the lead controlled area. Personal protective equipment shall include disposable whole body covering, including appropriate foot, head, and hand protection. PPE shall remain the property of the Contractor. The Government will provide respiratory protection for the Contracting Officer.

1.7 PROJECT/SITE CONDITIONS

1.7.1 Protection of Existing Work to Remain

Perform paint removal work without damage or contamination of adjacent areas. Where existing work is damaged or contaminated, restore work to its original condition or better.

PART 2 PRODUCTS

Section 01 35 26 GOVERNMENT SAFETY REQUIREMENTS.

PART 3 EXECUTION

3.1 PREPARATION

3.1.1 Protection

3.1.1.1 Notification

a. Notify the Contracting Officer 20 days prior to the start of any paint removal work.

b. Occupant Notification

Submit occupant written acknowledgment of the delivery of lead hazard information pamphlet (EPA 747-K-99-001 "Protect Your Family From Lead in Your Home") prior to commencing the renovation work for each affected unit per 40 CFR 745 Subpart E.

3.1.1.2 Boundary Requirements

- a. Provide physical boundaries around the lead control area by roping off the area designated in the work plan or providing curtains, portable partitions or other enclosures to ensure that lead will not escape outside the lead control area.
- b. Warning Signs - Provide warning signs at approaches to lead control areas. Locate signs at such a distance that personnel may read the sign and take the necessary precautions before entering the area. Signs shall comply with the requirements of 29 CFR 1926.62.

3.1.1.3 Heating, Ventilating and Air Conditioning (HVAC) Systems

Shut down, lock out, and isolate HVAC systems that supply, exhaust, or pass through the lead control areas. Seal intake and exhaust vents in the lead control area with 6 mil plastic sheet and tape. Seal seams in HVAC components that pass through the lead control area.

3.1.1.4 Decontamination Facility

Provide clean and contaminated change rooms in accordance with this specification and 29 CFR 1926.62.

3.1.1.5 Eye Wash Station

Where eyes may be exposed to injurious corrosive materials, suitable facilities for quick drenching or flushing of the eyes shall be provided within the work area.

3.1.1.6 Mechanical Ventilation System

- a. Use adequate ventilation to control personnel exposure to lead in accordance with 29 CFR 1926.62.
- b. To the extent feasible, use local exhaust ventilation connected to HEPA filters or other collection systems, approved by the CP. Local exhaust ventilation systems shall be evaluated and maintained in accordance with 29 CFR 1926.62.
- c. Vent local exhaust outside the building only and away from building ventilation intakes.
- d. Use locally exhausted, power actuated, paint removal tools.

3.1.1.7 Personnel Protection

Personnel shall wear and use protective clothing and equipment as specified herein. Eating, smoking, or drinking or application of cosmetics is not permitted in the lead control area. No one will be permitted in the lead control area unless they have been appropriately trained and provided with protective equipment.

3.2 ERECTION

3.2.1 Lead Control Area Requirements

Establish a lead control area by situating critical barriers and physical boundaries around the area or structure where LBP/PWL removal/control

operations will be performed.

3.3 APPLICATION

3.3.1 Work Procedures

Perform removal of lead-based paint in accordance with approved lead-based paint/paint with lead removal/control plan. Use procedures and equipment required to limit occupational and environmental exposure to lead when lead-based paint is removed in accordance with 29 CFR 1926.62. Dispose of removed paint chips and associated waste in compliance with Environmental Protection Agency (EPA), State, and local requirements.

3.3.2 Lead-Based Paint Removal/Control/Deleading

Manual or power sanding of interior and exterior surfaces is not permitted unless tools are equipped with HEPA attachments or wet methods. The dry sanding or grinding of surfaces that contain lead is prohibited. Provide methodology for LBP removal/control in work plan. Remove paint within the areas designated on the drawings in order to completely expose the substrate. Take whatever precautions necessary to minimize damage to the underlying substrate.

Provide methodology for LBP/PWL removal and abatement/control and processes to minimize contamination of work areas outside the control area with lead-contaminated dust or other lead-contaminated debris/waste and to ensure that unprotected personnel are not exposed to hazardous concentrations of lead. Describe this LBP/PWL removal/control process in the LBP/PWL R/CP.

3.3.2.1 Outdoor Paint Removal

Perform outdoor removal as indicated in federal, State, and local regulations and in the LBP/CPR/CP. The worksite preparation (barriers or containments) shall be job dependent and presented in the LBP/PWL R/CP.

3.3.3 Personnel Exiting Procedures

Whenever personnel exit the lead-controlled area, they shall perform the following procedures and shall not leave the work place wearing any clothing or equipment worn during the work day:

- a. Vacuum themselves off.
- b. Remove protective clothing in the contaminated change room, and place them in an approved impermeable disposal bag.
- c. Change to clean clothes prior to leaving the physical boundary designated around the lead control area.

3.4 FIELD QUALITY CONTROL

3.4.1 Tests

3.4.1.1 Air and Wipe Sampling

Air sample for lead in accordance with 29 CFR 1926.62 and as specified herein. Air and wipe sampling shall be directed or performed by the CP.

- a. The CP shall be on the job site directing the air and non-clearance wipe sampling and inspecting the lead-based paint removal/control work to ensure that the requirements of the contract have been satisfied during the entire lead-based paint removal operation.
- b. Collect personal air samples on employees who are expected to have the greatest risk of exposure as determined by the CP. In addition, collect air samples on at least 25 percent of the work crew or a minimum of two employees, whichever is greater, during each work shift.
- c. Submit results of air samples, within 72 hours after the air samples are taken.
- d. Before any work begins, a third party consultant shall collect and analyze baseline wipe samples in accordance with methods defined in federal, State, and local standards inside and outside of the physical boundary to assess the degree of dust contamination in the facility prior to lead-based paint removal/control.
- e. Collect surface wipe samples at a location no greater than 10 feet outside the lead control area at a frequency of once per day while lead removal work is conducted. Surface wipe results shall meet criteria in paragraph "Clearance Certification."

3.4.1.2 Air Sampling During Paint Removal Work

Conduct area air sampling daily, on each shift in which lead-based paint removal operations are performed, in areas immediately adjacent to the lead control area. Sufficient area monitoring shall be conducted to ensure unprotected personnel are not exposed at or above 30 micrograms per cubic meter of air. If 30 micrograms per cubic meter of air is reached or exceeded, stop work, correct the condition(s) causing the increased levels. Notify the Contracting Officer immediately. Determine if condition(s) require any further change in work methods. Removal work shall resume only after the CP and the Contracting Officer give approval. For outdoor operations, at least one sample on each shift shall be taken on the downwind side of the lead control area.

3.4.1.3 Sampling After Paint Removal/Control

After the visual inspection, collect wipe samples according to the HUD protocol contained in HUD 6780 to determine the lead content of settled dust and dirt in micrograms per square meter foot of surface area.

3.4.1.4 Testing of Removed Paint and Used Abrasive

Test removed paint and used abrasive in accordance with 40 CFR 261 for hazardous waste.

3.5 CLEANING AND DISPOSAL

3.5.1 Cleanup

Maintain surfaces of the lead control area free of accumulations of paint chips and dust. Restrict the spread of dust and debris; keep waste from being distributed over the work area. Do not dry sweep or use compressed air to clean up the area. At the end of each shift and when the paint removal operation has been completed, clean the area of visible lead paint contamination by vacuuming with a HEPA filtered vacuum cleaner, wet mopping

the area and wet wiping the area as indicated by the CP. Reclean areas showing dust or residual paint chips or debris. After visible dust, chips and debris is removed, wet wipe and HEPA vacuum all surfaces in the work area. If adjacent areas become contaminated at any time during the work, clean, visually inspect, and then wipe sample all contaminated areas. The CP shall then certify in writing that the area has been cleaned of lead contamination before restarting work.

3.5.1.1 Clearance Certification

The CP shall certify in writing that air samples collected outside the lead control area during paint removal operations are less than 30 micrograms per cubic meter of air; the respiratory protection used for the employees was adequate; the work procedures were performed in accordance with 29 CFR 1926.62 and 40 CFR 745; and that there were no visible accumulations of material and dust containing lead left in the work site. Do not remove the lead control area or roped off boundary and warning signs prior to the Contracting Officer's acknowledgement of receipt of the CP certification.

For lead-based paint hazard abatement work, surface wipe shall be conducted and clearance determinations made according to the work practice standards presented in 40 CFR 745.227.

3.5.2 Disposal

a. Collect lead-contaminated waste, scrap, debris, bags, containers, equipment, and lead-contaminated clothing that may produce airborne concentrations of lead particles. Label the containers in accordance with 29 CFR 1926.62 and 40 CFR 262. Dispose of lead-contaminated waste material in accordance with Section 01 57 20.00 10 ENVIRONMENTAL PROTECTION paragraph "Materials Management and Waste Disposal," and contract clause "Hazardous Waste."

b. The result of each waste characterization (TCLP for RCRA materials) will dictate disposal requirements.

3.5.2.1 Disposal Documentation

Contractor shall, in accordance with the contract clause "Hazardous Waste," provide all KSC Waste Management internal manifest copies upon completion of the project to the Contracting Officer.

-- End of Section --

SECTION TABLE OF CONTENTS

DIVISION 02 - EXISTING CONDITIONS

SECTION 02 84 33

REMOVAL AND DISPOSAL OF POLYCHLORINATED BIPHENYLS (PCBs)

PART 1 GENERAL

- 1.1 REFERENCES
- 1.2 REQUIREMENTS
- 1.3 DEFINITIONS
 - 1.3.1 Leak
 - 1.3.2 PCBs
 - 1.3.3 Spill
- 1.4 QUALITY ASSURANCE
 - 1.4.1 Training
 - 1.4.2 Certified Industrial Hygienist (CIH)
 - 1.4.3 Regulation Documents
 - 1.4.4 Surveillance Personnel
- 1.5 SUBMITTALS
- 1.6 EQUIPMENT
 - 1.6.1 Special Clothing
 - 1.6.2 Special Clothing for Government Personnel
 - 1.6.3 PCB Spill Kit
- 1.7 QUALITY ASSURANCE
 - 1.7.1 Training Certification
 - 1.7.2 Qualifications of CIH
 - 1.7.3 PCB Removal Work Plan
 - 1.7.4 PCB Disposal Plan
 - 1.7.5 Notification

PART 2 PRODUCTS

PART 3 EXECUTION

- 3.1 PROTECTION
 - 3.1.1 Decontamination Room, Clean Room and Shower Facilities
 - 3.1.2 PCB Control Area
 - 3.1.3 Personnel Protection
 - 3.1.4 Footwear
 - 3.1.5 Permissible Exposure Limits (PEL)
 - 3.1.6 Special Hazards
 - 3.1.7 PCB Caution Label
 - 3.1.8 PCB Caution Sign
- 3.2 WORK PROCEDURE
 - 3.2.1 No Smoking
 - 3.2.2 Work Operations
- 3.3 PCB TRANSFORMERS
 - 3.3.1 Draining of Transformer Liquid
 - 3.3.2 Markings
 - 3.3.3 Laboratory Analysis

- 3.3.4 Markings
 - 3.3.4.1 Transformers, Less Than 50 ppm
 - 3.3.4.2 Transformers, 50-499 ppm
 - 3.3.4.3 Transformers, Greater Than 500 ppm
 - 3.3.4.4 Drums
- 3.4 PCB REMOVAL
 - 3.4.1 Confined Spaces
 - 3.4.2 Control Area
 - 3.4.3 Exhaust Ventilation
 - 3.4.4 Temperatures
 - 3.4.5 Solvent Cleaning
 - 3.4.6 Drip Pans
 - 3.4.7 Evacuation Procedures
- 3.5 PCB SPILL CLEANUP REQUIREMENTS
 - 3.5.1 PCB Spills
 - 3.5.2 PCB Spill Control Area
 - 3.5.3 PCB Spill Cleanup
- 3.6 STORAGE FOR DISPOSAL
 - 3.6.1 Storage Containers for PCBs
 - 3.6.2 Waste Containers
 - 3.6.3 PCB Articles and PCB-Contaminated Items
 - 3.6.4 Approval of Storage Site
- 3.7 CLEANUP
- 3.8 PCB DISPOSAL AND MANAGEMENT

-- End of Section Table of Contents --

SECTION 02 84 33

REMOVAL AND DISPOSAL OF POLYCHLORINATED BIPHENYLS (PCBs)

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

U.S. NATIONAL ARCHIVES AND RECORDS ADMINISTRATION (NARA)

29 CFR 1910.1000	Air Contaminants
29 CFR 1910.145	Accident Prevention Signs and Tags
40 CFR 761	Polychlorinated Biphenyls (PCBs) Manufacturing, Processing, Distribution in Commerce, and Use Prohibitions
49 CFR 171	General Information, Regulations, and Definitions
49 CFR 172	Hazardous Materials Table, Special Provisions, Hazardous Materials Communications, Emergency Response Information, and Training Requirements
49 CFR 173	Shippers - General Requirements for Shipments and Packagings
49 CFR 174	Carriage by Rail
49 CFR 175	Carriage by Aircraft
49 CFR 176	Carriage by Vessel
49 CFR 177	Carriage by Public Highway
49 CFR 178	Specifications for Packagings
49 CFR 179	Specifications for Tank Cars

1.2 REQUIREMENTS

The work includes the removal and disposal of material containing PCBs located in paint coatings, caulking, and electrical equipment, and as indicated on the drawings. Perform work in accordance with 40 CFR 761 and the requirements specified herein.

1.3 DEFINITIONS

1.3.1 Leak

Leak or leaking means any instance in which a PCB Article, PCB Container, or PCB Equipment has any PCBs on any portion of its external surface.

1.3.2 PCBs

PCBs as used in this specification shall mean the same as PCBs, PCB Article, PCB Article Container, PCB Container, PCB Equipment, PCB Item, PCB Transformer, PCB-Contaminated Electrical Equipment, as defined in 40 CFR 761, Section 3, Definitions.

1.3.3 Spill

Spill means both intentional and unintentional spills, leaks, and other uncontrolled discharges when the release results in any quantity of PCBs running off or about to run off the external surface of the equipment or other PCB source, as well as the contamination resulting from those releases.

1.4 QUALITY ASSURANCE

1.4.1 Training

Instruct employees on the dangers of PCB exposure, on respirator use, decontamination, and applicable OSHA and EPA regulations.

1.4.2 Certified Industrial Hygienist (CIH)

Obtain the services of an industrial hygienist certified by the American Board of Industrial Hygiene to certify training, review and approve the PCB removal plan, including determination of the need for personnel protective equipment (PPE) in performing PCB removal work.

1.4.3 Regulation Documents

Maintain at all times one copy each at the office and one copy each in view at the job site 29 CFR 1910.1000, 40 CFR 761, and Contractor work practices for removal, storage and disposal of PCBs.

1.4.4 Surveillance Personnel

Surveillance personnel may enter PCB control areas for brief periods of time provided they wear disposable polyethylene gloves and disposal polyethylene foot covers, as a minimum. Additional protective equipment may be required if respiratory hazard is involved or if skin contact with PCB is involved.

1.5 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for Contractor Quality Control approval. The following shall be submitted in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-07 Certificates

Training certification

Qualifications of CIH

PCB removal work plan

PCB disposal plan

Notification

1.6 EQUIPMENT

1.6.1 Special Clothing

Work clothes shall consist of PPE as required by OSHA regulations, including, but not limited to the following:

- a. Disposable coveralls
- b. Gloves (Disposable rubber gloves may be worn under these)
- c. Disposable foot covers (polyethylene)
- d. Chemical safety goggles
- e. Half mask cartridge respirator.

1.6.2 Special Clothing for Government Personnel

Provide PPE specified in paragraph entitled "Special Clothing" to the Contracting Officer as required for inspection of the work.

1.6.3 PCB Spill Kit

Assemble a spill kit to include the following items:

<u>ITEM</u>	<u>MINIMUM QUANTITY</u>
1. Disposable gloves (polyethylene)	6 prs
2. Gloves with a high degree of impermeability to PCB	6 prs
3. Disposable coveralls with permeation resistance to PCB	4 ea
4. Chemical safety goggles	2 ea
5. Disposable foot covers (polyethylene)	6 prs
6. PCB Caution Sign: "PCB Spill--Authorized Personnel Only"	2 ea
7. Banner guard or equivalent banner material	100 feet
8. Absorbent material	
9. Blue polyethylene waste bags	5 bags
10. Cloth backed tape	5 ea
11. Area access logs, blank	1 roll
12. Brattice cloth, 6' x 6'	10 ea
13. Rags	1 piece
14. Ball point pens	20 ea
15. Herculite, 4' x 4' and 8' x 8'	2 ea
16. Blank metal signs and grease pencils	1 ea

	<u>ITEM</u>	<u>MINIMUM QUANTITY</u>
17.	Waste containers 55 gallon drum, may be used as container for kit)	2 ea 1 ea

1.7 QUALITY ASSURANCE

1.7.1 Training Certification

Submit certificates, prior to the start of work but after the main abatement submittals, signed and dated by the CIH and by each employee stating that the employee has received training. Certificates shall be organized by individual worker, not grouped by type of certificates.

1.7.2 Qualifications of CIH

Submit the name, address, and telephone number of the Industrial Hygienist selected to perform the duties in paragraph entitled "Certified Industrial Hygienist." Submit proper documentation that the Industrial Hygienist is certified, including certification number and date of certification/recertification.

1.7.3 PCB Removal Work Plan

Submit a detailed job-specific plan of the work procedures to be used in the removal of PCB-containing materials, not to be combined with other hazardous abatement plans. Provide a Table of Contents for each abatement submittal which shall follow the sequence of requirements in the contract. The plan shall include a sketch showing the location, size, and details of PCB control areas, location and details of decontamination rooms, change rooms, shower facilities, and mechanical ventilation system. Include in the plan, eating, drinking, smoking and restroom procedures, interface of trades, sequencing of PCB related work, PCB disposal plan, respirators, protective equipment, and a detailed description of the method of containment of the operation to ensure that PCB contamination is not spread or carried outside of the control area. Include provisions to ensure that airborne PCB concentrations of 3.10 E-08 pound per cubic feet of air are not exceeded outside of the PCB control area. Include air sampling, training and strategy, sampling methodology, frequency, duration of sampling, and qualifications of air monitoring personnel in the air sampling portion of the plan. Obtain approval of the plan prior to the start of PCB removal work.

1.7.4 PCB Disposal Plan

Submit a PCB Disposal Plan within 45 calendar days after award of contract for Contracting Officer's approval. The PCB Disposal Plan shall comply with applicable requirements of Federal, State, and local PCB waste regulations and Section 01 57 20.00 10 ENVIRONMENTAL PROTECTION and address:

- a. Identification of PCB wastes associated with the work.
- b. Estimated quantities of wastes to be generated and disposed of.
- c. Names and qualifications of each contractor that will be transporting, storing, treating, and disposing of the wastes. Include the facility location and a 24-hour point of contact.

- d. Names and qualifications (experience and training) of personnel who will be working on-site with PCB wastes.
- e. List of waste handling equipment to be used in performing the work, to include cleaning, volume reduction, and transport equipment.
- f. Spill prevention, containment, and cleanup contingency measures to be implemented.
- g. Work plan and schedule for PCB waste containment, removal and disposal. Wastes shall be cleaned up and containerized daily.

1.7.5 Notification

Notify the Contracting Officer 20 days prior to the start of PCB removal work.

PART 2 PRODUCTS

Not used.

PART 3 EXECUTION

3.1 PROTECTION

3.1.1 Decontamination Room, Clean Room and Shower Facilities

- a. Provide material and labor for construction of a decontamination room, a clean room, and shower facilities. Provide rooms with doors and attach to the exit ways of PCB work areas. Rooms shall be of sufficient size to accommodate the Contractor's operation within. Existing facilities with water closets, urinals, wash basins and showers may be used if available to the Contractor. Provide portable toilet and shower facilities. Locate shower facilities between the clean room and decontamination room. Provide separate clothing lockers or containers in each room to prevent contamination of street and work clothes.
- b. Remove PCB-contaminated PPE in the decontamination room. Workers shall then proceed to showers. Workers shall shower before lunch and at the end of each day's work. Hot water, towels, soap, and hygienic conditions are the responsibility of the Contractor.

3.1.2 PCB Control Area

Isolate PCB control area by physical boundaries to prevent unauthorized entry of personnel. Food, drink and smoking materials shall not be permitted in areas where PCBs are handled or PCB items are stored.

3.1.3 Personnel Protection

Workers shall wear and use PPE, as recommended by the Industrial Hygienist, upon entering a PCB control area. If PPE is not required per the CIH, specify in the PCB removal work plan.

3.1.4 Footwear

Work footwear shall remain inside work area until completion of the job.

3.1.5 Permissible Exposure Limits (PEL)

PEL for PCBs is 3.1 E-08 lb/cubic foot on an 8-hour time weighted average basis.

3.1.6 Special Hazards

- a. PCBs shall not be exposed to open flames or other high temperature sources since toxic decomposition by-products may be produced.
- b. PCBs shall not be heated to temperatures of 135 degrees F or higher without Contracting Officer's concurrence.

3.1.7 PCB Caution Label

40 CFR 761, Subpart C. Affix labels to PCB waste containers and other PCB-contaminated items. Provide label with sufficient print size to be clearly legible, with bold print on a contrasting background, displaying the following: CAUTION: Contains PCBs (Polychlorinated Biphenyls).

3.1.8 PCB Caution Sign

29 CFR 1910.145. Provide signs at approaches to PCB control areas. Locate signs at such a distance that personnel may read the sign and take the necessary precautions before entering the area.

3.2 WORK PROCEDURE

Furnish labor, materials, services, and equipment necessary for the complete removal of PCBs located at the site as indicated or specified in accordance with local, State, or Federal regulations. Package and mark PCB as required by EPA and DOT regulations and dispose of off Government property in accordance with EPA, DOT, and local regulations at a permitted site.

3.2.1 No Smoking

Smoking is not permitted within 50 feet of the PCB control area. Provide "No Smoking" signs as directed by the Contracting Officer.

3.2.2 Work Operations

Ensure that work operations or processes involving PCB or PCB-contaminated materials are conducted in accordance with 40 CFR 761 and the applicable requirements of this section, including but not limited to:

- a. Obtaining advance approval of PCB storage sites.
- b. Notifying Contracting Officer prior to commencing the operation.
- c. Reporting leaks and spills to the Contracting Officer.
- d. Cleaning up spills.
- e. Maintaining an access log of employees working in a PCB control area and providing a copy to the Contracting Officer upon completion of the operation.

- f. Inspecting PCB and PCB-contaminated items and waste containers for leaks and forwarding copies of inspection reports to the Contracting Officer.
- g. Maintaining a spill kit as specified in paragraph entitled "PCB Spill Kit."
- h. Maintaining inspection, inventory and spill records.

3.3 PCB TRANSFORMERS

3.3.1 Draining of Transformer Liquid

Perform work in accordance with 49 CFR 171, 49 CFR 172, 49 CFR 173, 49 CFR 174, 49 CFR 175, 49 CFR 176, 49 CFR 177, 49 CFR 178, and 49 CFR 179, Subchapter C and as specified herein. Drain the transformer, switches, and regulators of free flowing liquid prior to transportation. Place the drained liquids in DOT Spec 17E drums. The drums shall not contain more than 50 gallons of oil. If the equipment cannot be drained, then place it in DOT Spec 17C drums.

3.3.2 Markings

Provide drums and drained PCB-contaminated electrical equipment with caution label markings as specified in paragraph entitled "PCB Caution Label."

3.3.3 Laboratory Analysis

All transformers shall have a laboratory analysis for turn-in. The only two exceptions to this rule are:

- a. The transformer is hermetically sealed (solder sealed or fusion sealed. No access ports or openings).
- b. The name plate states that the transformer contains pyranol, interteen, etc.

Attach a copy of the lab analysis to both the DD 1348-1 and the transformer itself.

3.3.4 Markings

3.3.4.1 Transformers, Less Than 50 ppm

Add conventional absorbent material specified for spill containment to absorb residue oil remaining after draining. Write the date drained on the transformer. Turn in transformers to the RRMF. Telephone 861-8795 to schedule appointment for turn-in.

3.3.4.2 Transformers, 50-499 ppm

Same procedure as transformers in the less than 50 ppm range.

3.3.4.3 Transformers, Greater Than 500 ppm

Stencil date drained on the transformer. Turn in transformer to the RRMF.

3.3.4.4 Drums

Stencil on DOT-approved 55 gallon drums containing PCB liquid the following:

- a. ppm
- b. Date drum filled
- c. Serial number of transformer liquid came from
- d. National Stock Number
 - (1) "9999-00-OIL" for <50 ppm
 - (2) "9999-00-CONPCB" for 50-499 ppm
 - (3) "9999-00-PCBOIL" for >500 ppm

Do not mix different ppms in the same drum. Drums must have a 2 inch ullage space from the top of the drum.

3.4 PCB REMOVAL

Select PCB removal procedure to minimize contamination of work areas with PCB or other PCB-contaminated debris/waste. Handle PCBs such that no skin contact occurs. PCB removal process should be described in the work plan.

3.4.1 Confined Spaces

As feasible, do not carry out PCB handling operations in confined spaces. A confined space shall mean a space having limited means of egress and inadequate cross ventilation.

3.4.2 Control Area

Establish a PCB control area around the PCB item as specified in paragraph entitled "PCB Control Area." Only personnel briefed on the elements in the paragraph entitled "Training" and on the handling precautions shall be allowed into the area.

3.4.3 Exhaust Ventilation

If used, exhaust ventilation for PCB operations shall discharge to the outside and away from personnel.

3.4.4 Temperatures

As feasible, handle PCBs at ambient temperatures and not at elevated temperatures.

3.4.5 Solvent Cleaning

Clean contaminated tools, containers, etc., after use by rinsing three times with an appropriate solvent or by wiping down three times with a solvent wetted rag. Suggested solvents are stoddard solvent or hexane.

3.4.6 Drip Pans

Drip pans are required under portable PCB transformers and rectifiers in

use or stored for use. The pans shall have a containment volume of at least one and one-half times the internal volume of PCBs in the item.

3.4.7 Evacuation Procedures

Procedures shall be written for evacuation of injured workers. Aid for a seriously injured worker shall not be delayed for reasons of decontamination.

3.5 PCB SPILL CLEANUP REQUIREMENTS

3.5.1 PCB Spills

Immediately report to the Contracting Officer any PCB spills on the ground or in the water, PCB spills in drip pans, or PCB leaks. Handle, contain, and document spills in accordance with contract clause "Spills".

3.5.2 PCB Spill Control Area

Rope off an area around the edges of a PCB leak or spill and post a "PCB Spill Authorized Personnel Only" caution sign. Immediately transfer leaking items to a drip pan or other container.

3.5.3 PCB Spill Cleanup

Contractor shall contain spills and document the spill area to ensure it is PCB-free. Handle spills in accordance with the contract clause "Spills." The KSC Spill Cleanup Team will be responsible for final cleanup of a spill.

3.6 STORAGE FOR DISPOSAL

3.6.1 Storage Containers for PCBs

Store PCBs in Government provided containers.

3.6.2 Waste Containers

Label as directed by the Government.

3.6.3 PCB Articles and PCB-Contaminated Items

Label as directed by the Government.

3.6.4 Approval of Storage Site

Storage sites shall be in accordance with the contract clause "PCB Management".

3.7 CLEANUP

Maintain surfaces of the PCB control area free of accumulations of PCBs. Restrict the spread of dust and debris; keep waste from being distributed over work area.

- a. Do not remove the PCB control area and warning signs prior to the Contracting Officer's approval. Reclean areas showing residual PCBs.

3.8 PCB DISPOSAL AND MANAGEMENT

Comply with disposal requirements and procedures outlined in the contract clause "PCB Management" and 40 CFR 761.

-- End of Section --

SECTION TABLE OF CONTENTS

DIVISION 31 - EARTHWORK

SECTION 31 00 00

EARTHWORK

PART 1 GENERAL

- 1.1 REFERENCES
- 1.2 DEFINITIONS
 - 1.2.1 Satisfactory Materials
 - 1.2.2 Unsatisfactory Materials
 - 1.2.3 Degree of Compaction
 - 1.2.4 Unstable Material
- 1.3 DEWATERING WORK PLAN
- 1.4 QUALITY CONTROL TESTING DURING CONSTRUCTION
- 1.5 TEST REPORTS
- 1.6 EXISTING CONDITIONS
- 1.7 DRAWINGS
- 1.8 SUBMITTALS

PART 2 PRODUCTS

- 2.1 REQUIREMENTS FOR OFFSITE SOILS
- 2.2 BACKFILL AND FILL MATERIALS
- 2.3 COHESIONLESS MATERIALS
- 2.4 COHESIVE MATERIALS
- 2.5 SUBBASE MATERIAL
- 2.6 COMPOST
- 2.7 COMPACTION EQUIPMENT

PART 3 EXECUTION

- 3.1 GENERAL REQUIREMENTS
- 3.2 UNAUTHORIZED EXCAVATION
- 3.3 SURFACE PREPARATION
 - 3.3.1 Stripping Of Topsoil
 - 3.3.2 Clearing
 - 3.3.3 Tree Removal
 - 3.3.4 Pruning
 - 3.3.5 Grubbing Operations
 - 3.3.6 Filling Depressions
 - 3.3.7 Stability of Sides
 - 3.3.8 Shoring and Bracing
- 3.4 GENERAL EXCAVATION
 - 3.4.1 Ditches, Gutters, and Channels
 - 3.4.2 Drainage
 - 3.4.3 Dewatering
 - 3.4.3.1 Dewatering System
 - 3.4.3.2 Observation Wells
 - 3.4.3.3 Discharge
 - 3.4.4 Trench Excavation Requirements

- 3.4.4.1 Removal of Unstable Material
- 3.4.4.2 Removal of Unsatisfactory Soil Materials
- 3.4.5 Underground Utilities
- 3.5 OPENING AND DRAINAGE OF EXCAVATION AND BORROW PITS
- 3.6 SHORING
 - 3.6.1 General Requirements
- 3.7 GRADING AREAS
 - 3.7.1 Grading Outside Building Lines
- 3.8 GROUND SURFACE PREPARATION
 - 3.8.1 General Requirements
 - 3.8.2 Frozen Material
- 3.9 UTILIZATION OF EXCAVATED MATERIALS
- 3.10 FILLING AND BACKFILLING
 - 3.10.1 Preparations Prior to Backfill Placement
 - 3.10.2 Preparation of Ground Surface to Receive Fill
 - 3.10.3 Placement and Compaction
 - 3.10.4 Trench Backfill
 - 3.10.4.1 Replacement of Unstable Material
- 3.11 COMPACTION
 - 3.11.1 Percentage of Maximum Density Requirements
 - 3.11.2 Moisture Control
- 3.12 SPECIAL REQUIREMENTS
 - 3.12.1 Water Lines
 - 3.12.2 Electrical Distribution System
- 3.13 EMBANKMENTS
 - 3.13.1 Earth Embankments
- 3.14 SUBGRADE PREPARATION
 - 3.14.1 Proof Rolling
 - 3.14.2 Construction
 - 3.14.3 Compaction
 - 3.14.3.1 Subgrade for Pavements
- 3.15 FINISHING
 - 3.15.1 Subgrade and Embankments
 - 3.15.2 Grading Around Structures
- 3.16 TESTING
 - 3.16.1 Fill and Backfill Material Gradation
 - 3.16.2 In-Place Densities
 - 3.16.3 Check Tests on In-Place Densities
 - 3.16.4 Moisture Contents
 - 3.16.5 Optimum Moisture and Laboratory Maximum Density
 - 3.16.6 Tolerance Tests for Subgrades
- 3.17 MAINTENANCE
 - 3.17.1 Protection of Graded Areas
 - 3.17.2 Reconditioning Compacted Areas

-- End of Section Table of Contents --

SECTION 31 00 00

EARTHWORK

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN ASSOCIATION OF STATE HIGHWAY AND TRANSPORTATION OFFICIALS
(AASHTO)

AASHTO M 145	(1991; R 2000) Classification of Soils and Soil-Aggregate Mixtures for Highway Construction Purposes
AASHTO T 180	(2001; R 2004) Moisture-Density Relations of Soils Using a 4.54-kg (10-lb) Rammer and an 457-mm (18-in) Drop
AASHTO T 2	(1991; R 2006) Standard Method of Test for Sampling of Aggregates (same as ASTM D 75)
AASHTO T 87	(1986; R 2004) Standard Method of Test for Dry Preparation of Disturbed Soil and Soil Aggregate Samples for Test

ASTM INTERNATIONAL (ASTM)

ASTM C 117	(2004) Materials Finer Than 75 micrometer (No. 200) Sieve in Mineral Aggregates by Washing
ASTM C 136	(2006) Standard Test Method for Sieve Analysis of Fine and Coarse Aggregates
ASTM D 1556	(2007) Density and Unit Weight of Soil in Place by the Sand-Cone Method
ASTM D 1557	(2007) Standard Test Methods for Laboratory Compaction Characteristics of Soil Using Modified Effort (56,000 ft-lbf/ft ³) (2700 kN-m/m ³)
ASTM D 2216	(2005) Laboratory Determination of Water (Moisture) Content of Soil and Rock by Mass
ASTM D 2487	(2006e1) Soils for Engineering Purposes (Unified Soil Classification System)
ASTM D 3740	(2004) Minimum Requirements for Agencies Engaged in the Testing and/or Inspection

of Soil and Rock as Used in Engineering
Design and Construction

- ASTM D 422 (1963; R 2007) Particle-Size Analysis of Soils
- ASTM D 4318 (2005) Liquid Limit, Plastic Limit, and Plasticity Index of Soils
- ASTM D 6938 (2007a) Standard Test Method for In-Place Density and Water Content of Soil and Soil-Aggregate by Nuclear Methods (Shallow Depth)

U.S. ENVIRONMENTAL PROTECTION AGENCY (EPA)

- EPA 600/4-79/020 (1983) Methods for Chemical Analysis of Water and Wastes
- EPA SW-846.3-3 (1999, Third Edition, Update III-A) Test Methods for Evaluating Solid Waste: Physical/Chemical Methods

1.2 DEFINITIONS

1.2.1 Satisfactory Materials

Satisfactory materials shall mean ASTM D 2487, SP, SP-SM, SM, A-2-3, A-2-4, and A-3.

1.2.2 Unsatisfactory Materials

Unsatisfactory soil materials shall mean ASTM D 2487, GW, GP, GM, GP-GM, CW-GM, GC, GP-GC, GM-GC, SW, SW-SM, SC, SW-SC, SP-SC, CL, ML, CL-ML, CH, MH, and AASHTO M 145, Soil Classification Groups A-2-5, A-2-6, A-2-7, A-4, A-5, A-6, and A-7, peat, muck and other highly organic soil, and other highly organic material, buried vegetation, roots, and post consumer materials such as trash, refuse, or other debris and soil materials of any classification that have a moisture content at the time of compaction beyond the range of 1 percentage point below and 3 percentage points above the optimum moisture content of the soil material as determined by moisture-density relations test.

1.2.3 Degree of Compaction

Degree of compaction required is expressed as a percentage of the maximum density obtained by the test procedure, Method B or D.

1.2.4 Unstable Material

Unstable materials are too wet to properly support the appurtenant structure.

1.3 DEWATERING WORK PLAN

Submit procedures for accomplishing dewatering work in accordance with drawings.

1.4 QUALITY CONTROL TESTING DURING CONSTRUCTION

Soil survey for satisfactory soil materials and samples of soil materials shall be furnished by the Contractor. A certified soil-testing service approved by the Contracting Officer shall be provided by the Contractor. Testing shall include soil survey for satisfactory soil materials; sampling and testing soil materials proposed for use in the work, and field-testing facilities for quality control during construction period.

Testing agencies shall conform to the requirements of ASTM D 3740.

Soil materials shall be tested by the Contractor during construction as follows:

<u>MATERIAL</u>	<u>REQUIREMENT</u>	<u>TEST METHOD</u>	<u>NUMBER OF TESTS</u>
Satisfactory soil materials	Sieve analysis of fine and coarse aggregates	ASTM C 136	One daily for each soil material from each source; additional test whenever there is any apparent change
	Preparation of samples	AASHTO T 87	
	Sieve analysis is of fine and coarse aggregates	ASTM C 136	
	Amount of material passing No. 200 sieve	ASTM C 117	
	Moisture content of subbase material	ASTM D 2216	
Soil materials prior to compaction	Moisture-density relations of soil	ASTM D 1557	One of each type of subgrade soil material except under backfill for structures; one for each backfill and fill material from each source
Soil material-in-place after compaction	Density of soil-in-place	ASTM D 1556 Sand Cone Method	At least three daily for each subgrade soil material except under backfill for structures, and for each layer and backfill and fill

<u>MATERIAL</u>	<u>REQUIREMENT</u>	<u>TEST METHOD</u>	<u>NUMBER OF TESTS</u> material; for each 400 linear feet of trench or fraction thereof, whichever is greater; and ad- ditional test whenever there is any change in moisture conditions
-----------------	--------------------	--------------------	---

1.5 TEST REPORTS

No soil material shall be used until a written report of Soil Test results has been reviewed and approved by the Contracting Officer.

1.6 EXISTING CONDITIONS

Records of Underground Utilities Location of Inspections, Location of Testing and Location of Utility Approvals shall be submitted to the Contracting Officer prior to start of work.

1.7 DRAWINGS

As-Built Drawings shall be submitted in accordance with Section 01 33 00 SUBMITTAL PROCEDURES.

1.8 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for Contractor Quality Control approval. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-01 Preconstruction Submittals

Shoring; G

Dewatering Work Plan; G

Submit 15 days prior to starting work.

Contractor shall record Existing Conditions prior to starting work in accordance with the paragraph entitled, "Existing Conditions," of this section.

SD-02 Shop Drawings

As-Built Drawings shall be submitted in accordance with paragraph entitled, "Drawings," of this section.

SD-06 Test Reports

Borrow Site Testing

Within 24 hours of conclusion of physical tests, 6 copies of test

results, including calibration curves and results of calibration tests. Results of testing at the borrow site.

Contractor shall submit written Test Reports of Soil Test results within 5 calendar days. Submit test reports in accordance with paragraph entitled, "Quality Control Testing During Construction," of this section.

SD-07 Certificates

Certificates for Proposed Soil Materials shall be submitted to the Contracting Officer in accordance with paragraph entitled, "Backfill and Fill Materials," of this section.

Certificates of Compliance for Compost shall be submitted indicating grade and compliance to state and local regulations.

PART 2 PRODUCTS

2.1 REQUIREMENTS FOR OFFSITE SOILS

Test offsite soils brought in for use as backfill for Total Petroleum Hydrocarbons (TPH), Benzene, Toluene, Ethyl Benzene, and Xylene (BTEX) and full Toxicity Characteristic Leaching Procedure (TCLP) including ignitability, corrosivity and reactivity. Backfill shall contain a maximum of 100 parts per million (ppm) of total petroleum hydrocarbons (TPH) and a maximum of 10 ppm of the sum of Benzene, Toluene, Ethyl Benzene, and Xylene (BTEX) and shall pass the TCLP test. Determine TPH concentrations by using EPA 600/4-79/020 Method 418.1. Determine BTEX concentrations by using EPA SW-846.3-3 Method 5030/8020. Perform TCLP in accordance with EPA SW-846.3-3 Method 1311. Provide Borrow Site Testing for TPH, BTEX and TCLP from a composite sample of material from the borrow site, with at least one test from each borrow site. Do not bring material onsite until tests have been approved by the Contracting Officer.

2.2 BACKFILL AND FILL MATERIALS

Backfill and fill material shall consist of sandy clay, sand, gravel, soft shale, or other satisfactory soil materials as defined in Subpart 1.2.1 Satisfactory Materials.

Materials for backfill and fill shall be satisfactory soil materials, free of clay clods, rock or gravel larger than 2 inches in any dimension, debris, waste, frozen materials and other deleterious matter, and shall be satisfactory soil material as follows:

<u>MATERIAL</u>	<u>REQUIREMENT</u>	<u>TEST METHOD</u>	<u>NUMBER OF TESTS</u>
Satisfactory soil materials	Sampling	AASHTO T 2	One for each source of material to determine conformance to definition of satisfactory soil materials; additional tests whenever there is any apparent change
	Preparation of samples	AASHTO T 87	
	Sieve analysis of fine and coarse aggregate	ASTM C 136	
	Mechanical analysis of	ASTM D 422	

<u>MATERIAL</u>	<u>REQUIREMENT</u>	<u>TEST METHOD</u>	<u>NUMBER OF TESTS</u>
	soils		
	Liquid limit of soils	ASTM D 4318	
	Plastic limit and plasticity index of soils	ASTM D 4318	
	Moisture-den- sity relations of soil	AASHTO T 180, Method B or D	

2.3 COHESIONLESS MATERIALS

Cohesionless soil materials include gravels, gravel-sand mixtures, sands, and gravelly-sands. Moisture-density relations of compacted cohesionless soils, when plotted on graphs, will show straight lines or reverse-shaped moisture density curves.

2.4 COHESIVE MATERIALS

Cohesive soil materials include clayey and silty gravels, sand-clay mixtures, gravel-silt mixtures, clayey and silty sands, sand-silt mixtures, clays, silts, and very fine sands. Moisture-density relations of compacted cohesive soils, when plotted on graphs, will show normal moisture-density curves.

2.5 SUBBASE MATERIAL

Subbase material shall be a naturally or artificially graded mixture of natural or crushed gravel, crushed stone, or sand.

2.6 COMPOST

Compost shall be yard trimmings or yard waste compost processed and graded according to state and local regulations.

2.7 COMPACTION EQUIPMENT

Compaction equipment shall consist of sheepsfoot rollers, pneumatic-tired rollers, tamper rollers, vibrating tampers, or other compaction equipment capable of obtaining the required density throughout the entire layer.

PART 3 EXECUTION

3.1 GENERAL REQUIREMENTS

Before starting earthwork, the location of underground utilities shall be carefully verified by hand methods. Utilities to be left in place shall be protected from damage.

Excavation, filling, backfilling, and grading shall be to subgrade elevations specified.

Excavated materials suitable for backfill shall be piled in an orderly manner sufficiently distant from excavations to prevent overloading,

slides, and cave-ins.

Excavations shall be done in ways that will prevent surface water and subsurface water from flowing into excavations and will also prevent flooding of the site and surrounding area.

3.2 UNAUTHORIZED EXCAVATION

Unauthorized excavation shall consist of removal of materials beyond indicated subgrade elevations or side dimensions specified without specific direction and shall be replaced as specified at no additional cost to the Government.

Unauthorized excavation under foundations or retaining walls shall be filled by lowering the bottom elevation of the footing or base to the excavation bottom without altering the approved top elevation.

Elsewhere unauthorized excavations shall be backfilled and compacted as specified for authorized excavations of the same classification.

3.3 SURFACE PREPARATION

Heavy growths of grass and other vegetation, roots, debris, stones, objects larger than 2 inches in any dimension, and other materials undesirable to the subsurface construction shall be removed by mowing, grubbing, raking, or other methods from the surface of areas to be stripped.

3.3.1 Stripping Of Topsoil

Where indicated or directed, strip topsoil to a depth of 4 inch. Spread topsoil on areas already graded and prepared for topsoil, or transported and deposited in stockpiles convenient to areas that are to receive application of the topsoil later, or at locations indicated or specified. Keep topsoil separate from other excavated materials, brush, litter, objectionable weeds, roots, stones larger than 2 inch in diameter, and other materials that would interfere with planting and maintenance operations. Excavated topsoil shall be transported to, and stockpiled in, designated topsoil storage areas.

3.3.2 Clearing

Clearing shall consist of the felling, trimming, and cutting of trees into sections and the satisfactory disposal of the trees and other vegetation designated for removal, including downed timber, snags, brush, and rubbish occurring within the areas to be cleared. Trees, stumps, roots, brush, and other vegetation in areas to be cleared shall be cut off flush with or below the original ground surface, except such trees and vegetation as may be indicated or directed to be left standing. Trees designated to be left standing within the cleared areas shall be trimmed of dead branches 1-1/2 inches or more in diameter and shall be trimmed of all branches the heights indicated or directed. Limbs and branches to be trimmed shall be neatly cut close to the bole of the tree or main branches. Cuts more than 1-1/2 inches in diameter shall be painted with an approved tree-wound paint. Apply herbicide in accordance with the manufacturer's label to the top surface of stumps designated not to be removed.

3.3.3 Tree Removal

Where indicated or directed, trees and stumps that are designated as trees

shall be removed from areas outside those areas designated for clearing and grubbing. This work shall include the felling of such trees and the removal of their stumps and roots as specified in paragraph GRUBBING. Trees shall be disposed of as specified in paragraph DISPOSAL OF MATERIALS.

3.3.4 Pruning

Trim trees designated to be left standing within the cleared areas of dead branches 1 1/2 inches or more in diameter; and trim branches to heights and in a manner as indicated. Neatly cut limbs and branches to be trimmed close to the bole of the tree or main branches. Paint cuts more than 1 1/4 inches in diameter with an approved tree wound paint.

3.3.5 Grubbing Operations

Grubbing shall consist of the removal and disposal of stumps, roots larger than 3 inches in diameter, and matted roots from the designated grubbing areas. Material to be grubbed, together with logs and other organic or metallic debris not suitable for foundation purposes, shall be removed to a depth of not less than 18 inches below the original surface level of the ground in areas indicated as areas to be paved and sodded. Material to be grubbed, together with logs and other organic or metallic debris not suitable for foundation purposes, shall be removed to a depth of not less than 10 feet below the original surface level of the ground in areas indicated as areas for buildings, dry retention ponds and in a 10 foot wide perimeter around Buildings.

3.3.6 Filling Depressions

Depressions resulting from grubbing operations shall be completely filled with acceptable backfilling material, unless further excavation or earthwork is required.

Prior to filling, subgrade surfaces of depressions shall be free of standing water, frost, or frozen material. Unsatisfactory soil materials shall be removed.

Any structural backfill or fill required for site development should be placed in loose lifts not exceeding 12 inches in thickness and compacted by the use of a vibratory drum roller. If hand-held or track-mounted compaction equipment is used, the lift thickness should be reduced to 6 and 8 inches, respectively. Each layer shall be compacted at the optimum moisture content to a density equal to the original adjacent ground. Surface of filled depressions shall be graded to meet adjacent contours and to provide surface water drainage.

3.3.7 Stability of Sides

Sides of excavations over 5 feet in depth shall be sloped not steeper than 34 degrees from the horizontal (slope 1/1.5) of the material excavated or shall be shored and braced where sloping is not possible because of space restrictions, stability of material excavated, or where excavations are subjected to vibrations from vehicular traffic, the operation of machinery, or any other source.

Sides and slopes of excavations shall be maintained in a safe condition by scaling, benching, shelving, or bracing until completion of backfill placement.

3.3.8 Shoring and Bracing

Shoring and bracing in excavations shall be maintained for the entire length of time excavations will be open. Shoring and bracing shall be carried down with the excavation.

Sheeting used to prevent lateral movement of soil shall be removed in accordance with the requirements.

Untreated sheeting shall not be left in place beneath structures or pavements.

3.4 GENERAL EXCAVATION

3.4.1 Ditches, Gutters, and Channels

Excavation shall be accomplished by cutting accurately to the cross sections, grades, and elevations indicated. Excessive open-ditch or gutter excavation shall be backfilled with suitable materials to grade at no additional cost.

3.4.2 Drainage

Provide for the collection and disposal of surface and subsurface water encountered during construction. Completely drain construction site during periods of construction to keep soil materials sufficiently dry. Construct storm drainage features (ponds/basins) at the earliest stages of site development, and throughout construction grade the construction area to provide positive surface water runoff away from the construction activity and provide temporary ditches, swales, and other drainage features and equipment as required to maintain dry soils. When unsuitable working platforms for equipment operation and unsuitable soil support for subsequent construction features develop, remove unsuitable material and provide new soil material as specified herein. It is the responsibility of the Contractor to assess the soil and ground water conditions presented by the plans and specifications and to employ necessary measures to permit construction to proceed.

3.4.3 Dewatering

3.4.3.1 Dewatering System

The dewatering system shall be adequate to pre-drain the soils to be excavated to the extent that the piezometric water level in the construction area is a minimum of 2 feet below the bottom of the excavation, side slopes of excavations, or bottom of the footings at all times, or as otherwise required to obtain the specified compaction and installation conditions. Pipeline trenches must be dewatered at least 6 inches below the trench bottom.

In the event of layered soils, the hydrostatic head in the zone below the subgrade elevation shall be relieved to prevent uplift.

Unless otherwise noted and prior to any excavating below or within 2 feet above the groundwater level, a dewatering system shall be placed into operation to lower water levels to the extent specified previously, and then shall be operated continuously 24 hours per day, 7 days a week, until work has been completed to the satisfaction of the Contracting Officer.

Where used, well points shall be installed in an approved manner and in sufficient numbers to provide the necessary removal of water as stated previously. Well points and header piping shall be installed in such a manner that traffic on public thoroughfares and site access roads will not be impeded.

The Contractor shall be solely responsible for the arrangements, locations, and depths of the dewatering system necessary to accomplish the specified work.

To prevent excessive noise, exhaust from all pumps and engines shall be silenced and muffled.

Wellpoint pump discharge shall be controlled to prevent erosion, undermining, and all other damage, and be piped to approved locations.

The Contractor shall comply with any and all applicable regulations and permitting requirements concerning groundwater and discharge.

Excavations shall be kept free from water during the placing of concrete structures and utilities.

3.4.3.2 Observation Wells

The Contractor shall install observation wells as may be required to record accurate water levels.

The Contractor shall be responsible for maintaining wells and observing and recording the elevation of the piezometric water levels daily.

3.4.3.3 Discharge

Discharge of water from dewatering shall be in accordance with contract clause "Dewatering/Consumptive Use Permitting."

3.4.4 Trench Excavation Requirements

Trenches shall be of adequate width and depth for the specified purpose. Side slopes of the trenches shall be as nearly vertical as practicable. Care shall be taken not to overexcavate.

Trench excavations in surfaced areas shall be by open cut, unless otherwise shown. The pavement shall be cut by concrete saw or other approved method. Cuts shall be in straight lines parallel to the utility line location and shall be to a depth of at least one quarter of the pavement thickness. The remainder of the pavement shall be broken out. Pavement shall be removed a minimum of 12 inches on each side of the trench and 6 inches beyond where the base course is to be removed.

3.4.4.1 Removal of Unstable Material

Where unstable material is encountered in the bottom of the trench, remove such material to the depth directed and replace it to the proper grade with select granular material as provided in paragraph BACKFILLING AND COMPACTION. When removal of unstable material is required due to the Contractor's fault or neglect in performing the work, the Contractor is responsible for excavating the resulting material and replacing it without additional cost to the Government.

3.4.4.2 Removal of Unsatisfactory Soil Materials

Unsatisfactory soil materials encountered that extend below the required elevations, as specified under Grubbing Operations shall be excavated to the depth directed by the Contracting Officer.

3.4.5 Underground Utilities

The Contractor is responsible for movement of construction machinery and equipment over pipes and utilities during construction. Perform work adjacent to non-Government utilities as indicated in accordance with procedures outlined by the utility company. Excavation made with power-driven equipment is not permitted within two feet of known Government-owned utility or subsurface construction. For work immediately adjacent to or for excavations exposing a utility or other buried obstruction, excavate by hand. Start hand excavation on each side of the indicated obstruction and continue until the obstruction is uncovered or until clearance for the new grade is assured. Support uncovered lines or other existing work affected by the contract excavation until approval for backfill is granted by the Contracting Officer. Report damage to utility lines or subsurface construction immediately to the Contracting Officer.

3.5 OPENING AND DRAINAGE OF EXCAVATION AND BORROW PITS

Notify the Contracting Officer sufficiently in advance of the opening of any excavation or borrow pit to permit elevations and measurements of the undisturbed ground surface to be taken. Except as otherwise permitted, excavate borrow pits and other excavation areas providing adequate drainage. Transport overburden and other spoil material to designated spoil areas or otherwise dispose of as directed. Provide neatly trimmed and drained borrow pits after the excavation is completed. Ensure that excavation of any area, operation of borrow pits, or dumping of spoil material results in minimum detrimental effects on natural environmental conditions.

3.6 SHORING

3.6.1 General Requirements

Submit a Shoring and Sheet piling plan for approval 15 days prior to starting work. Submit drawings and calculations, certified by a registered professional engineer, describing the methods for shoring and sheet piling of excavations. Finish shoring, including sheet piling, and install as necessary to protect workmen, banks, adjacent paving, structures, and utilities. Remove shoring, bracing, and sheet piling as excavations are backfilled, in a manner to prevent caving.

3.7 GRADING AREAS

Areas within the limits of grading under this section, including adjacent transition areas, shall be uniformly graded. Finished surface shall be smooth within the specified tolerances, compacted, and with uniform levels or slopes between points where elevations are indicated or between such points and existing grades.

3.7.1 Grading Outside Building Lines

Areas outside the building lines for each structure shall be graded to drain away from the structure and to prevent ponding of water after rains.

Finished surface shall be within the tolerance specified below for each area classification, compacted as specified, and free from irregular surface changes.

Grassed or planted areas:

Finished surface of areas to receive topsoil blend shall be not more than 0.10 foot above or below the indicated finish elevations.

3.8 GROUND SURFACE PREPARATION

3.8.1 General Requirements

Remove and replace unsatisfactory material with satisfactory materials, as directed by the Contracting Officer, in surfaces to receive fill or in excavated areas. Scarify the surface to a depth of 6 inches before the fill is started. Flow, step, bench, or break up sloped surfaces steeper than 1 vertical to 4 horizontal so that the fill material will bond with the existing material. When subgrades are less than the specified density, break up the ground surface to a minimum depth of 6 inch, pulverizing, and compacting to the specified density. When the subgrade is part fill and part excavation or natural ground, scarify the excavated or natural ground portion to a depth of 12 inches and compact it as specified for the adjacent fill.

3.8.2 Frozen Material

Do not place material on surfaces that are muddy, frozen, or contain frost. Finish compaction by sheepsfoot rollers, pneumatic-tired rollers, steel-wheeled rollers, or other approved equipment well suited to the soil being compacted. Moisten material as necessary to provide the moisture content that will readily facilitate obtaining the specified compaction with the equipment used.

3.9 UTILIZATION OF EXCAVATED MATERIALS

Dispose of unsatisfactory materials removed from excavations as directed by the Contracting Officer and in accordance with NASA environmental requirements. Use satisfactory material removed from excavations, insofar as practicable, in the construction of fills, embankments, subgrades, shoulders, bedding (as backfill), and for similar purposes. Do not waste any satisfactory excavated material without specific written authorization. Dispose of satisfactory material, authorized to be wasted, in designated areas approved for surplus material storage or designated waste areas as directed by the Contracting Officer. Clear and grub newly designated waste areas on Government-controlled land before disposal of waste material thereon. Stockpile and use coarse rock from excavations for constructing slopes or embankments adjacent to streams, or sides and bottoms of channels and for protecting against erosion. Do not dispose excavated material to obstruct the flow of any stream, endanger a partly finished structure, impair the efficiency or appearance of any structure, or be detrimental to the completed work in any way.

3.10 FILLING AND BACKFILLING

3.10.1 Preparations Prior to Backfill Placement

Excavations shall be backfilled as promptly as the work permits but not until completion of the following:

Approval of construction below finish grade

Inspection, testing, approval, and recording location of underground utilities

Removal of shoring and bracing; backfilling of voids with satisfactory soil material; temporary sheet piling driven below bottom of structures; and cutting off and removing of utilities in a manner that prevents settlement of the structure or utilities

Removal of trash and debris

3.10.2 Preparation of Ground Surface to Receive Fill

Vegetation, debris, unsatisfactory soil materials, obstructions, and deleterious materials shall be removed from ground surface prior to the placement of fills. Sloped surfaces steeper than 1 vertical to 4 horizontal shall be plowed, stripped, or broken up in such manner that fill material will bond with the existing material.

When the ground surface has a density less than that specified for the particular area classification, the ground surface shall be broken up, pulverized, moisture-conditioned to near optimum moisture content of the soil material, and compacted to the required depth and percentage of maximum density.

3.10.3 Placement and Compaction

Any structural backfill or fill required for site development should be placed in loose lifts not exceeding 12 inches in thickness and compacted by the use of a vibratory drum roller. If hand-held or track-mounted compaction equipment is used, the lift thickness should be reduced to 6 and 8 inches, respectively. Before compaction, each layer of backfill or fill material shall be moistened or aerated as necessary to provide the optimum moisture content of the soil material and shall then be compacted to the percentage of maximum density for each area classification as specified. Backfill or fill material shall not be placed on surfaces that are muddy, frozen, icy, or contain frost.

Backfill and fill materials adjacent to structures shall be brought up evenly around structures and shall be carried up to the indicated elevations.

Compaction adjacent to structures, within a horizontal distance from the face of the structure equal to the depth of backfill or fill material (measured from the bottom of footing or bottom of foundation or retaining wall) to final grade, shall be done with power-driven hand tampers.

3.10.4 Trench Backfill

3.10.4.1 Replacement of Unstable Material

Replace unstable material removed from the bottom of the trench or excavation with select granular material placed in layers not exceeding 6 inch loose thickness.

3.11 COMPACTION

3.11.1 Percentage of Maximum Density Requirements

Actual density of each layer of soil material-in-place shall be not less than the following percentages of the maximum density of the same soil material determined by the moisture-density test.

<u>AREA CLASSIFICATION</u>	<u>PERCENT MAXIMUM DENSITY</u>
Grassed areas	95
Walks	95
Utility trenches	95
Structures	
Each layer of back-fill material	98
Building slabs and steps	
Top 12 inches of subgrade and each layer of backfill material	98

3.11.2 Moisture Control

Moisture content in soil material at time of compaction shall be within specified limits.

Where the moisture content of a layer of soil material is below optimum before compaction, the required amount of water shall be uniformly applied to the surface of the layer of soil material and the layer of soil disked or otherwise mixed until a uniform moisture content is reached.

Where the moisture of a layer of soil material is above optimum, it shall be dried.

3.12 SPECIAL REQUIREMENTS

Special requirements for both excavation and backfill relating to the specific utilities are as follows:

3.12.1 Water Lines

Excavate trenches to a depth that provides a minimum cover of 3 feet from the existing ground surface, or from the indicated finished grade, whichever is lower, to the top of the pipe.

3.12.2 Electrical Distribution System

Provide a minimum cover of 36 inches from the finished grade to direct burial cable and conduit or duct line, unless otherwise indicated.

3.13 EMBANKMENTS

3.13.1 Earth Embankments

Construct earth embankments from satisfactory materials free of organic or frozen material and rocks with any dimension greater than 3 inches. Place the material in successive horizontal layers of loose material not more than 8 inches in depth. Spread each layer uniformly on a soil surface that has been moistened or aerated as necessary, and scarified or otherwise broken up so that the fill will bond with the surface on which it is placed. After spreading, plow, disk, or otherwise break up each layer; moisten or aerate as necessary; thoroughly mix; and compact to at least 90 percent laboratory maximum density for cohesive materials or 95 percent laboratory maximum density for cohesionless materials. Compaction requirements for the upper portion of earth embankments forming subgrade for pavements are identical with those requirements specified in paragraph SUBGRADE PREPARATION. Finish compaction by sheepsfoot rollers, pneumatic-tired rollers, steel-wheeled rollers, vibratory compactors, or other approved equipment.

3.14 SUBGRADE PREPARATION

3.14.1 Proof Rolling

Finish proof rolling on an exposed subgrade free of surface water (wet conditions resulting from rainfall) which would promote degradation of an otherwise acceptable subgrade.

3.14.2 Construction

Shape subgrade to line, grade, and cross section, and compact as specified. Include plowing, disking, and any moistening or aerating required to obtain specified compaction for this operation. Remove soft or otherwise unsatisfactory material and replace with satisfactory excavated material or other approved material as directed. Excavate rock encountered in the cut section to a depth of 6 inch below finished grade for the subgrade. Bring up low areas resulting from removal of unsatisfactory material or excavation of rock to required grade with satisfactory materials, and shape the entire subgrade to line, grade, and cross section and compact as specified. After rolling, do not show deviations for the surface of the subgrade for roadways greater than 1.0 inch when tested with a 10-foot straightedge applied both parallel and at right angles to the centerline of the area. Do not vary the elevation of the finish subgrade more than 0.05 foot from the established grade and cross section.

3.14.3 Compaction

Finish compaction by sheepsfoot rollers, pneumatic-tired rollers, steel-wheeled rollers, vibratory compactors, or other approved equipment. Except for paved areas, compact each layer of the embankment to at least 98 percent of laboratory maximum density.

3.14.3.1 Subgrade for Pavements

As indicated on the drawings.

3.15 FINISHING

Finish the surface of excavations, embankments, and subgrades to a smooth

and compact surface in accordance with the lines, grades, and cross sections or elevations shown. Provide the degree of finish for graded areas within 0.1 foot of the grades and elevations indicated except that the degree of finish for subgrades specified in paragraph SUBGRADE PREPARATION. Finish gutters and ditches in a manner that will result in effective drainage. Finish the surface of areas to be turfed from settlement or washing to a smoothness suitable for the application of turfed materials. Repair graded, topsoiled, or backfilled areas prior to acceptance of the work, and re-established grades to the required elevations and slopes.

3.15.1 Subgrade and Embankments

During construction, keep embankments and excavations shaped and drained. Maintain ditches and drains along subgrade to drain effectively at all times. Do not disturb the finished subgrade by traffic or other operation. Protect and maintain the finished subgrade in a satisfactory condition until ballast, subbase, base, or pavement is placed. Do not permit the storage or stockpiling of materials on the finished subgrade. Do not lay subbase, base course, ballast, or pavement until the subgrade has been checked and approved, and in no case place subbase, base, surfacing, pavement, or ballast on a muddy, spongy, or frozen subgrade.

3.15.2 Grading Around Structures

Construct areas within 5 feet outside of each building and structure line true-to-grade, shape to drain, and maintain free of trash and debris until final inspection has been completed and the work has been accepted.

3.16 TESTING

Perform testing by a Corps validated commercial testing laboratory or the Contractor's validated testing facility. If the Contractor elects to establish testing facilities, do not permit work requiring testing until the Contractor's facilities have been inspected, Corps validated and approved by the Contracting Officer. Determine field in-place density in accordance with ASTM D 1557. When test results indicate, as determined by the Contracting Officer, that compaction is not as specified, remove the material, replace and recompact to meet specification requirements. Perform tests on recompacted areas to determine conformance with specification requirements. Appoint a registered professional civil engineer to certify inspections and test results. These certifications shall state that the tests and observations were performed by or under the direct supervision of the engineer and that the results are representative of the materials or conditions being certified by the tests. The following number of tests, if performed at the appropriate time, will be the minimum acceptable for each type operation.

3.16.1 Fill and Backfill Material Gradation

One test per 75 cubic yards stockpiled or in-place source material. Determine gradation of fill and backfill material in accordance with ASTM C 136.

3.16.2 In-Place Densities

- a. One test per 2,000 square feet, or fraction thereof, of each lift of fill or backfill areas compacted by other than hand-operated machines.

- b. One test per 2,000 square feet, or fraction thereof, of each lift of fill or backfill areas compacted by hand-operated machines.

3.16.3 Check Tests on In-Place Densities

If ASTM D 6938 is used, check in-place densities by ASTM D 1556 as follows:

- a. One check test per lift for each 2,000 square feet, or fraction thereof, of each lift of fill or backfill compacted by other than hand-operated machines.
- b. One check test per lift for each 2,000 square feet, of fill or backfill areas compacted by hand-operated machines.

3.16.4 Moisture Contents

In the stockpile, excavation, or borrow areas, perform a minimum of two tests per day per type of material or source of material being placed during stable weather conditions. During unstable weather, perform tests as dictated by local conditions and approved by the Contracting Officer.

3.16.5 Optimum Moisture and Laboratory Maximum Density

Perform tests for each type material or source of material including borrow material to determine the optimum moisture and laboratory maximum density values. One representative test per 75 cubic yards of fill and backfill, or when any change in material occurs which may affect the optimum moisture content or laboratory maximum density.

3.16.6 Tolerance Tests for Subgrades

Perform continuous checks on the degree of finish specified in paragraph SUBGRADE PREPARATION during construction of the subgrades.

3.17 MAINTENANCE

3.17.1 Protection of Graded Areas

Newly graded areas shall be protected from traffic and erosion and shall be maintained free of trash and debris.

3.17.2 Reconditioning Compacted Areas

Where approved compacted areas are disturbed by subsequent construction operations or adverse weather, the surface shall be scarified, reshaped, and compacted as specified to the required density prior to further construction.

-- End of Section --

SECTION TABLE OF CONTENTS

DIVISION 32 - EXTERIOR IMPROVEMENTS

SECTION 32 92 23

SODDING

PART 1 GENERAL

- 1.1 REFERENCES
- 1.2 DEFINITIONS
 - 1.2.1 Stand of Turf
- 1.3 RELATED REQUIREMENTS
- 1.4 SUBMITTALS
- 1.5 DELIVERY, STORAGE, AND HANDLING
 - 1.5.1 Delivery
 - 1.5.1.1 Sod Protection
 - 1.5.1.2 Fertilizer Delivery
 - 1.5.2 Storage
 - 1.5.2.1 Sod Storage
 - 1.5.2.2 Topsoil
 - 1.5.2.3 Handling
- 1.6 TIME RESTRICTIONS AND PLANTING CONDITIONS
 - 1.6.1 Restrictions
- 1.7 TIME LIMITATIONS
 - 1.7.1 Sod

PART 2 PRODUCTS

- 2.1 SODS
 - 2.1.1 Classification
 - 2.1.2 Purity
- 2.2 TOPSOIL
- 2.3 SOIL CONDITIONERS
- 2.4 FERTILIZER
- 2.5 WATER

PART 3 EXECUTION

- 3.1 PREPARATION
 - 3.1.1 Extent of Work
 - 3.1.2 Soil Preparation
 - 3.1.2.1 Fertilizer Application Rates
- 3.2 SODDING
 - 3.2.1 Finished Grade and Topsoil
 - 3.2.2 Placing
 - 3.2.3 Sodding Slopes and Ditches
 - 3.2.4 Finishing
 - 3.2.5 Rolling
- 3.3 PROTECTION OF TURF AREAS
- 3.4 GRASS ESTABLISHMENT
 - 3.4.1 General
 - 3.4.2 Watering

- 3.4.3 Mowing
- 3.4.4 Weeding
- 3.4.5 Resodding
- 3.5 RESTORATION
- 3.6 ACCEPTANCE REQUIREMENTS
 - 3.6.1 Acceptance Requirements
 - 3.6.2 Repairs

-- End of Section Table of Contents --

SECTION 32 92 23

SODDING

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

FLORIDA DEPARTMENT OF TRANSPORTATION (FDOT)

Section 162 (2010) Prepared Soil Layer

TURFGRASS PRODUCERS INTERNATIONAL (TPI)

TPI GSS (1995) Guideline Specifications to Turfgrass Sodding

1.2 DEFINITIONS

1.2.1 Stand of Turf

100 percent ground cover of the established species.

1.3 RELATED REQUIREMENTS

Section 31 00 00 EARTHWORK applies to this section for pesticide use and plant establishment requirements, with additions and modifications herein.

1.4 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for Contractor Quality Control approval. The following shall be submitted in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-03 Product Data

Fertilizer

Include physical characteristics, and recommendations.

SD-07 Certificates

Sod farm certification for sods. Indicate type of sod in accordance with TPI GSS.

1.5 DELIVERY, STORAGE, AND HANDLING

1.5.1 Delivery

1.5.1.1 Sod Protection

Protect from drying out and from contamination during delivery, on-site storage, and handling.

1.5.1.2 Fertilizer Delivery

Deliver to the site in original, unopened containers bearing manufacturer's chemical analysis, name, trade name, trademark, and indication of conformance to state and federal laws. Instead of containers, fertilizer may be furnished in bulk with certificate indicating the above information.

1.5.2 Storage

1.5.2.1 Sod Storage

Lightly sprinkle with water, cover with moist burlap, straw, or other approved covering; and protect from exposure to wind and direct sunlight until planted. Provide covering that will allow air to circulate so that internal heat will not develop. Do not store sod longer than 24 hours. Do not store directly on concrete or bituminous surfaces.

1.5.2.2 Topsoil

Prior to stockpiling topsoil, treat growing vegetation with application of appropriate specified non-selective herbicide. Clear and grub existing vegetation three to four weeks prior to stockpiling topsoil.

1.5.2.3 Handling

Do not drop or dump materials from vehicles.

1.6 TIME RESTRICTIONS AND PLANTING CONDITIONS

1.6.1 Restrictions

Do not plant when the ground is frozen, muddy, or when air temperature exceeds 90 degrees Fahrenheit.

1.7 TIME LIMITATIONS

1.7.1 Sod

Place sod a maximum of thirty six hours after initial harvesting, in accordance with TPI GSS as modified herein.

PART 2 PRODUCTS

2.1 SODS

2.1.1 Classification

Argentine Bahia sod shall be well matted with live grass roots. Sod shall be sufficiently thick to hold together during handling operations and to obtain a satisfactory growth of grass. Sod shall be live, fresh, and

uninjured at the time of planting and it shall be the Contractor's responsibility to ensure that it contains sufficient moisture at planting to produce growth. Before the sod is harvested, the grass shall be mowed to the average height normally maintained for that variety of grass and shall have all clippings removed. Presence of weeds or other material which might be detrimental to the proposed planting will be cause for rejection of sod.

2.1.2 Purity

Sod species shall be genetically pure, free of weeds, pests, and disease.

2.2 TOPSOIL

Supply and install topsoil in accordance with FDOT Standard Section 162.

2.3 SOIL CONDITIONERS

Add conditioners to topsoil as required to bring into compliance with "composition" standard for topsoil as specified herein.

2.4 FERTILIZER

Provide commercial fertilizer of neutral character, with some elements derived from organic sources, containing not less than 8 percent phosphoric acid, 8 percent potassium, and percentage of nitrogen required to provide less than 1.0 pound of actual nitrogen per 1,000 square feet of area. Provide nitrogen in form that will be available to the seeded and sodded area during initial period of growth. The chemical designation shall be 5-10-10.

Ensure that the fertilizer is delivered to the site in labeled bags or containers.

2.5 WATER

Source of water shall be approved by Contracting Officer and of suitable quality for irrigation containing no element toxic to plant life.

PART 3 EXECUTION

3.1 PREPARATION

3.1.1 Extent of Work

Provide soil preparation (including soil conditioners), fertilizing, and sodding of all newly graded finished earth surfaces, unless indicated otherwise, and at all areas inside or outside the limits of construction that are disturbed by the Contractor's operations.

3.1.2 Soil Preparation

Provide 4 inches of off-site topsoil to meet indicated finish grade. After areas have been brought to indicated finish grade, incorporate fertilizer into soil a minimum depth of 4 inches by disking, harrowing, tilling or other method approved by the Contracting Officer. Remove debris and stones larger than 3/4 inch in any dimension remaining on the surface after finish grading. Correct irregularities in finish surfaces to eliminate depressions. Protect finished topsoil areas from damage by vehicular or

pedestrian traffic.

3.1.2.1 Fertilizer Application Rates

Apply fertilizer at rates as determined by laboratory soil analysis of the soils at the job site. For bidding purposes only apply at rates for the following:

Organic Granular Fertilizer 10 to 15 pounds per 1000 square feet.

Synthetic Granular Fertilizer 10 to 15 pounds per 1000 square feet.

3.2 SODDING

3.2.1 Finished Grade and Topsoil

Prior to the commencement of the sodding operation, the Contractor shall verify that finished grades are as indicated on drawings; the placing of topsoil, smooth grading, and compaction requirements have been completed in accordance with Section 31 00 00 EARTHWORK.

The prepared surface shall be a maximum 1 inch below the adjoining grade of any surfaced area. New surfaces shall be blended to existing areas. The prepared surface shall be completed with a light raking to remove from the surface debris and stones over a minimum 5/8 inch in any dimension.

3.2.2 Placing

Place sod a maximum of 36 hours after initial harvesting, in accordance with TPI GSS as modified herein.

3.2.3 Sodding Slopes and Ditches

For slopes 2:1 and greater, lay sod with long edge perpendicular to the contour. For V-ditches and flat bottomed ditches, lay sod with long edge perpendicular to flow of water. Anchor each piece of sod with wood pegs or wire staples maximum 2 feet on center. On slope areas, start sodding at bottom of the slope.

3.2.4 Finishing

After completing sodding, blend edges of sodded area smoothly into surrounding area. Air pockets shall be eliminated and a true and even surface shall be provided. Frayed edges shall be trimmed and holes and missing corners shall be patched with sod.

3.2.5 Rolling

Immediately after sodding, firm entire area except for slopes in excess of 3 to 1 with a roller not exceeding 90 pounds for each foot of roller width.

3.3 PROTECTION OF TURF AREAS

Immediately after turfing, protect area against traffic and other use.

3.4 GRASS ESTABLISHMENT

3.4.1 General

The period of grass establishment shall begin immediately after the completion of sodding in an area and shall continue for a period of 2 months after the completion of sodding on the entire project unless the desired grass cover is established in a shorter period of time and shortening of the grass-establishment is authorized.

3.4.2 Watering

Provide and maintain temporary piping and lawn-watering equipment required to convey water from the water source to uniformly water the grassed areas. Water shall be free from substances detrimental to the growth of vegetation. Water sources located on Government property will be subject to approval prior to use. Temporary water equipment shall be removed after grass area acceptance.

Watering schedules shall be arranged and lawn-watering equipment laid out in a manner to avoid the necessity of walking over muddy and newly grassed areas.

After the initial watering, the grassed areas shall be watered as required to maintain the soil in a moist condition for the entire grass-establishment period.

3.4.3 Mowing

When the average height of grass reaches 2-1/4 inches, seeded lawn areas shall be mowed with approved mowing equipment to a grass height of 1-1/2 inches. When the amount of cut grass is heavy, the cuttings shall be removed to prevent smothering the grass.

When the average height of grass reaches 8 inches, areas shall be mowed with approved mowing equipment to a grass height of 4 inches.

3.4.4 Weeding

Weeds or other undesirable vegetation that threaten to smother the grass shall be uprooted and removed from the area.

3.4.5 Resodding

The area on which an acceptable stand of grass is not present shall be sodded as specified for the original planting. An acceptable stand of living grass from at least 90 percent of the sod placed according to this specification. Areas on which there is not an acceptable stand of grass shall continue to be replanted throughout the following year until an acceptable stand of grass is present.

3.5 RESTORATION

Restore to original condition existing turf areas which have been damaged during turf installation operations. Keep clean at all times at least one paved pedestrian access route and one paved vehicular access route to each building. Clean other paving when work in adjacent areas is complete.

3.6 ACCEPTANCE REQUIREMENTS

3.6.1 Acceptance Requirements

Completed grass areas shall have been recently mowed and be covered with a uniform stand of the specified grass, be free of rank growths of weeds or other undesirable vegetation, and be free of irregular surface changes and other depressions where water will accumulate.

Scattered bare spots not larger than 6 inches in any dimension will be allowed, up to a maximum of 3 percent of any grass area.

Condition of grass areas at the time of inspection will be noted and a determination made whether the grass-establishment period shall be extended for any area.

3.6.2 Repairs

If, before completion and final acceptance of the facility, portions of the surface become gullied or otherwise damaged, the grass areas having been destroyed, the affected area shall be repaired to re-establish the condition and grade of the soil prior to sodding and then re-sodded, and the grass established as specified.

-- End of Section --

SECTION TABLE OF CONTENTS

DIVISION 33 - UTILITIES

SECTION 33 11 00

WATER DISTRIBUTION

PART 1 GENERAL

- 1.1 REFERENCES
- 1.2 DESIGN REQUIREMENTS
 - 1.2.1 Water Distribution Mains
 - 1.2.2 Water Service Lines
- 1.3 SUBMITTALS
- 1.4 SHOP DRAWINGS
- 1.5 DELIVERY, STORAGE, AND HANDLING
 - 1.5.1 Delivery and Storage
 - 1.5.2 Handling

PART 2 PRODUCTS

- 2.1 WATER DISTRIBUTION MAIN MATERIALS
 - 2.1.1 Piping Materials
 - 2.1.1.1 Ductile-Iron Piping
 - 2.1.1.2 Ductile-Iron Fittings
 - 2.1.1.3 Pipe Connections
 - 2.1.2 Valves and Other Water Main Accessories
 - 2.1.2.1 Gate Valves
 - 2.1.2.1.1 Type 620 - Cast-Iron Resilient Wedge Gate Valves, 2 Inches through 3 Inches, Threaded End (AWWA C509)
 - 2.1.2.1.2 Type 685 - Ductile-Iron Resilient Wedge Gate Valves, 3 Inches through 20 Inches, for Exposed and Buried Service (AWWA C515)
 - 2.1.2.2 Valve Boxes
 - 2.1.2.3 Warning Tape and Tracing Wire for Buried Piping
 - 2.1.2.4 Retainer Glands
 - 2.1.2.5 Tracer Wire for Nonmetallic Piping
 - 2.1.2.6 Polyethylene Bagging
- 2.2 WATER SERVICE LINE APPURTENANCES

PART 3 EXECUTION

- 3.1 INSTALLATION OF PIPELINES
 - 3.1.1 General Requirements for Installation of Pipelines
 - 3.1.1.1 Cutting Of Pipe
 - 3.1.1.2 Earthwork
 - 3.1.1.3 Placing, Laying And Pipe Connections
 - 3.1.1.4 Rubber Gaskets
 - 3.1.1.5 Installation of Tracer Wire
 - 3.1.1.6 Locating Devices
- 3.2 DISINFECTION CRITERIA FOR KSC POTABLE WATER SYSTEM INSTALLATION, REPAIR, OR MODIFICATION TO WATER MAINS
- 3.3 DISPOSING OF HEAVILY CHLORINATED WATER

3.4 CLEANUP

-- End of Section Table of Contents --

SECTION 33 11 00

WATER DISTRIBUTION

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN NATIONAL STANDARDS INSTITUTE (ANSI)

- | | |
|--------------|---|
| ANSI A21.11 | (2000) Rubber Gasket Joints Cast and Ductile Iron Press Pip |
| ANSI A21.53 | (2006) Ductile Iron Compact Fittings for Water Service |
| ANSI B1.20.1 | (1983; R2001) Pipe Threads, General Purpose (Inch) |

AMERICAN WATER WORKS ASSOCIATION (AWWA)

- | | |
|------------------|--|
| AWWA C104/A21.4 | (2003) Cement-Mortar Lining for Ductile-Iron Pipe and Fittings for Water |
| AWWA C105/A21.5 | (2005) Polyethylene Encasement for Ductile-Iron Pipe Systems |
| AWWA C110/A21.10 | (2008) Ductile-Iron and Gray-Iron Fittings for Water |
| AWWA C111/A21.11 | (2000) Rubber-Gasket Joints for Ductile-Iron Pressure Pipe and Fittings |
| AWWA C115/A21.15 | (2005) Flanged Ductile-Iron Pipe With Ductile-Iron or Gray-Iron Threaded Flanges |
| AWWA C150 | (2002) Thickness Design of Ductile-Iron Pipe |
| AWWA C151/A21.51 | (2002; Errata 2002) Ductile-Iron Pipe, Centrifugally Cast, for Water |
| AWWA C509 | (2001) Resilient-Seated Gate Valves for Water Supply Service |
| AWWA C515 | (2009) Reduced-Wall, Resilient-Seated Gate Valves for Water Supply Service |
| AWWA C651 | (2005; Errata 2005) Standard for Disinfecting Water Mains |

ASME INTERNATIONAL (ASME)

ASME B18.2.1	(1996; Addenda A 1999; Errata 2003; R 2005) Square and Hex Bolts and Screws (Inch Series)
ASME B18.21.1	(1999; R 2005) Lock Washers (Inch Series)
ASME B18.22.1	(1965; R 2008) Plain Washers
ASME B18.6.1	(1981; R 2008) Wood Screws (Inch Series)
ASME B18.6.3	(2003; R 2008) Machine Screws and Machine Screw Nuts

ASTM INTERNATIONAL (ASTM)

ASTM A 153/A 153M	(2009) Standard Specification for Zinc Coating (Hot-Dip) on Iron and Steel Hardware
ASTM A 27/A 27M	(2008) Standard Specification for Steel Castings, Carbon, for General Application
ASTM A 307	(2007b) Standard Specification for Carbon Steel Bolts and Studs, 60 000 PSI Tensile Strength
ASTM A 325	(2009) Standard Specification for Structural Bolts, Steel, Heat Treated, 120/105 ksi Minimum Tensile Strength
ASTM A 47/A 47M	(1999; R 2009) Standard Specification for Steel Sheet, Aluminum-Coated, by the Hot-Dip Process
ASTM A 489	(2004e1) Standard Specification for Carbon Steel Lifting Eyes
ASTM A 536	(1984; R 2009) Standard Specification for Ductile Iron Castings
ASTM A 563	(2007a) Standard Specification for Carbon and Alloy Steel Nuts
ASTM B 584	(2000) Standard Specification for Copper Alloy Sand Castings for General Applications
ASTM B 62	(2002) Standard Specification for Composition Bronze or Ounce Metal Castings
ASTM B 633	(2007) Standard Specification for Electrodeposited Coatings of Zinc on Iron and Steel
ASTM D 1238	(2004c) Melt Flow Rates of Thermoplastics by Extrusion Plastometer

ASTM E 488	(1996; R 2003) Standard Test Methods for Strength of Anchors in Concrete and Masonry Elements
ASTM F 1554	(2007a) Standard Specification for Anchor Bolts, Steel, 36, 55, and 105-ksi Yield Strength
ASTM F 436	(2009) Hardened Steel Washers
ASTM F 593	(2002; R 2008) Stainless Steel Bolts, Hex Cap Screws, and Studs
ASTM F 594	(2008) Standard Specification for Stainless Steel Nuts
ASTM F 879	(2008) Standard Specification for Stainless Steel Socket Button and Flat Countersunk Head Cap Screws

FLORIDA DEPARTMENT OF ENVIRONMENTAL PROTECTION (FDEP)

FAC 62-555.335	(2003) Guidance Documents for Public Water Systems
FAC 62-555.340	(2003) Disinfection and Bacteriological Evaluation of Public Water System Components

JOHN F. KENNEDY SPACE CENTER (KSC)

KNPR 8500.1	(2007) KSC Environmental Requirements
-------------	---------------------------------------

NSF INTERNATIONAL (NSF)

NSF 14	(2003) Plastics Piping System Components and Related Materials
NSF 61	(2009) Drinking Water System Components - Health Effects

1.2 DESIGN REQUIREMENTS

1.2.1 Water Distribution Mains

Provide water main accessories and gate valves as specified and where indicated.

Provide water distribution piping indicated as 10 through 16 inch diameter pipe sizes of ductile-iron pipe. Also provide water main accessories and gate valves as specified and where indicated.

1.2.2 Water Service Lines

Provide water service accessories as specified and where indicated.

1.3 SUBMITTALS

Government approval is required for submittals with a "G" designation;

submittals not having a "G" designation are for Contractor Quality Control approval. The following shall be submitted in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

The following drawing types shall be submitted in accordance with paragraph entitled, "Shop Drawings," of this section.

As-Built Drawings; G

SD-03 Product Data

Manufacturer's instructions and catalog data shall be submitted for the following items:

Rubber Gaskets; G
Ductile-Iron Fittings; G
Valves; G
Appurtenances; G
Valve Boxes; G

1.4 SHOP DRAWINGS

As-built drawings are required for all systems and will be prepared by a surveyor registered in the State of Florida. As-built drawing shall contain the following information:

Location of valves and fittings.

Material used.

1.5 DELIVERY, STORAGE, AND HANDLING

1.5.1 Delivery and Storage

Inspect materials delivered to site for damage. Unload and store with minimum handling. Store materials on site in enclosures or under protective covering. Store jointing materials and rubber gaskets under cover out of direct sunlight. Do not exceed the manufacturer's recommended stacking height during storage. Do not store materials directly on the ground. Keep inside of fittings and valves free of dirt and debris.

1.5.2 Handling

Accessories shall be handled so as to ensure delivery to the trench in an undamaged condition. Particular care shall be taken not to injure the pipe coating. When the coating or lining of any pipe or fitting is damaged, the Contractor shall repair at his expense in an approved manner. Before installation, the pipe shall be inspected for defects. Material found to be defective shall be replaced with sound material without additional cost to the Government. Rubber Gaskets that are not to be installed immediately shall be stored in a cool dark place out of the direct rays of the sun.

PART 2 PRODUCTS

Newly installed or constructed Public Water System (PWS) components that come into contact with drinking water or drinking water treatment chemicals shall conform to NSF 61 or Section 6 of NSF 14.

Any pipe and pipe fitting used in the construction, alteration, or repair of any PWS shall be lead free (contain not more than 8% lead). Any plumbing fitting or fixture that is intended to dispense water for human consumption and that is used in the construction, alteration or repair of any PWS shall be lead free (in compliance with Section 9 of NSF 61 as adopted in FAC 62-555.335).

All water main pipes, including fittings, shall be color coded or marked using blue as a predominant color to differentiate drinking water from reclaimed or other water. Underground metal pipe shall have blue stripes applied to the pipe wall. Pipe striped during manufacturing of the pipe shall have continuous stripes that run parallel to the axis of the pipe, that are located at no greater than 90-degree intervals around the pipe, and that will remain intact during and after installation of the pipe. If tape or paint is used to stripe pipe during installation of the pipe, the tape or paint shall be applied in a continuous line that runs parallel to the axis of the pipe and that is located along the top of the pipe; for pipes with an internal diameter of 24 inches or greater, tape or paint shall be applied in continuous lines along each side of the pipe as well as along the top of the pipe.

2.1 WATER DISTRIBUTION MAIN MATERIALS

2.1.1 Piping Materials

All materials in contact with potable water shall be NSF 61 approved and shall be suitable for use with chloraminated water.

2.1.1.1 Ductile-Iron Piping

Ductile iron pipe shall be manufactured in accordance with AWWA C150 and AWWA C151/A21.51 with push-on joints.

All non-flanged pipe shall be minimum Pressure Class 250.

Unless otherwise noted on the drawings, all ductile iron pipe exposed above grade shall be flanged ductile iron pipe in accordance with AWWA C115/A21.15, minimum thickness Class 53 with Class 125 flanges. Flanges shall be ductile iron.

All ductile iron pipe and ductile iron fittings shall be cement lined in accordance with AWWA C104/A21.4.

All buried pipe and fittings shall be petroleum asphalt coated according to the manufacturer's recommendations and encased in 8-mil high-density polyethylene tubes in accordance with AWWA C105/A21.5 Method A. All flanged and above grade or exposed pipe and fittings shall be painted in accordance with the manufacturer's recommendations.

Unless noted otherwise on the drawings, exposed fittings shall be flanged, ductile iron in accordance with AWWA C110/A21.10, rated for 250-psi operating pressure. Where new flanged pipe is to be joined with existing and other new flanges, adaptor flange pipe sections shall be provided if necessary.

All bolts, nuts, and studs shall be corrosion-resistant alloy with hex heads or heavy hex heads conforming to AWWA C115/A21.15 and Appendix A of AWWA C115/A21.15, except where otherwise indicated on the drawings.

Flange gaskets shall conform to the requirements of AWWA C111/A21.11, shall be 1/8-inch thick full-face-type and shall conform to the dimensions of Appendix A of AWWA C115/A21.15. Gaskets shall be suitable for the service conditions and shall be provided by the pipe manufacturer.

2.1.1.2 Ductile-Iron Fittings

Ductile-iron fittings shall be manufactured in accordance with AWWA C150 and AWWA C151/A21.51 with push-on joints.

All non-flanged fittings shall be minimum Pressure Class 250.

All ductile iron fittings shall be cement lined in accordance with AWWA C104/A21.4.

All buried fittings shall be petroleum asphalt coated according to the manufacturer's recommendations and encased in 8-mil high-density polyethylene tubes in accordance with AWWA C105/A21.5 Method A.

Unless noted otherwise on the drawings, exposed fittings shall be flanged, ductile iron in accordance with AWWA C110/A21.10, rated for 250-psi operating pressure.

All bolts, nuts, and studs shall be corrosion-resistant alloy with hex heads or heavy hex heads conforming to AWWA C115/A21.15 and Appendix A of AWWA C115/A21.15, except where otherwise indicated on the drawings.

Flange gaskets shall conform to the requirements of AWWA C111/A21.11, shall be 1/8-inch thick full-face-type and shall conform to the dimensions of Appendix A of AWWA C115/A21.15. Gaskets shall be suitable for the service conditions and shall be provided by the pipe manufacturer.

All water main fittings shall be color coded or marked using blue as a predominant color to differentiate drinking water from reclaimed or other water.

2.1.1.3 Pipe Connections

Provide fasteners in accordance with the following section unless otherwise noted.

1. General: For all exterior applications and where fastening aluminum, provide Type 304 stainless-steel fasteners. Provide hot-dipped galvanized fasteners in all other applications in accordance with ASTM A 153/A 153M unless noted otherwise on the drawings. Select fasteners for type, grade, and class required.
2. High-Strength Bolts and Nuts: ASTM A 325 with heavy hex nuts ASTM A 563 and hardened carbon-steel washers ASTM F 436.
3. Steel Bolts and Nuts: Regular hexagon-head bolts, ASTM A 307, Grade A, with hex nuts, ASTM A 563, and, where indicated, flat washers.
4. Stainless-Steel Bolts and Nuts: Regular hexagon-head annealed stainless-steel bolts, nuts, and flat washers; ASTM F 593 for bolts and ASTM F 594 for nuts, Alloy Group A4.
5. Stainless Steel Socket Button and Flat Countersunk Head Cap

Screws: ASTM F 879.

6. Anchor Bolts: ASTM F 1554, Grade 36.

7. Eyebolts: ASTM A 489.

8. Machine Screws: ASME B18.6.3.

9. Lag Bolts: ASME B18.2.1.

10. Wood Screws: Flat head, ASME B18.6.1.

11. Plain Washers: Round, ASME B18.22.1.

12. Lock Washers: Helical, spring type, ASME B18.21.1.

13. Cast-in Place Anchors in Concrete: Anchors capable of sustaining, without failure, a load equal to four times the load imposed, as determined by testing conducted by a qualified independent testing agency according to ASTM E 488.

a. Threaded or wedge type; galvanized ferrous castings, either ASTM A 47/A 47M malleable iron or ASTM A 27/A 27M cast steel. Provide bolts, washers, and shims as needed, hot-dip galvanized in accordance with ASTM A 153/A 153M.

14. Expansion Anchors: Anchor bolt and sleeve assembly with the ability to sustain, without failure, a load equal to six times the load imposed when installed in unit masonry and four times the load imposed when installed in concrete, as determined by testing conducted by a qualified independent testing agency according to ASTM E 488.

a. Material for Anchors in Interior Locations: Carbon-steel components zinc-plated to comply with ASTM B 633, Class Fe/Zn 5.

b. Material for Anchors in Exterior Locations: Alloy Group (A4) stainless-steel bolts complying with ASTM F 593 and nuts complying with ASTM F 594.

2.1.2 Valves and Other Water Main Accessories

2.1.2.1 Gate Valves

2.1.2.1.1 Type 620 - Cast-Iron Resilient Wedge Gate Valves, 2 Inches through 3 Inches, Threaded End (AWWA C509)

Ensure that valves 2 inches through 3 inches are of cast-iron or ductile-iron body construction and conform to AWWA C509 for resilient seated gate valves. Ensure that the valve design incorporates non-rising stems and triple "O" ring seal staff box. Ensure that the valves open counterclockwise. Ensure that the valve wedge is symmetrical and fully encapsulated with molded rubber with no exposed iron. Design valves for bubbletight shutoff to flow in either direction. Before shipment the valve manufacturer shall test each valve to 200-psi pressure differential in both directions and provide a certificate to the Contracting Officer stating each valve provided bubbletight shutoff during testing. Ensure that the valve interior and exterior is epoxy fusion coated.

Ensure the ends are threaded ends complying with ANSI B1.20.1.

Gate valves shall be manufactured by Mueller, American Flow Control or Kennedy.

2.1.2.1.2 Type 685 - Ductile-Iron Resilient Wedge Gate Valves, 3 Inches through 20 Inches, for Exposed and Buried Service (AWWA C515)

Ensure that valves are cast-iron or ductile-iron body valves and comply with AWWA C515 and the following. Ensure that valves are of the bolted-bonnet type with nonrising stems. Ensure that the valve gate is of ductile-iron with a resilient wedge. Ensure that valve stems are Type 304 or 316 stainless-steel or cast, forged, or rolled bronze. Ensure that stem nuts are made of solid bronze. Ensure that bronze conforms to ASTM B 62 or ASTM B 584. Ensure that body bolts are Type 316 stainless-steel. Ensure that end connections for exposed valves are flanged. Ensure that end connections for buried valves are mechanical joint type. Provide reduction-thrust bearings above the stem collar. Ensure that stuffing boxes are O-ring seal type with two rings located in the stem above the thrust collar. Ensure that each valve has a smooth unobstructed waterway free from any sediment pockets. Ensure that valves are lined and coated at the place of manufacture with either fusion-bonded epoxy or heat-cured liquid epoxy. Ensure that minimum epoxy thickness is 8 mil.

Manufacturers: Clow, AVK, American Flow Control, Kennedy, or approved equal.

2.1.2.2 Valve Boxes

Valve boxes shall be cast iron, complete with lock-type covers requiring a special wrench for removal. Cast-iron boxes shall be the extension type with screw or slide adjustments and with flared bases. Concrete boxes shall be constructed in accordance with details indicated. The word "WATER" shall be cast in the cover. Boxes shall be installed over each gate valve. Boxes shall be of such a length as can be adapted, without full extension, to the depth of cover required over the pipe at the valve location. Concrete boxes may be installed only in locations not subjected to traffic.

2.1.2.3 Warning Tape and Tracing Wire for Buried Piping

Warning tape and tracing wire for buried pipe is specified under Section 31 00 00 EARTHWORK.

2.1.2.4 Retainer Glands

Provide retainer glands for all buried ductile-iron mechanical joints, fitting, and ductile-iron pipe connections to buried valves. Design retainer glands for joint retaining through the use of a follower gland and set screw-anchoring devices which impart multiple wedging action against the pipe. The mechanical joint restraint device shall be UL listed and shall have a working pressure of at least 250 psi with a minimum safety factor of 2.

1. Gland: Manufactured of ductile iron conforming to ASTM A 536. Gland dimensions shall match ANSI A21.11 and ANSI A21.53.

2. Restraining Devices: Manufactured of ductile iron heat treated to a minimum hardness of 370 BHN. Incorporate a set screw/twist-off nut bolt into restraining devices to ensure the proper actuating of the restraining device. Design the twist-off nut to come off at the torque limit desired to anchor the restraining device in place on the pipe.

3. Joint Deflection: Limit retainer gland joint deflection to manufacturer's recommended maximum deflection angle. Apply joint deflection before the set screws are torqued.

4. Acceptable manufacturers:

a. EBAA Iron, Inc.; Megalug 1100 Series or approved equal.

2.1.2.5 Tracer Wire for Nonmetallic Piping

Tracer wire for nonmetallic piping is specified under Section 31 00 00 EARTHWORK.

2.1.2.6 Polyethylene Bagging

Polyethylene bagging for buried ductile iron pipe, fittings, and valves shall be 8 mils thickness minimum polyethylene, manufactured in accordance with ASTM D 1238, Type I, Class C, Grade E1.

2.2 WATER SERVICE LINE APPURTENANCES

Verify existing water service line material and provide appropriate cap.

PART 3 EXECUTION

3.1 INSTALLATION OF PIPELINES

3.1.1 General Requirements for Installation of Pipelines

3.1.1.1 Cutting Of Pipe

Cutting of pipe shall be done without damage to the pipe. Cutting shall be done with an approved mechanical cutter. Wheel cutters shall be used when practical.

3.1.1.2 Earthwork

Perform earthwork operations in accordance with Section 31 00 00 EARTHWORK.

3.1.1.3 Placing, Laying And Pipe Connections

Accessories shall be carefully lowered into the trench by suitable equipment. Under no circumstances shall materials be dropped or dumped into the trench. Care shall be taken to avoid abrasion of the pipe coating. When work is not in progress, open ends of pipe, fittings, and valves shall be securely closed so that foreign material will not enter the pipes or fittings. Where any part of the coating or lining is damaged, the repair shall be made by the Contractor in an approved manner, at no additional expense to the Government.

Pipe ends left for future connections shall be valved, plugged, or capped and anchored.

3.1.1.4 Rubber Gaskets

Rubber gaskets shall be handled, lubricated, and installed in accordance with the pipe manufacturer's recommendations.

3.1.1.5 Installation of Tracer Wire

Where nonmetallic pipe is used, install a single conductor #6 gauge thick wire with Type TW insulation above the pipe to facilitate pipe location.

3.1.1.6 Locating Devices

For all subsurface elbows, tees, and valves, embed the device into the top surface on the thrust block such that half the device is exposed and the location is at the centroid of the thrust block top surface area. The locating devices shall be Omni Marker Model 161 Water Marker or approved equal.

3.2 DISINFECTION CRITERIA FOR KSC POTABLE WATER SYSTEM INSTALLATION, REPAIR, OR MODIFICATION TO WATER MAINS

The KSC Pollution Control and Sanitation Officer (PCSO) or designated representative shall approve the disinfection procedure to be used and be present during the process. A minimum of 24 hours lead time is required to schedule attendance of disinfection by PCSO or representative. Contact should be made through the Construction Management Office. Ensure proper disinfection protocol/bacteriological sampling occurs if water line is broken, tapped, modified, or if loss of pressure occurs. All repaired, modified or newly installed water system components shall be disinfected after pressure and leak tests have been performed. All existing mains closed for outage shall be disinfected and tested prior to use. The system components to be disinfected shall be thoroughly flushed with potable water before introducing the chlorinating solution. This flushing is required to remove all debris from the systems components. The chlorinating solution shall provide a dosage of not less than 50 parts per million (ppm). The chlorine solution shall be introduced into the water line in an approved manner and be evenly distributed throughout the entire effected systems components long enough to destroy all non-spore forming bacteria. Except where a shorter period is approved, the retention time shall be at least 24 hours and tests shall reveal not less than 25 ppm of chlorine residual after the 24 hour retention period. The line shall be flushed with potable water until the residual chlorine level is reduced to less than 1.0 ppm or to the normal background level in the area. Discharge of highly chlorinated water from disinfection shall be coordinated with EG&G Water and Wastewater. Samples will be collected by the Contractor or designated representative from several points in the water system for bacteriological examination. The system will remain closed and will not be accepted for use until two consecutive days of satisfactory bacteriological results have been obtained and approval has been given by the PCSO and regulatory agencies.

Taps, modification, repairs, or new lines added to the system shall be tested and disinfected following AWWA C651 and KNPR 8500.1. Successful disinfection shall be demonstrated by bacteriological testing following FAC 62-555.340(1) and FAC 62-555.340(2).

3.3 DISPOSING OF HEAVILY CHLORINATED WATER

The environment to which chlorinated water may be discharged shall be inspected by the Contractor, and, if there is any question that the chlorinated discharge will cause damage to personnel or the environment, then a reducing agent shall be applied to the water (reference Appendix B of the current AWWA C651 for neutralizing chemicals). Such discharges should be coordinated with the KSC PCSO, or designated representative.

3.4 CLEANUP

Upon completion of the installation of water lines, and appurtenances, all debris and surplus materials resulting from the work shall be removed.

-- End of Section --