

- D. The Contractor shall provide at his expense all the necessary labor, equipment, and material.

3.17 CONSERVATION

- A. All energy consumption and resources shall be conserved to the greatest extent possible by the Contractor. The Contractor is responsible for communicating this requirement to all on-site personnel and for compliance. Energy and resource utilization shall be proactively managed and conservation measures and methods developed and promoted by the Contractor's management and supervision.
- B. Temporary lighting shall be divided into switchable areas of relatively small size to promote and achieve energy conservation to the satisfaction of the Government. Lighting shall be off unless absolutely necessary to accomplish the work at hand. Lighting for security purposes only shall be minimized and other non-energy consuming methods employed to the greatest extent.
- C. Recyclable materials (e.g. aluminum cans, white paper, cardboard, metals, etc.) shall be diverted from the waste stream and delivered to the appropriate off-site, off-Center recycle center by the Contractor as indicated. For Leadership in Energy and Environmental Design (LEED) projects, see other specification sections for more stringent requirements.
- D. All cardboard materials shall be flattened, consolidated, and recycled. Cardboard may be delivered to the Center's cardboard recycling location.

3.18 ~~JOBSITE TRAILER (FOR GOVERNMENT)~~

This paragraph is not applicable to solicitation #NNM13ZPS004E.

- ~~A. Contractor shall provide an approximately 500 square foot trailer at the jobsite for use solely by the Government and government representatives. Contractor shall provide the original and four copies of the keys to the trailer; no one else shall have a key to this trailer. Trailer shall be heated and cooled and custodial services shall be provided at least once per week. Trailer is to be located adjacent to the superintendent's trailer. A refrigerator with at least 14 cubic feet and -potable water shall be provided for sole use by the Government. Trailer shall be divided into four (4) rooms: an office at each end, a restroom equipped with sanitary sewer services including running water, and a common area in the middle for drawings, files, and small meetings. Submit layout drawing for COTR's review and approval.~~

3.19 FEDERAL AVIATION ADMINISTRATION (FAA) REQUIREMENTS

- A. The Contractor shall comply with all applicable FAA regulations, particularly FAA AC 70/7460-1.
- B. The Contractor shall provide all notices to the COTR in writing in order for the Government to assist the Contractor in meeting the applicable FAA regulations. The FAA requires multiple notifications and submission of forms then approval for any work including cranes above the ground over a certain height from ground level at the construction site (height limit). The Contractor shall know the current regulations and provide the notifications to meet these regulations using the 100 to 1 slope from the Redstone Army Airfield. The Contractor shall determine the requirements and any potential project impacts (both schedule and cost) prior to