

WALLOPS NORTH ISLAND ELECTRICAL UPGRADE, IFB NNG14517542R

INDUSTRY QUESTIONS

96. RFI answer #89 states that “The slack length for V-62 is clearly indicated on the provided Attachment K, “NORTH ISLAND HANDHOLE AND SPLICES”.” But there is no distances given on any of the documents.

NASA RESPONSE: The Contractor should leave 400’ of slack fiber optic cable in the handhole for V-62. V-62 is located on the road shoulder approximately 200’ southwest of the V-65 (Coast Guard Station) intersection.

97. NASA clarification to Question 62, regarding MEC training and associated cost: MEC refers to Munitions and Explosives of Concern, or unexploded ordnance. The successful offeror will be briefed by the construction manager and/or environmental office prior to beginning construction on what to do if unexploded ordnance is discovered.